




SPECIFICATIONS The following Tree Preservation and Protection Measures will be 6. Where fill or excavated material must be temporarily located near a undertaken to help eliminate and/or significantly reduce construction TPZ, a wooden barrier must be used to ensure no material enters the injury to all trees recommended for preservation. All temporary tree protection measures cited for retained trees must comply with the 7. Remove any garbage and foreign debris from the tree protection Town of Caledon Tree Protection Specifications and Details. Any zones, daily. 8. For the trees that were recommended for removal and/or crown variation from the standard tree protection measures must be pruning that are within the TPZ limits, these activities are to be approved in writing by the Town of Caledon. performed by a qualified ISA certified arborist prior to the installation of the Tree Protection Zone barriers and prior to the commencement B. Pre-Construction Phase of any construction activities. Install the Tree Protection Zone barrier 1. Prior to construction, the trees to be preserved shall be protected with as per Tree Preservation Fencing, STD 606 at the limits shown on the a Tree Protection Barrier. The barrier shall consist of 1.2m (4ft) high tree inventory and protection plan after the tree removal, whichever is orange plastic snow fence wired to T-bars (see Town of Caledon Tree greater, and crown pruning activities are completed. 9. A Tree Protection Zone sign must be mounted on all sides of the Preservation Fencing, STD 606). 2. If applicable, attach a filter cloth 600mm high to the construction side tree protection barrier for the duration of site construction. The sign should be a minimum of 40cm x 60cm and made of white gator board of the hoarding to act as sediment control. Sediment control fencing shall meet or exceed OPSD-219.110, and be installed to the or equivalent material. satisfaction of the Town of Caledon. 10. The sign must be similar to the illustration shown below, or as directed 3. All supports and bracing used to safely secure the barrier should be by the Town of Caledon. located outside the Tree Protection Zone (TPZ). All supports and bracing should minimize damage to roots. TREE PROTECTION ZONE 4. The TPZ fence is to be installed along the edge of the tree protection No work is permitted in the Tree Protection Zone zones. This hoarding is to remain in place and remain in good This includes construction works, grading, storage of trash or materials. condition throughout the entire duration of the project. Dismantling the The tree protection barrier must not be removed without written tree protection barrier prior to approval by the Town of Caledon staff authorization of the Town of Caledon. may constitute a contravention. 5. The applicant shall notify the Town of Caledon and the consulting 11. All contractors and site visitors should be informed of the tree certified arborist or landscape architect to confirm that the tree preservation and protection measures at a pre-construction meeting. protection barriers are in place. specifications continued on next panel... TOWN OF CALEDON ATE: AUGUST 17 PR'D: B.B. SCALE: NTS RAWN: B.M. TREE PRESERVATION STANDARD NOTES - PART 1 STANDARD No. 710 APR'D DATE REVISION





NOT FOR CONSTRUCTION

SEAL



IBI GROUP Suite 200 - 360 James Street North Hamilton ON L8L 1H5 Canada tel 905 546 1010 fax 905 546 1011 ibigroup.com

12304 HEART LAKE ROAD

CALEDON, ON. L7C 2J2

ROJECT MGR:	APPROVED BY:
A	TO
RAWN BY:	CHECKED BY:
K	TO
ROJECT NO: 35636	

SHEET TITLE

TREE PROTECTION DETAILS

SHEET NUMBER

TPD-1

ISSUE