
# HUMBER STATION DISTRIBUTION CENTRE TOWN OF CALEDON

# DETAILED CHANNEL REALIGNMENT AND WETLAND RELOCATION DESIGN

SLR PROJECT NO.: 2008102







KEY MAP SCALE = 1 : 10,000

AERIAL IMAGERY RETRIEVED FROM GOOGLE EARTH

# LIST OF DRAWINGS

SHEET NO.	DESCRIPTION	DRAWING NO.	DATE
00	COVER SHEET		2025/08/12
01	CONSTRUCTION NOTES (TYPICAL)	N-1	2025/08/12
02	SITE LAYOUT PLAN	SL-1	2025/08/12
03	PLAN AND PROFILE - RELOCATED WETLAND AREA A	PP-1	2025/08/12
04	PLAN AND PROFILE - REACH 3, SECTION 1	PP-2	2025/08/12
05	PLAN AND PROFILE - REACH 3, SECTION 2	PP-3	2025/08/12
06	PLAN AND PROFILE - REACH 3, SECTION 3	PP-4	2025/08/12
07	DESIGN WETLAND CROSS SECTIONS	XS-1	2025/08/12
08	DESIGN CHANNEL CROSS SECTIONS	XS-2	2025/08/12
09	CONSTRUCTION DETAILS	CD	2025/08/12

# NOT FOR CONSTRUCTION







### BACKGROUND INFORMATION NOTES

- 1. BACKGROUND INFORMATION AND EXISTING CONDITIONS PROVIDED BY CROZIER CONSULTING ENGINEERS ON JANUARY 28, 2025.
- 2. SURVEY INFORMATION PROVIDED BY CROZIER CONSULTING ENGINEERS ON JANUARY 28, 2025. HORIZONTAL DATUM CONTROL IS IN NAD 83 (CSRS) / UTM ZONE 17N.
- 3. AERIAL IMAGERY RETRIEVED FROM GOOGLE EARTH IMAGING ON FEBRUARY 4, 2025.
- 4. CONTOUR INTERVAL IS 0.25-1.00 METERS (SEE INDIVIDUAL SHEET NOTES)

### **GENERAL NOTES**

- 1. THE NOTES ON THESE DRAWINGS APPLY TO ALL WORKS UNDER THIS CONTRACT UNLESS OTHERWISE INDICATED ON THESE SETS OF PLANS.
- 2. THE STANDARD DRAWINGS OF THE TOWN OF CALEDON, REGION OF PEEL, THE TORONTO AND REGION CONSERVATION AUTHORITY AND THE ONTARIO MINISTRY OF TRANSPORTATION CONSTITUTE PART OF THIS SET OF PLANS AND SHALL BE THE REVISION IN EFFECT AS OF THE DATE OF APPROVAL OF THE CONSTRUCTION DRAWINGS.
- 3. ALL CONSTRUCTION WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE "OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS".
- 4. THE CONTRACTORS ATTENTION IS DRAWN TO THE LIMITS OF THE WORK AREA. CONSTRUCTION ACTIVITY SHALL BE CONFINED TO PUBLIC PROPERTY AND/OR EXISTING EASEMENTS UNLESS OTHERWISE DIRECTED OR DETAILED IN THE CONTRACT DOCUMENTS.
- 5. INFORMATION REGARDING ANY EXISTING SERVICES AND/OR UTILITIES SHOWN ON THIS SET OF PLANS IS FURNISHED AS THE BEST AVAILABLE INFORMATION AT THE TIME OF PREPARATION. THE CONTRACTOR SHALL INTERPRET THIS INFORMATION AS HE/SHE SEES FIT WITH THE UNDERSTANDING THAT THE OWNER, THE CITY AND ENGINEER DISCLAIM ALL RESPONSIBILITY FOR ITS ACCURACY
- 6. THE CONTRACTOR SHALL NOTE THAT THERE MAY BE OVERHEAD AND UNDERGROUND UTILITIES WHICH ARE NOT SHOWN ON THESE DRAWINGS. SOME, OR ALL OF THESE UTILITIES MAY REQUIRE SHIELDING OR OTHER APPROPRIATE FORM OF PROTECTION AS SPECIFIED BY THE RESPECTIVE UTILITY COMPANIES, OR ANY OTHER APPLICABLE LEGISLATION IN FORCE. CONTRACTORS SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH THE NUMBER OF LOCATIONS OF THE OVERHEAD UTILITY CABLES. ANY UTILITY DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE UTILITY COMPANY AT THE CONTRACTOR'S EXPENSE. THE COST OF THE SHIELDING WHERE REQUIRED SHALL BE DEEMED TO BE INCLUDED IN THE UNIT PRICES BID, WITH NO ADDITIONAL PAYMENT TO BE MADE THE CONTRACTOR.
- 7. ALL DIMENSIONS AND ELEVATIONS SHALL BE CHECKED AND VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION AND HE/SHE REPORT ANY DISCREPANCIES TO THE CITY IMMEDIATELY. DETAILS ARE NOT TO BE SCALED FROM THE DRAWINGS. ALL DIMENSIONS ARE SHOWN IN METRES UNLESS OTHERWISE NOTED.
- 8. CLEARING OF ANY EXISTING VEGETATION OTHER THAN THAT DETAILED ON THE CONTRACT DRAWINGS, SHALL NOT BE UNDERTAKEN WITHOUT SPECIFIC WRITTEN DIRECTION BY THE CONTRACT ADMINISTRATOR. VERTICAL TRENCHING, HAND TRENCHING, AUGERING AND IMMEDIATE BACKFILLING OF ANY TRENCH SHALL BE UNDERTAKEN BY THE CONTRACTOR AS NECESSARY TO ENSURE THAT ALL REASONABLE PRECAUTIONS ARE TAKEN TO PROMOTE THE SURVIVAL OF ANY EXISTING VEGETATION. ALL AREAS DISTURBED BY THE CONTRACTOR DURING CONSTRUCTION OF THE WORKS SHOWN HEREIN SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER. ALL GRASS AND VEGETATION COVERED AREAS SHALL BE RESTORED BY PLACING 100MM OF APPROVED TOPSOIL AND SOD TO ESTABLISH A GRASS COVER, UNLESS OTHERWISE NOTED ON THE PLANS, TO THE SATISFACTION OF THE TOWN OF CALEDON.
- 9. VEHICULAR TRAFFIC AND ACCESS TO ALL DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES DURING THE WORK. SHOULD ACCESS TO ANY DRIVEWAYS BE TEMPORARILY CUT-OFF. THE CONTRACTOR SHALL NOTIFY THE RESIDENT OR BUSINESS OWNERS A MINIMUM OF 48 HOURS IN ADVANCE AND ENSURE THAT THE DRIVEWAY OWNERS A MINIMUM OF 48 HOURS IN ADVANCE AND ENSURE THAT THE DRIVEWAY A MINIMUM OF 48 HOURS IN ADVANCE AND ENSURE THAT THE DRIVEWAY 48 HOURS IN ADVANCE AND ENSURE THAT THE DRIVEWAY ACCESS IS RESTORED AS QUICKLY AS POSSIBLE THE CONTRACTOR SHALL PREPARE A TRAFFIC CONTROL PLAN FOR REVIEW AND APPROVAL BY THE CITY PRIOR TO START OF CONSTRUCTION.
- 10. APPROVED FILL MATERIAL SHALL BE COMPACTED TO A DRY DENSITY AS PER THE SPECIFICATIONS. COMPACTION TESTING SHALL BE CONDUCTED BY A QUALIFIED SOIL ENGINEER TO ENSURE COMPACTION AND STABILITY OF THE FILL AND TEST RESULTS SHALL BE SUBMITTED TO THE TOWN OF CALEDON, THE CONTRACTOR AND THE CONSULTANT. ANY APPROVED FILL MATERIAL BROUGHT ON SITE SHALL BE CERTIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER AND SHALL INCLUDE AN ENVIRONMENTAL ANALYSIS REPORT FOR METALS AND INORGANIC PARAMETERS.
- 11. ANY TEMPORARY MODIFICATIONS TO PATH CORNERS TO BE APPROVED BY THE CONTRACT ADMINISTRATOR AND TO BE RESTORED TO EXISTING CONDITIONS OR BETTER POST CONSTRUCTION.

# **EROSION AND SEDIMENT CONTROL (TRCA STANDARD) NOTES**

### **SECTION 1: SITE MANAGEMENT**

- 1. EROSION AND SEDIMENT CONTROL (ESC) MEASURES WILL BE IMPLEMENTED PRIOR TO, AND MAINTAINED DURING THE CONSTRUCTION PHASES, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER. ALL DAMAGED EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF THE INSPECTION
- 2. DISTURBED AREAS WILL BE MINIMIZED TO THE EXTENT POSSIBLE, AND TEMPORARILY OR PERMANENTLY STABILIZED OR RESTORED AS THE WORK PROGRESSES.
- 3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY WITH APPROPRIATE EROSION AND SEDIMENT CONTROLS.
- 4. THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO MINIMIZE SEDIMENT LADEN RUNOFF FROM LEAVING THE WORK AREAS. IF THE PRESCRIBED MEASURES ON THE PLANS ARE NOT EFFECTIVE IN PREVENTING THE RELEASE OF A DELETERIOUS SUBSTANCE. INCLUDING SEDIMENT, THEN ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO MINIMIZE POTENTIAL ECOLOGICAL IMPACTS. TRCA ENFORCEMENT OFFICER SHOULD BE IMMEDIATELY CONTACTED. ADDITIONAL ESC MEASURES TO BE KEPT ON SITE AND USED AS NECESSARY
- 5. AN ENVIRONMENTAL MONITOR WILL ATTEND THE SITE TO INSPECT ALL NEW CONTROLS IMMEDIATELY AFTER INSTALLATION. INSPECTION OF ESC MEASURES TO BE WILL OCCUR, AT MINIMUM: PRIOR TO SIGNIFICANT RAINFALL EVENTS (MINIMUM PREDICTED 25mm OVER 24 HOURS;
- AFTER EVERY RAINFALL / SNOWMELT EVENT; AND DAILY DURING EXTENDED RAINFALL PERIODS. INSPECTIONS WILL FOCUS ON MEASURES RELATED TO EROSION AND SEDIMENT CONTROLS, DEWATERING OR UNWATERING, RESTORATION AND IN - OR NEAR - WATER WORKS. SHOULD CONCERNS
- ARISE ON SITE THE ENVIRONMENTAL MONITOR WILL CONTACT THE TRCA ENFORCEMENT OFFICER AS WELL AS THE PROPONENT
- 6. ALL ACTIVITIES, INCLUDING MAINTENANCE PROCEDURES, WILL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELING AND MAINTENANCE WILL BE CONDUCTED A MINIMUM OF 30 METRES FROM THE WATER.
- 7. ALL GRADES WITHIN THE REGULATORY FLOOD PLAIN WILL BE MAINTAINED OR MATCHED
- 8. THE PROPONENT/CONTRACTOR SHALL MONITOR THE WEATHER SEVERAL DAYS IN ADVANCE OF THE ONSET OF THE PROJECT TO ENSURE THAT THE WORKS WILL BE CONDUCTED DURING FAVOURABLE WEATHER CONDITIONS. SHOULD AN UNEXPECTED STORM ARISE, THE CONTRACTOR WILL REMOVE ALL UNFIXED ITEMS FROM THE REGIONAL STORM FLOOD PLAIN THAT WOULD HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW, E.G., FUEL TANKS, PORTA-POTTIES, MACHINERY, EQUIPMENT, CONSTRUCTION MATERIALS, ETC
- 9. ALL DEWATERING/UNWATERING SHALL BE TREATED AND RELEASED TO THE ENVIRONMENT AT LEAST 30 METRES FROM A WATERCOURSE OR WETLAND AND ALLOWED TO DRAIN THROUGH A WELL-VEGETATED AREA. NO DEWATERING EFFLUENT SHALL BE SENT DIRECTLY TO ANY WATERCOURSE, WETLAND OR FOREST, OR ALLOWED TO DRAIN ONTO DISTURBED SOILS WITHIN THE WORK AREA. THESE CONTROL MEASURES SHALL BE MONITORED FOR EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING THE RELEASE OF SEDIMENT LADEN WATER.
- 10. ALL ACCESS TO THE WORK SITE SHALL BE FROM EITHER SIDE OF THE WATERCOURSE. NO EQUIPMENT OR VEHICLES ARE PERMITTED TO CROSS THROUGH THE WATERCOURSE UNLESS APPROVED BY
- 11. THE CONTRACTOR SHALL INSTALL SEDIMENT CONTROL FENCING, AS REQUIRED TO CONTROL THE DISCHARGE OF EXPOSED SOIL OR TEMPORARY PILE(S) OF EXCAVATED SOILS OR, SOILS AND GRANULAR MATERIAL TO BE USED DURING CONSTRUCTION. WHERE POSSIBLE BIODEGRADABLE ALTERNATIVES TO SILT FENCING SHOULD BE CONSIDERED. REUSABLE FENCE SUCH AS FAST FENCE SHOULD BE USED TO ISOLATE THE WORK AREA WHEN SEDIMENT CONTROL FENCING IS NOT REQUIRED.
- 12. EROSION AND SEDIMENT CONTROL MEASURES ARE TO REMAIN IN PLACE AND IN WORKING ORDER UNTIL ALL ON-SITE CONSTRUCTION IS COMPLETED AND VEGETATION IS RE-ESTABLISHED.
- 13. AREAS WHICH REMAIN DISTURBED FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING SEED OR APPROVED EROSION CONTROL BLANKET OR SIMILAR. IF CONDITIONS AREN'T SUITABLE FOR SEED APPLICATION AN EROSION CONTROL MATTING WILL BE USED IN ITS PLACE.
- 14. ALL SLOPES SHALL BE STABILIZED USING MEASURES SUCH AS EROSION CONTROL BLANKET AS PER OPSS 804 OR APPROVED EQUIVALENT. NO EROSION AND CONTROL MEASURE SHALL HAVE ANY PLASTIC, EVEN IF IT IS BIODEGRADABLE.
- 15. PUBLIC WALKWAYS AND MUNICIPAL ROADS ARE TO BE KEPT CLEAR OF EXCESS SEDIMENT
- 16. THE CONTRACTOR MUST HAVE SUITABLE PUMPING CAPABILITIES ON SITE AT ALL TIMES TO FACILITATE CONSTRUCTION ACTIVITIES IN THE DRY
- 17. WHERE PRACTICAL, WORKS SHOULD BE COMPLETED IN STAGES TO REDUCE THE DURATION OF SOIL EXPOSURE WITHIN DISTURBED AREAS.
- 18. CONTRACTOR IS NOT TO DISPOSE OF ANY OF THE MATERIAL USED IN THE PEA GRAVEL METRE BAGS INTO THE CHANNEL OR SURROUNDING AREA. ALL PEA GRAVEL BAGS ARE TO BE REMOVED OFF OF
- 19. TEMPORARY STAGING AREAS WILL BE SITUATED WITHIN 15 METRES OF THE WATERCOURSE DUE TO THE CONFINED NATURE OF THE PROJECT AREA. ALL MAJOR/OVERNIGHT STAGING/STOCKPILING AREAS WILL BE A MINIMUM OF 15m AWAY FROM THE WATERCOURSE. CONTRACTOR TO MONITOR WEATHER FORECASTS TO ENSURE MACHINES AND MATERIALS ARE REMOVED WHEN THE INCLEMENT WEATHER IS ANTICIPATED. STOCKPILE HEIGHTS WILL BE KEPT BELOW 1.5 METRES IN HEIGHT.
- 20. REFER TO EROSION AND SEDIMENT CONTROL GUIDE FOR URBAN CONSTRUCTION, 2019 FOR FURTHER EROSION AND SEDIMENT CONTROL MEASURES APPROVED BY THE TRCA.

# **SECTION 2: CONSTRUCTION TIMING**


- PRIOR TO SITE DISTURBANCE THE CONTRACTOR/PROPONENT SHOULD ENSURE THAT THE WORKS ARE IN CONFORMANCE WITH THE MIGRATORY BIRDS CONVENTION ACT. PLEASE NOTE THAT THE GENERAL BREEDING BIRD WINDOW FOR THIS AREA IS APRIL 1ST TO AUGUST 31ST, HOWEVER, BREEDING ACTIVITIES MIGHT INITIATE PRIOR TO AND CONTINUE PAST THIS PERIOD.
- WHERE IMPACTS TO LOCAL FISH POPULATIONS MAY OCCUR DURING THEIR SPAWNING, NURSERY AND MIGRATORY PERIODS, CONSTRUCTION TIMING WINDOWS SHOULD APPLY TO IN-WATER OR NEAR-WATER ACTIVITIES. THE PROPONENT/CONTRACTOR SHOULD CONFIRM APPLICABILITY AND DATES WITH APPROPRIATE PROVINCIAL AND FEDERAL AGENCIES. TO PROTECT LOCAL FISH POPULATIONS DURING THEIR SPAWNING, NURSERY AND MIGRATORY PERIODS, IN-WATER/NEAR-WATER ACTIVITIES MAY ONLY OCCUR DURING THE FOLLOWING TIME PERIOD OF JULY 1ST TO MARCH
- . ANY CONSTRUCTION WORK RELATED TO THE EXISTING HDF-3 FEATURE (AND BY EXTENSION ITS ASSOCIATED RIPARIAN WETLANDS), AS WELL AS THE PROPOSED WETLAND COMPENSATION AREA MAY ONLY OCCUR DURING THE FOLLOWING TIME PERIOD OF JULY 1ST TO SEPTEMBER 15TH.

# SECTION 3: FISH AND WILDLIFE RELOCATION

1. FISH AND WILDLIFE STRANDED WITHIN THE WORK AREA SHALL BE CAPTURED AND RELEASED LIVE IN SUITABLE HABITAT UPSTREAM OF THE WORK AREA UNDER THE SUPERVISION OF QUALIFIED AQUATIC TECHNICAL STAFF. THE PROPONENT/CONTRACTOR SHOULD CONFIRM REQUIREMENTS DIRECTLY WITH MINISTRY OF NATURAL RESOURCES AND FORESTRY.

# SECTION 4: ENVIRONMENTAL COMPLIANCE

- 1. PLEASE NOTIFY TRCA ENFORCEMENT OFFICER 48 HOURS PRIOR TO COMMENCING CONSTRUCTION.
- AN ENVIRONMENTAL MONITOR WILL BE ON SITE, AND PROVIDE ADVICE, TO ENSURE THAT ACTIVITIES THAT COULD HAVE A NEGATIVE IMPACT TO THE NATURAL ENVIRONMENT ARE EFFECTIVELY MITIGATED AS CONSTRUCTION PROCEEDS. THE ENVIRONMENTAL MONITOR SHALL NOTIFY THE TRCA ENFORCEMENT OFFICER AND PROJECT MANAGER IF ISSUES ARISE.




LEGEND

1	TR	МО	12/08/25	DETAILED DESIGN SUBMISSION
0	TR	МО	10/03/25	DRAFT DETAILED DESIGN
Revision	Ву	Chk'd By	dd/mm/yy Date	Comments



300 TOWN CENTRE BLVD MARKHAM ON L3R 8H8 T: 905.415.7248 F: 905.415.1019 www.slrconsulting.com





Client:

# **PROLOGIS - HUMBER STATION**


## DETAILED CHANNEL REALIGNMENT AND WETLAND RELOCATION DESIGN


Drawing Title:


# **CONSTRUCTION NOTES (TYPICAL)**


Scale: N/A		Date: MAR. 10, 2025		Drawing No.	N-1
Drawn by:	TR	Checked by:	МО	Sheet No.	
Designed by:	МО	Approved by:	RM		01
















# PROPOSED REACH 3, SECTION 3 - LONG PROFILE

SCALE: H=1:500 , V=1:50





# **LEGEND**

EXISTING CONTOUR (MINOR) EXISTING CONTOUR (MAJOR) — EXISTING SUBJECT PROPERTY BOUNDARY EXISTING ADJACENT PROPERTY BOUNDARY EXISTING NATURAL HERITAGE SYSTEM LIMIT EXISTING SIGNIFICANT WOODLAND AREA — — — — EXISTING CENTRELINE OF WATERWAY EXISTING WETLAND AREA PROPOSED WETLAND AREA REMOVAL PROPOSED CENTRELINE OF CHANNEL PROPOSED RIFFLE STONE AREA PROPOSED BED MATERIAL AREA PROPOSED BRUSH LAYERING AREA PROPOSED ONLINE/OFFLINE WETLAND AREA PROPOSED GRADING CONTOURS PROPOSED LIMIT OF GRADING PROPOSED LIMIT OF GRADING PROPOSED PHASE 1 WORKS (BY OTHERS)

### NOTES

- BACKGROUND INFORMATION AND EXISTING CONDITIONS PROVIDED BY CROZIER CONSULTING ENGINEERS ON JANUARY 28, 2025.
- SURVEY INFORMATION PROVIDED BY CROZIER CONSULTING ENGINEERS ON JANUARY 28, 2025. HORIZONTAL DATUM CONTROL IS IN NAD 83 (CSRS) / UTM ZONE 17N.
- AERIAL IMAGERY RETRIEVED FROM GOOGLE EARTH IMAGING ON FEBRUARY 4, 2025.

1	TR	МО	12/08/25	DETAILED DESIGN SUBMISSION
0	TR	МО	10/03/25	DRAFT DETAILED DESIGN
Revision	By	Chk'd By	dd/mm/yy	Comments

岩SLR

300 TOWN CENTRE BLVD MARKHAM ON L3R 8H8 T: 905.415.7248 F: 905.415.1019 www.slrconsulting.com





**PROLOGIS - HUMBER STATION** 


DETAILED CHANNEL REALIGNMENT AND WETLAND RELOCATION DESIGN

**PLAN & PROFILE REACH 3, SECTION 3 OF 3** 

Drawing No. MAR. 10, 2025 1:500 PP-4 Drawn by: TR | Checked by: MO Approved by: NOT FOR CONSTRUCTION

# PROPOSED WETLAND - SECTION 1-1

SCALE: H=1:250 , V=1:125



# RELOCATION AREA A PHASE 1 - BY OTHERS CHANNEL LOCATION EXISTING DRAINAGE FEATURE SITE LOCATION **KEY MAP**

LEGEND


EXISTING GRADE PROPOSED GRADE

> EXISTING WETLAND AREA PROPOSED IMPORTED WETLAND MATERIAL

PROPOSED SUBGRADE MATERIAL


# PROPOSED WETLAND - SECTION 2-2

SCALE: H=1:250 , V=1:125



### **DETAILED DESIGN SUBMISSION** TR MO TR DRAFT DETAILED DESIGN MO 10/03/25 Chk'd By Ву Revision Comments

300 TOWN CENTRE BLVD MARKHAM ON L3R 8H8 T: 905.415.7248 F: 905.415.1019 www.slrconsulting.com





# PROLOGIS - HUMBER STATION


DETAILED CHANNEL REALIGNMENT AND WETLAND RELOCATION DESIGN


Drawing Title:


# **DESIGN WETLAND CROSS SECTIONS**


Scale:		Date:		Drawing No.		
AS SHOWN		MAR. 10, 2025			XS-1	
Drawn by:	TR	Checked by:	MO	Sheet No.		
Designed by:	МО	Approved by:	RM		07	


# PROPOSED WETLAND - SECTION 3-3 SCALE: H=1:250 , V=1:125
















ORGANIC SOIL- 150 mm






WIDTH VARIES (REFER TO PLAN)


ONLINE WETLAND DETAIL (TYP.)


\* SEE WETLAND CHANNEL DETAIL

←WETLAND PLANTINGS


ORGANIC SOIL- 150 mm







300 TOWN CENTRE BLVD MARKHAM ON L3R 8H8 T: 905.415.7248 F: 905.415.1019 www.slrconsulting.com





Client:

# PROLOGIS - HUMBER STATION

# DETAILED CHANNEL REALIGNMENT AND WETLAND RELOCATION DESIGN

Drawing Title:

# **CONSTRUCTION DETAILS**

Scale:		Date:		Drawing No.		
AS SHOWN		MAR. 10, 2025			CD	
Drawn by:	TR	Checked by:	МО	Sheet No.		_
Designed by:	МО	Approved by:	RM		09	