

TOWN OF CALEDON
PLANNING
RECEIVED

Dec 17, 2024



871 Equestrian Court, Unit 1, Oakville, ON L6L 6L7
Tel: 647-795-8153 | www.pecg.ca

Hydrogeological Assessment

**12519 & 12713 Humber Station Road, Bolton,
Ontario**

Palmer Project #
2008102

Prepared For
Prologis c/o Mainline Planning Services Inc.

November 21, 2024

November 21, 2024

Prologis
c/o
Mainline Planning Services Inc.
P.O. Bo 319 Kleinburg, ON
L0J 1C0

Re: Hydrogeological Assessment – 12519 & 12713 Humber Station Road, Bolton, ON
Project #: 2008102

Palmer is pleased to submit the attached report presenting the results of our hydrogeological assessment for the proposed development located at 12519 & 12713 Humber Station Road, Bolton, ON. The hydrogeological assessment covers all the items provided in the proposal with adjustment based on site constraints and project requirement. Palmer conducted the required assessments and analyses as per applicable provincial guidelines and generally accepted practices. The major findings include:

- The site is underlain with over 20 m thick overburden sediments that consist of silt to clay till and silt of the Halton Till formation within investigation depths. Significant aquifers are not identified below the site;
- Groundwater levels from monitoring wells range from 0.2 to 2.9 metres below ground surface (mbgs) with a predominant flow direction from northwest to southeast and to southwest, towards the tributary of West Humber River. The shallow groundwater levels measured are interpreted to be a reflection of the low permeability and poor drainage of the surficial soils;
- Groundwater level and surface water level data from mini-piezometers do not show hydraulic connection between groundwater and surface water, indicating that groundwater does not support stream flow and associated wetlands and shallow ponds. Therefore, groundwater does not take part in forming the hydroperiod of these features and these feature can be considered surface water supported;
- Hydraulic conductivity values range from the orders of 6.0×10^{-10} to 6.6×10^{-7} m/s, generally increasing with depths and grain size of formations;
- Based on in-situ percolation testing, the infiltration rate for the shallow soils averages 2.3 cm/min with a T-time of 56 min/cm;
- Groundwater quality is fresh and no visual or olfactory evidence of contamination such as visible petroleum hydrocarbon film or sheen as well as smell and odor were recorded during drilling or sampling. A number of exceedances were identified over ODWS and PWQO criteria, which is typical in raw groundwater, particularly in an agricultural setting;

- The construction dewatering analysis shows that the required dewatering rate for a typical construction working face for site servicing or shallow foundations could be up to 6,018 L/day, which is below the threshold of 50,000 L/day for consideration of an EASR. Therefore, neither an EASR registration nor a PTTW application is expected to be required for this project. Potential possible stormwater accumulation is provided for client's reference only;
- The water taking for construction dewatering is of short term, limited quantity and limited influence zones. No impacts from construction dewatering to natural heritage features or private wells is expected;
- The site water balance analysis shows the proposed Phase 1 development will cause a reduction of infiltration of 25,476 m³/year and an increase in runoff of 158,582 m³/year. The proposed infiltration tank will fully compensate the infiltration deficit;
- FBWB conducted for Phase One development shows that the development will result in an increased runoff of 86,633 m³/year and reduced infiltration of 1,012 m³/year in the East Wetland catchment, and an increased runoff of 81,353 m³/year and reduced infiltration of 678 m³/year in the East Wetland catchment. As neither the East Wetland and West Wetland receive groundwater discharge contribution, the minor reduction of infiltration within the catchment of each wetland will not adversely impact the wetlands. Runoff should be properly managed through the proposed SWM Plan to prevent the increased runoff to end up in the both wetlands. Through the establishment of wetland setbacks and new compensation areas in the Eastern Wetland catchment, and the creation of a new, higher functioning drainage channel in the Western Wetland catchment, no impacts to wetland hydrology or hydrogeology is expected.

We trust that this report is complete within our terms of reference and suitable for your present requirements. If you have any questions or require further information, please do not hesitate to contact our office.

Yours truly,



Jason Cole, M.Sc., P.Geo.

Technical Discipline Manager, Hydrology and Hydrogeology

Table of Contents

Letter

1.	Introduction	1
1.1	Proposed Development.....	1
1.2	Methodology	1
1.2.1	Review of Records and Previous Studies.....	1
1.2.2	Monitoring Point Inventory, Enlisting and Instrumentation	2
1.2.3	In-Situ Hydraulic Test.....	3
1.2.4	Groundwater Sampling	4
1.2.5	Groundwater Level and Surface Water Stage Monitoring	4
1.2.6	WWIS Well Record and PGMN Well Inventory	4
2.	Site Characterization.....	6
2.1	Physiography and Natural Heritage	6
2.1.1	Geomorphology and Climate	6
2.1.2	Natural Heritage Features.....	6
2.2	Geology and Site Stratigraphy	9
2.3	Site Groundwater Conditions	13
2.3.1	Source Protection, Water Supply and Sewerage System	13
2.4	Groundwater Levels, Flow Direction and Gradient	17
2.5	Hydraulic Conductivity	21
2.5.1	Hydraulic Conductivity from Single Well Response Tests	21
2.5.2	Hydraulic Conductivity from Grain Size Analysis	21
2.5.3	Hydraulic Conductivity for Different Formations	22
2.6	Infiltration Rate.....	22
2.7	Groundwater Chemistry	23
2.8	Water Levels from Mini-Piezometers.....	24
3.	Construction Dewatering Assessment	24
3.1	Dewatering Rate and Influence Zone.....	25
3.2	Location of Discharge and Dewatering Methods	26
3.3	PTTW, EASR and Municipal Permits	27
4.	Site Water Balance Assessment.....	27
4.1	Water Surplus	28
4.2	Land Use Unit Delineation and Infiltration Factor	29
4.3	Water Balance for Pre-Development and Post-Development.....	30
4.4	LID Design Considerations	31
5.	Feature-Based Water Balance Assessment	32
5.1	Water Surplus	32

5.2	Catchment Delineation and Infiltration Factor	33
5.3	Feature-Based Water Balance for Pre-Development and Post-Development.....	36
5.4	Retained Natural Heritage Features Protection	38
6.	Impact Assessment and Mitigation	38
6.1	Natural Heritage Features	38
6.2	Source Water Protection	38
6.3	Private Water Wells	39
6.4	Discharge Receiver.....	39
7.	Conclusions and Recommendations	39
8.	Signatures	41
	Limitations of Report	42
	References	43

List of Figures

Figure 1.	Site Investigation Plan	5
Figure 2.	Physiography	7
Figure 3.	Terrain and Drainage System.....	8
Figure 4.	Surficial geology.....	11
Figure 5.	Bedrock geology	12
Figure 6.	Source Water Protection.....	14
Figure 7.	Well Record Locations	16
Figure 8.	Groundwater Level Hydrographs	19
Figure 9.	Groundwater Level Contours and Flow Direction	20
Figure 10.	Catchment Delineation for Pre-Development Condition	34
Figure 11.	Catchment Delineation for Post-Development Condition	35

List of Tables

Table 1.	Monitoring Wells and Mini-piezometers Selected for Current Study	3
Table 2.	Monthly Averaged Climate Data	6
Table 3.	Overburden Geology (ORMGP).....	9
Table 4.	Summary of Stratigraphy	10
Table 5.	Summary of Well Records	13
Table 6.	Groundwater Levels	17
Table 7.	Historical Groundwater Levels	18
Table 8.	Hydraulic Conductivity from Slug Tests	21
Table 9.	Hydraulic Conductivity from Grain Size Analysis	22
Table 10.	Hydraulic Conductivity Summary	22
Table 11.	Infiltration Rate	23

Table 12. Exceedances Over ODWQS.....	23
Table 13. Water Level Monitoring Results for MPs	24
Table 14. Summary of Dewatering Analysis for Typical Length of Trenches	26
Table 15. Water Surplus for pervious Soil	28
Table 16. Land Use Units and Infiltration Factor for Pre- and Post-Development.....	29
Table 17. Site Water Balance for Pre- and Post-Development	31
Table 18. Catchment Areas and Infiltration Factor for East Wetland.....	33
Table 19. Catchment Areas and Infiltration Factor for West Wetland	36
Table 20. Feature Water Balance for East Wetland	36
Table 21. Feature Water Balance for West Wetland	37

List of Appendices

Appendix A.	Site Plan (Prologis 2023, Crozier 2024)
Appendix B.	Well Logs (Pinchin and IBI 2022)
Appendix C.	Single Well Response Tests (Palmer, 2022)
Appendix D.	Grain Size Distribution and K-Value Estimation (Pinchin and Palmer 2022)
Appendix E.	Groundwater Chemistry Analyses (ALS, 2022)
Appendix F.	Well Records (WWIS)
Appendix G.	Natural Heritage Features (GEI 2022)
Appendix H.	TRSPA Water Balance Results

1. Introduction

Palmer was retained by Prologis c/o Mainline Planning Services Inc. (“the client”) to complete a Hydrogeological Assessment as part of the Draft Plan and Site Plan applications for the proposed industrial/commercial development located at 12519 and 12713 Humber Station Road, Bolton, ON L7E 0Y1/0Z6 (“the site”) (**Figure 1**). The site is approximately 78.46 ha in area and is located at the northwest quadrant of Mayfield Road and Humber Station Road. The site currently is vacant, and hosts cultivated lands, a small woodlot, a pond and hedgerows. The site has access to municipal servicing from Peel Region.

The purpose of the Hydrogeological Assessment is conducted as part of project design and permitting with the Town of Caledon, Region of Peel, and Toronto and Region Conservation Authority (TRCA).

1.1 Proposed Development

Based on site plans and design drawings provided by the client, dated April 2024, the development consists of following features (**Appendix A**):

- Proposed Phase One Building 1 with a footprint of 14.32 ha;
- Future Phase 2A and Phase 2B;
- Future Phase 3;
- Pavement for parking, loading areas, access driveways;
- Seven (7) storage tanks (Tank 1 to Tank 7) for Phase 1 Building 1;
- Three rainwater harvesting tanks (Tank A, B, D) for Phase 1 Building 1;
- Three infiltration tanks (Tank C, E, F) for Phase 1 Building 1;
- Shallow and deep servicing utilities such as storm sewers, sanitary sewers, gas and power lines; and
- Landscaped features.

The existing pond feature is planned to be retained and re-purposed as a stormwater management (SWM) facility.

1.2 Methodology

1.2.1 Review of Records and Previous Studies

Detailed background and record review was conducted for the area surrounding the site to delineate the regional setting of the site, including physical setting and environmental setting. The regional setting will help delineate site conditions, help with data interpretation, and help with impact assessment.

The sources of data and records reviewed included, but are not limited to, Ontario Geological Survey database (physiography, geology and boreholes), MECP database (well record, natural heritage, hydrology, source protection and environmental instruments), data from Conservation Authorities (watershed plan, subwatershed studies, source protection plan, stormwater criteria and LID), and data from the municipalities (official plan, zoning plan, permit application, well head protection policies and sewer use bylaw).

Four previous study reports had been identified for the property, including:

1. Geotechnical Investigation Report by Pinchin in 2022;
2. Supplemental Geotechnical Investigation – Proposed Industrial Development, Pinchin 2023; and
3. Hydrogeological Investigation Report by IBI Group in 2022.

The following presents the parts from these studies that will contribute to the site characterization and data analysis of the present study.

Pinchin (2022) covered the same study area as the current study. The study was based on 18 boreholes (BH1 to BH18, depth range of 5.0 to 6.6 m, with six monitoring wells installed) and 14 test pits. The six monitoring wells installed for the first study will be enlisted for the current study. Grain size analysis results from this study were used by the present study to estimate hydraulic conductivity of formations (**Appendix D**).

Pinchin (2023) was based on the boreholes completed by the 2022 study and 82 more boreholes. Among the 82 boreholes, seven (7) monitoring wells were installed. The seven monitoring wells installed for this study will be enlisted for the current study. As this report was provided at later time, groundwater levels from only the recent rounds of monitoring were available.

The IBI Group (2022) Hydrogeological Study was completed for the overall Humber Station Landowners Group and was based on eight (8) monitoring wells (three nested) with depths ranging from 6.0 to 12.5 m, three (3) monitoring wells with depths ranging from 4.5 to 5.8 m, as well as nine (9) mini-piezometers, five groundwater samples (MW1-17, MW5-17S, MW3-17 and MW4-17D), and three surface water samples (SF1-17, SF5-17 and SF6-17). The monitoring wells and mini-piezometers installed within the site, and the two wells south of the site are enlisted for the current study.

1.2.2 Monitoring Point Inventory, Enlisting and Instrumentation

Following the review of previous studies, site reconnaissance was conducted several times by Palmer staff to examine landform, surficial features, monitoring wells, potential pathways, groundwater outcrops, water courses and potential natural hazards such as sinkholes, faults and karst features, and to inspect and confirm the conditions of monitoring wells and mini-piezometers.

The inspection of monitoring wells and mini-piezometers included such activities as grading surrounding ground surface to ensure surface water will not accumulate and infiltrate into wells and mini-piezometers, cleaning well structure (pit, pipe and cap), developing the wells and mini-piezometers, and measuring well depth and water levels in metres below ground surface (mbgs), and measuring stick-up height. Surface elevation of wells is presented in metres above sea level (masl). Four data loggers were installed in selected monitoring wells. **Table 1** lists the summary of the 21 monitoring wells (BH and MW) and five 95) mini-piezometers (SF and WL) that were confirmed to be in good condition and were selected to be monitored for the current study.

It should be noted that there are discrepancies between the elevations listed in **Table 1** and the elevations marked in borehole logs (**Appendix B**). The elevations in **Table 1** were provided by the client based on their survey, and will be used for calculating groundwater level elevations.

Figure 1 shows the location of the adopted monitoring wells. The well logs were attached as **Appendix B**.

Table 1. Monitoring Wells and Mini-piezometers Selected for Current Study

Well ID	Surface Elevation (masl)	Stick-up (m)	Depth (mbgs)	Screened Interval (mbgs)	Screened Unit	Logger Installed	Consultant
BH1	239.28	0.97	6.02	3-6	Silt	Yes	Pinchin
BH9	235.57	0.95	6.09	3-6	Silt	Yes	Pinchin
BH12	237.15	0.89	4.3	3-6	Silt	-	Pinchin
BH12b	-	0.95	5.31	-	-	-	-
BH13	237.42	0.94	6.04	3-6	Silt	Yes	Pinchin
BH15	234.02	1	6.19	3-6	Silt	-	Pinchin
BH18	232.61	0.93	6.35	3-6	Silt	Yes	Pinchin
MW103	238.79	0.92	6.07	3-6	Clay till	-	Pinchin
MW108	236.89	1.05	6.1	3-6	Clay till	-	Pinchin
BHz	-	0.81	6.1	3-6		-	-
MW124	239.04	0.95	6.23	3-6	Clay till and sand	-	Pinchin
MW160	234.36	0.9	6.23	3-6	Clay till and sandy silt	-	Pinchin
MW161	232.84	1.0	6.29	3-6	Clay till	-	Pinchin
MW168	231.87	1.08	6.03	3-6	Clay till	-	Pinchin
MW3-17	234.79	0.7	6.01	3-6	Silt	-	Soil Eng.
MW4-17S	233.98	0.93	5.85	3-6	Silt	-	Soil Eng.
MW4-17D	233.98	0.72	12.18	9-12	Silt	-	Soil Eng.
MW8	231.86	0.86	15.11	3.5-5	Silt till	-	Burnside
MW9	235.59	0.84	5.4	3.7-5.2	Silty sand	-	Burnside
BHx	-	0.86	6.28	-	-	-	-
SF2-7S	-	0.24	0.97	-	-	-	IBI
SF2-17D	-	1.38	0.66	-	-	-	IBI
SF5-17S	-	0.42	0.8	-	-	-	IBI
SF5-17D	-	1.06	0.96	-	-	-	IBI
WL2-17	-	1.6	0.3	-	-	-	IBI

1.2.3 In-Situ Hydraulic Test

Single well response test (SWRT or slug test) was conducted on November 21 and 29, 2021 in selected monitoring wells enlisted for the study to estimate hydraulic conductivity (K-value). During slug test, a change in hydraulic head was created with a bailer to remove water (<1 L) or with a slug rod to dispel water. The hydraulic conductivity was estimated by measuring the rate of change in water levels after the water head was created. The water level recovery during each test was recorded with an automatic datalogger. The recovery was also gauged manually using a water level tape. SWRTs in all wells were terminated after either 80% recovery was achieved or 30 minutes had passed. The testing results are attached as **Appendix C**.

1.2.4 Groundwater Sampling

Groundwater sampling was conducted in general accordance with provincial practices and Palmer's standard operation procedure (SOP). Chemical analysis was conducted by ALS Environmental Laboratory, which has been accredited Canadian Association for Laboratory Accreditation (CALA). The groundwater sample was taken from BH13 on November 21, 2022 and was submitted to the lab at the same day. The groundwater sample was tested against Ontario Drinking Quality Standards parameters. Test results were attached as **Appendix E**.

In addition, the chemical analysis results for groundwater from the enlisted monitoring wells located within the site from Pinchin (2023) are adopted for this study, which include testing results for groundwater samples from MW3-17 and MW4-17D. The certificates of analysis are attached as **Appendix E**.

1.2.5 Groundwater Level and Surface Water Stage Monitoring

Groundwater level and surface water stage monitoring was conducted through manual measurement, visual observations and logger recording, and was meant to delineate water level trend and fluctuation magnitude, as well as the interaction between surface water and groundwater. Palmer completed eight (8) rounds of site visits for groundwater level and surface water stage monitoring, and the following is the activities completed during each site visit:

- Measure groundwater levels for monitoring wells and mini-piezometers;
- Measure and observe surface water stage for creek and wetlands;
- Download data from loggers, confirm the conditions of logger, and reset loggers as required; and
- Carry out maintenance for monitoring wells and mini-piezometers.




1.2.6 WWIS Well Record and PGMN Well Inventory


Well records within 500 m from the site boundary were queried from the database of the Water Well Information System (WWIS) of Ontario for fields of well ID, completion date, well depth, static groundwater levels, aquifer type (bedrock or overburden well), water quality and water use. A total 46 wells were identified. The results of well survey were attached as **Appendix F**.

The Provincial Groundwater Monitoring Network (PGMN) was also searched. The closest PGMN well was found located 4.0 km northwest of the site (W0000327-3). Not water quality data is available for this well. Water level records show obvious seasonal trend, no yearly trend was observed, and fluctuations ranging from 0.6 to 0.8 m.



LEGEND

-  Site Boundary
-  Monitoring Well
-  Mini-Piezometer



North American Datum 1983, UTM Zone 17N (EPSG: 26917)

Scale: 1:7,000
Page Size: Letter (11 x 8.5 inches)

Drawn: FL
Checked: JC
Date: Aug 2024
Source Notes:
Basemap - Google Satellite (2020)
Topo Contour - Peel Region (Spring 2021)



CLIENT	Prologis	
PROJECT	12519 & 12713 Humber Station Road, Bolton, Ontario	
TITLE	Site Investigation Plan	
Palmer PART OF SLR	REF. NO.	2008102
	Figure 1	

2. Site Characterization

2.1 Physiography and Natural Heritage

2.1.1 Geomorphology and Climate

The site is located in a Drumlinized Till Plain, part of an larger unit, South Slope (Chapman & Putnam, 1984 and OGS, **Figure 2**). The site is currently used as farmland, with flat to rolling ground surface. The ground elevations range from 239.0 to 232 masl, and dip gently from north to south.

The site is in a continental climate region with a warm, humid summer and a cold winter as well as wet spring, dry summer and moderate rainfall in autumn. The region is generally affected by warm, moist air masses from the south and cold, dry air masses from the north and experiences a wide range of weather conditions through the course of an average year. The following table lists the average and daily values of major climate parameters collected at the closest climate station (Toronto Lester B. Pearson International Airport) for the period between 1981 and 2010 (**Table 2**).


Table 2. Monthly Averaged Climate Data

Average Value	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Daily Air T (°C)	-5.5	-4.5	0.1	7.1	13.1	18.6	21.5	20.6	16.2	9.5	3.7	-2.2
Rainfall (mm)	25.1	24.3	32.6	63	74.3	71.5	75.7	78.1	74.5	60.6	68	34
Snowfall (cm)	29.5	24	17.7	4.5	0	0	0	0	0	0.4	7.5	24.9
Precipitation (mm)	51.8	47.7	49.8	68.5	74.3	71.5	75.7	78.1	74.5	61.1	75.1	57.9
Extreme Daily Value	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Extreme Daily Rainfall (mm)	58.7	31.8	41.7	55.8	92.7	53.8	118.5	80.8	108	121.4	86.1	40.9
Extreme Daily Snowfall (cm)	36.8	39.9	32.3	26.7	2.3	0	0	0	0	7.4	33.5	28.2



2.1.2 Natural Heritage Features

The site is in the West Humber subwatershed of Humber River watershed under the jurisdiction of Toronto and Region Conservation Authority (TRCA).


Goreway Drive Tributary to the West Humber River flows from northwest to southeast about 90 m to the west of the site, and a subtributary (an ephemeral creek) flows through the site and join the Goreway Drive Tributary to the west of the site. Clarkway Drive Tributary runs along the east boundary of the site flowing from northwest to southeast. An ephemeral subtributary of Clarkway Drive Tributary flows along the middle line of the site. This subtributary is dry and has flow recoded only during or immediately following rainfall (**Figure 3**).




LEGEND

-  Watercourse¹
-  Subject Site

Physiographic Region²

-  1: Niagara Escarpment
-  30: Oak Ridges Moraine
-  32: South Slope
-  33: Peel Plain

1. LIO/MNRF
 2. Chapman, L.J. and Putnam, D.F. 2007. Physiography of southern Ontario; Ontario Geological Survey, Miscellaneous Release--Data 228.



North American Datum 1983
 Universal Transverse Mercator Projection Zone 17


Scale: 1:100,000
 Page Size: Letter (8.5 x 11 inches)

Drawn: CV
 Checked: FL
 Date: Nov 26, 2022









Source Notes:
 Imagery (2020) provided by Peel and York Region map services.
 Contains information licensed under the Open Government Licence - Ontario.

CLIENT	Prologis
PROJECT	Humber Station Road
TITLE	Physiography
REF. NO.	2008102-1-1
Figure 2	



LEGEND

-  Site Boundary
-  Topo Contour
-  Water Course
-  East Wetland
-  West Wetland



North American Datum 1983, UTM Zone 17N (EPSG: 26917)

Scale: 1:9,000
Page Size: Letter (11 x 8.5 inches)

Drawn: FL
Checked: JC
Date: Aug 2024
Source Notes:
Basemap - Google Satellite (2020)
Topo Contour - Peel Region (Spring 2021)



CLIENT	Prologis
PROJECT	12519 & 12713 Humber Station Road, Bolton, Ontario
TITLE	Terrain and Drainage

Based on the provincial natural heritage mapping and available site information, the site is located approximately 14 km east of the Niagara Escarpment, 6.0 km south of the Oak Ridges Moraine, 32.0 km to the north of Lake Ontario. Based on the Natural Heritage Feature map completed by GEI as part of the CEISMP Report (**Appendix G**), the natural heritage features identified near and within the site include:

- An ephemeral creek crossing the site. The creek is grown out with weed and shrubs;
- An in-line wetland on the north end of the site mapped by GEI as MAM2-11 and CUM1-1;
- A woodland located bordering the in-line wetland on the north end of the site mapped by GEI as FOD8-3.
- An in-line pond on the south part of the site. The pond was mapped as unevaluated wetland in the provincial natural heritage mapping, but mapped by GEI as SAS-1 and MAS2-1 and MAM2-2; and
- An in-line unevaluated wetland along the east boundary of the site mapped by GEI as MAM2-11/2, MAS2-1 and CUM1-1.

The ephemeral creek is proposed to be realigned to facilitate layout of the proposed development and is expected to maintain its function as a surface water supported, ephemeral feature.

2.2 Geology and Site Stratigraphy

Surficial geology of the Site was mapped by Ontario Geological Survey (OGS) as clay to silt-textured till (derived from glaciolacustrine deposits or shale), which is named regionally as Halton Till (**Figure 4**).

The site is located within the area of Oak Ridges Moraine Groundwater Program (ORMGP). ORMGP has developed three-dimensional overburden geological model within its area. Based on ORMGP model, the overburden geology under and surrounding the site is summarized in **Table 3**.

Table 3. Overburden Geology (ORMGP)

Division	Formation/Unit	Thickness (m)	Distribution within Site	Interpretation
Overburden	Halton Till	5-15	Whole area	
	ORM Complex	3-11	Whole area	Kame moraine
	Lower Newmarket Till	1-10	Whole area	-
Bedrock	Georgian Bay Formation	25-30 (depth)	-	-


Bedrock underlays the overburden and was mapped as Georgian Bay Formation of Late Ordovician age and consists of shale, limestone, dolostone, siltstone. Georgian Bay Formation serves as regional aquitard in the area based on regional hydrogeology of Ontario (**Figure 5**).

The stratigraphy under the site was characterized based on the regional information and the findings from the borehole logs completed by Pinchin, Soil Eng. and Burnside (**Table 1** and **Appendix B**). **Table 4** summarises the stratigraphy under the site including major lithological units, bottom depth ranges, natural water content and mechanical properties.

Table 4. Summary of Stratigraphy

Unit No	Unit Name	Lithology	Top Elvt (masl)	Bottom Elvt (masl)	Natural Water Content	N-Value	Hydro-stratigraphy
1	Topsoil	Silt, trace sand with organics, dark brown	239.28-232.61	239.13-232.46	Moist	-	Aquitard (Halton Till)
2	Brown Silt to silty clay till	Silt to clayey silt, trace sand and gravel, some oxidation.	239.13-232.46	234.73-229.19	Moist	8-30	
3	Grey Silt	Silt to sandy silt, or with trace sand and gravel, trace to some clay, trace oxidation locally.	234.73-229.19	222.1	Moist to wet	30-77	

As the summary of stratigraphy shows, the site is underlain with a suite of over-compacted clay till and silt deposited in glacial and proglacial environment. Both clay till and silt forms aquitards, and aquifer units were not encountered within the investigation depths.



LEGEND

Watercourse¹

Subject Site

Surficial Geology²

Phanerozoic / Cenozoic / Quaternary / Recent

- 20: Organic deposits (*peat, muck, marl*)
- 19: Modern alluvial deposits (*clay, silt, sand, gravel, may contain organic remains*)

Phanerozoic / Cenozoic / Quaternary / Pleistocene

- 12: Older alluvial deposits (*clay, silt, sand, gravel, may contain organic remains*)
- 9c: Coarse-textured glaciolacustrine deposits (*Foreshore and basinal deposits*)
- 8b: Fine-textured glaciolacustrine deposits (*Interbedded silt and clay and gritty, pebbly flow till and rainout deposits*)
- 7: Glaciofluvial deposits (*river deposits and delta topset facies*)
- 6: Ice-contact stratified deposits (*sand and gravel, minor silt, clay and till*)
- 5d: Till (Clay to silt-textured till [derived from glaciolacustrine deposits or shale])

Phanerozoic / Paleozoic

- 3: Paleozoic bedrock

1. LIO/MNRF
 2. Ontario Geological Survey 2010 (Mapped at 1:50,000). Surficial geology of southern Ontario; Ontario Geological Survey. Miscellaneous Release- Data 128 - Revised

0 0.5 1 2 3 4 5
KM

North American Datum 1983
 Universal Transverse Mercator Projection Zone 17

Scale: 1:100,000
 Page Size: Letter (8.5 x 11 inches)

Drawn: CV
 Checked: FL
 Date: Nov 26, 2022

Source Notes:
 Imagery (2020) provided by Peel and York Region map services.
 Contains information licensed under the Open Government Licence – Ontario.

CLIENT: Prologis


PROJECT: Humber Station Road

TITLE: Surficial Geology



REF. NO. 2008102-2-1

Palmer™

Figure 4





LEGEND


-  Watercourse¹
-  Subject Site

Paleozoic Bedrock Geology²

Upper Ordovician

-  16: Queenston (shale, siltstone, minor limestone and sandstone)
-  14: Georgian Bay (shale and limestone)

1. LIO/MNRF
 2. Armstrong, D.K. and Dodge, J.E.P. Paleozoic Geology Map of Southern Ontario; Ontario Geological Survey, Miscellaneous Release-Data 219



North American Datum 1983
 Universal Transverse Mercator Projection Zone 17

Scale: 1:100,000
 Page Size: Letter (8.5 x 11 inches)

Drawn: CV
 Checked: FL
 Date: Nov 26, 2022



Source Notes:
 Imagery (2020) provided by Peel and York Region map services.
 Contains information licensed under the Open Government Licence – Ontario.

CLIENT	Prologis
PROJECT	Humber Station Road
TITLE	Bedrock Geology
REF. NO.	2008102-3-1
Figure 5	

2.3 Site Groundwater Conditions

2.3.1 Source Protection, Water Supply and Sewerage System

The site is located within the Toronto and Region Source Protection Area under the Source Protection Plan of CTC Source Protection Region. The Source Protection Plan designated the following 10 types of vulnerable areas:


- Wellhead Protection Area-Quality
- Wellhead Protection Area E-(GUDI)
- Intake Protection Zone-Quality
- Intake Protection Zone-Quantity
- Issue Contributing Area
- Significant Groundwater Recharge Area
- Highly Vulnerable Aquifer
- Event Based Area
- Wellhead Protection Area Q1-Quantity
- Wellhead Protection Area Q2-Quantity

Based on the provincial source protection mapping and the above source protection plan (**Figure 6**), only two isolated areas within the site are located above the Highly Vulnerable Aquifer (HVA) with a vulnerable score of 6.



Based on well records queried from WWIS database (**Appendix F**), groundwater levels range from 0 to 14 mbgs. The groundwater levels have no apparent and even reverse correlation with well depths, indicating upward gradient may exist at certain depths within the well record searching area. All of the domestic wells were constructed before 1994, and about half of the domestic wells tapped water from bedrock aquifer and the other half tapped water from overburden aquifer. The well records within the site show that the shallow regional aquifers consisted of gravels and weathered shale (contact aquifer) may exist at depths greater than 17 mbgs.

Table 5. Summary of Well Records






	Classification	Record Number
Water Use	Domestic/livestock	19
	Commercial	-
	Industrial	-
	Municipal	-
	Monitoring	-
	Monitoring and Test Hole	8
	Irrigation	-
	Decommissioned	-
	Unknow/Not used	19
Water Quality	Fresh	-
	Salty	-
	Untested	-
	Unknown	46
Aquifer	Overburden	21
	Bedrock	13
	Unknown	11




LEGEND

-  Watercourse¹
-  Subject Site

Source Water Protection²

-  Wellhead Protection Area - A
-  Wellhead Protection Area - B
-  Wellhead Protection Area - C
-  Wellhead Protection Area - D
-  Wellhead Protection Area Q1/Q2

1. LIO/MNRF
 2. Source Protection Information Atlas, MECP © King's Printer for Ontario 2022



North American Datum 1983
 Universal Transverse Mercator Projection Zone 17


Scale: 1:100,000
 Page Size: Letter (8.5 x 11 inches)

Drawn: CV
 Checked: FL
 Date: Nov 26, 2022



Source Notes:
 Imagery (2020) provided by Peel and York Region map services.
 Contains information licensed under the Open Government Licence – Ontario.

CLIENT	Prologis	
PROJECT	Humber Station Road	
TITLE	Source Water Protection	
	REF. NO.	2008102-4a-1
	Figure 6a	



LEGEND

- Watercourse¹
- Subject Site

Source Water Protection²

- Highly Vulnerable Aquifer
- Significant Groundwater Recharge Area
- Score 0

1. LIO/MNRF
 2. Source Protection Information Atlas, MECP © King's Printer for Ontario 2022

0 0.5 1 2 3 4 5
 KM

North American Datum 1983
 Universal Transverse Mercator Projection Zone 17

Scale: 1:100,000
 Page Size: Letter (8.5 x 11 inches)

Drawn: CV
 Checked: FL
 Date: Nov 26, 2022

Source Notes:
 Imagery (2020) provided by Peel and York Region map services.
 Contains information licensed under the Open Government Licence – Ontario.

CLIENT: Prologis


PROJECT: Humber Station Road

TITLE: Source Water Protection

Palmer™

REF. NO. 2008102-4b-1

Figure 6b



LEGEND

- Well Record within 500m¹
- ~ Watercourse²
- Subject Site
- 500m Site Buffer

1. MECP
2. LIO/MNRF

0 50 100 200 300 400 500
METERS

North American Datum 1983
Universal Transverse Mercator Projection Zone 17

Scale: 1:13,000
Page Size: Letter (8.5 x 11 inches)

Drawn: CV
Checked: FL
Date: Nov 26, 2022

Source Notes:
Imagery (2020) provided by Peel and York Region map services.
Contains information licensed under the Open Government Licence – Ontario.

CLIENT	Prologis
PROJECT	Humber Station Road
TITLE	MECP Well Records within 500 m of Site
REF. NO.	2008102-5-1
Palmer™	
Figure 7	

As shown above, majority of overburden soil were interpreted to be, from top down, Halton Till, ORM complex and Newmarket Till. Both Halton Till and Newmarket Till have limited capacity to store and transmit groundwater and act as regional aquitards. ORM complex is well recognized as a regional aquifer. Top weathered and fractured zone of bedrock has moderate capacity to store and transmit groundwater and may serve as regional aquifer.

The water supply and sanitary servicing are provided by the Region of Peel. The water supply for the area surrounding the site was provided by Peel Region through Palgrave - Caledon East Drinking Water System, which consists of three supply wells in Palgrave and four supply wells in Caledon East. The supply wells are located over ten (10) km to the north of the site.

2.4 Groundwater Levels, Flow Direction and Gradient

Several rounds of manual groundwater level measurement were conducted for the monitoring wells enlisted for this study. Data loggers were installed in four monitoring wells to monitor groundwater in a frequency of one recording per hour. The manual measurement results were summarized in **Table 6**.

Table 6. Groundwater Levels

Well ID	Surface Elevation (masl)	Depth (mbgs)	Water Level (m)							
			Nov 8/9, 22		Nov 21, 22		Nov 29, 22		Feb 8, 23	
			mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl
BH1	239.28	6.02	2.51	236.77	2.62	236.66	2.72	236.56	2.74	236.54
BH9	235.57	6.09	2.24	233.33	2.14	233.43	2.28	233.29	1.52	234.05
BH12	237.15	4.30	0.53	236.62	0.44	236.71	-		0.23	236.92
BH12b	-	5.31	0.85	-	-	-	-		0.4	-
BH13	237.42	6.04	2.18	235.24	-	-	2.26	235.16	1.13	236.29
BH15	234.02	6.19	2.87	231.15	2.76	231.26	-		1.5	232.52
BH18	232.61	6.35	1.83	230.78	-	-	1.85	230.76	0.79	231.82
MW103	238.79	6.07	-	-	-	-	-	-	-	-
MW108	236.89	6.10	-	-	-	-	-	-	-	-
BHz	-	6.10	-	-	-	-	-	-	-	-
MW124	239.04	6.23	-	-	-	-	-	-	-	-
MW160	234.36	6.23	-	-	-	-	-	-	-	-
MW161	232.84	6.29	-	-	-	-	-	-	-	-
MW168	231.87	6.03	-	-	-	-	-	-	-	-
MW3-17	234.79	6.01	0.3	234.49	0.52	234.27	-	-	0.22	234.57
MW4-17S	233.98	5.85	1.97	232.01	2	231.98	2.06	231.92	0.87	233.11
MW4-17D	233.98	12.18	2.18	231.80	2.07	231.91	2.12	231.86	0.97	233.01
MW8	231.86	15.11	1.81	230.05	-	-	1.84	230.02	0.52	231.34
MW9	235.59	5.40	3.04	232.55	2.93	232.66	-	-	1.96	233.63
BHx	-	6.28	-	-	-	-	-	-	-	-

Well ID	Surface Elevation (masl)	Depth (mbgs)	Water Level (m)							
			May 12, 23		July 31, 23		Feb 18, 24		May 20, 24	
			mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl
BH1	239.28	6.02	1.49	237.79	1.14	238.14	-	-	1.18	238.1
BH9	235.57	6.09	0.6	234.97	0.54	235.03	0.72	234.85	0.58	234.99
BH12	237.15	4.30	0.24	236.91	0.13	237.02	0.17	236.98	0.26	236.89
BH12b	-	5.31	0.27	-	0.27	-	0.21	-	0.35	-
BH13	237.42	6.04	0.33	237.09	0.305	237.115	0.43	236.99	0.4	237.02
BH15	234.02	6.19	0.93	233.09	-	-	1	233.02	0.98	233.04
BH18	232.61	6.35	0.45	232.16	0.42	232.19	0.49	232.12	0.45	232.16
MW103	238.79	6.07	-	-	-	-	1.04	237.75	0.37	238.42
MW108	236.89	6.10	-	-	-	-	0.82	236.07	0.63	236.26
BHz	-	6.10	-	-	-	-	1.69	-	-	-
MW124	239.04	6.23	-	-	-	-	1.5	237.54	0.62	238.42
MW160	234.36	6.23	-	-	-	-	1.01	233.35	1.05	233.31
MW161	232.84	6.29	-	-	-	-	0.45	232.39	0.53	232.31
MW168	231.87	6.03	-	-	-	-	-	-	0.67	231.2
MW3-17	234.79	6.01	0.16	234.63	-	-	1.94	232.85	0.19	234.6
MW4-17S	233.98	5.85	0.6	233.38	0.54	234.83	0.59	233.39	0.64	233.34
MW4-17D	233.98	12.18	0.53	233.45	0.54	233.44	0.55	233.43	0.52	233.46
MW8	231.86	15.11	0.59	231.27	0.66	233.44	0.52	231.34	0.66	231.2
MW9	235.59	5.4	1.61	233.98	1.55	231.2	1.6	233.99	1.62	233.97
BHx	-	6.28	-	-	-	-	0.96	-	0.81	-

Representative range of historical values of groundwater levels measured by previous studies of Soil Engineers and Palmer were listed in **Table 7**.


Table 7. Historical Groundwater Levels

Well ID	Surface Elevation (masl)	Depth (mbgs)	Water Level (m)													
			Aug 31, 17		Sep 22, 17		Nov 10, 17		Dec 5, 17		Feb 7, 18		Apr 23, 18		Apr 25, 22	
			mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl	mbgs	masl
BH1	239.28	6.15	-	-	-	-	-	-	-	-	-	-	-	-	5.5	233.78
BH9	235.57	6.13	-	-	-	-	-	-	-	-	-	-	-	-	1.8	233.77
BH12	237.15	4.22	-	-	-	-	-	-	-	-	-	-	-	-	1.2	235.95
BH12b	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
BH13	237.42	6.00	-	-	-	-	-	-	-	-	-	-	-	-	1.4	236.02
BH15	234.02	6.30	-	-	-	-	-	-	-	-	-	-	-	-	2	232.02
BH18	232.61	6.40	-	-	-	-	-	-	-	-	-	-	-	-	1.5	231.11
MW3-17	234.79	7.04	2.61	232.18	0.45	234.34	0.3	234.49	0.14	234.65	-	-	0.1	234.69	-	-
MW4-17S	233.98	5.90	1.06	232.92	1.37	232.61	1.76	232.22	1.4	232.58	1.48	232.5	0.48	233.5	-	-
MW4-17D	233.98	12.20	0.95	233.03	1.27	232.71	1.67	232.31	1.44	232.54	1.44	232.54	0.61	233.37	-	-
MW8	231.86	5.15	0.39	231.47	1.85	230.01	1.76	230.1	1.12	230.74	0.97	230.89	0.31	231.55	-	-
MW9	235.59	5.15	1.89	233.7	2.1	233.49	2.24	233.35	1.92	233.67	2.11	233.48	1.38	234.21	-	-

Continuous recording of groundwater levels was acquired with dataloggers for BH1, BH9, BH13 and BH18. The hydrographs are presented in **Figure 8**. The hydrographs show the following characteristics of the groundwater regime at the site:

- The forms and trends of these hydrographs are highly synchronized, indicating that groundwater under different locations within the site responds to recharge similarly and the overburden soil at the site are hydraulically uniform;
- The hydrographs do not show typical spring-high and summer-low patterns of groundwater levels in Southern Ontario. The peak groundwater levels appear three to four months after spring, indicating that groundwater levels respond slowly to precipitation, which may be due to low permeability of soils; and
- Overall, the hydrographs show a semi-year pattern, with peak levels on August and lowest levels at late December.

Figure 8. Groundwater Level Hydrographs





Based on the elevation of groundwater levels, the groundwater table contours and flow direction were delineated and shown in **Figure 9**. The horizontal groundwater gradient is about 0.7% and the flow direction is from northwest to southeast and south toward the tributaries.

It should be noted that no aquifer units were encountered within the investigation depths, which means that all monitoring wells were completed in aquitard units. Recorded groundwater levels show drastic variation among different monitoring wells and over different monitoring events, indicating that the groundwater table and saturated zones are not continuous within the investigation depths at the site. Groundwater in monitoring wells stems mostly from local recharge and the predominant direction of the hydraulic gradient is expected to be downwards.



LEGEND

- Site Boundary
- ⊕ Monitoring Well
- GW Table Ele Contour
- ➔ Predominant Groundwater Flow Direction



North American Datum 1983, UTM Zone 17N (EPSG: 26917)

Scale: 1:7,000
Page Size: Letter (11 x 8.5 inches)

Drawn: FL
Checked: JC
Date: Nov 2024
Source Notes:
Basemap - Google Satellite (2020)
Topo Contour - Peel Region (Spring 2021)



CLIENT	Prologis
PROJECT	12519 & 12713 Humber Station Road, Bolton, Ontario
TITLE	Groundwater Table Contour and Flow Direction

Palmer PART OF SLR	REF. NO. 2008102
Figure 9	

2.5 Hydraulic Conductivity

2.5.1 Hydraulic Conductivity from Single Well Response Tests

Hydraulic conductivity (K-value) of saturated zones was estimated through single well response tests (SWRTs) or slug tests, which has been introduced above. The results of the slug tests are summed up in **Table 8**.

Table 8 Hydraulic Conductivity from Slug Tests

Well ID	Surface Elevation (masl)	Depth (mbgs)	Screened Interval (mbgs)	Screened Unit	K-value (m/s)
BH9	235.57	6.13	3-6	Silt	6.6×10^{-7}
BH12	237.15	4.22	3-6	Silt	5.7×10^{-9}
BH15	234.02	6.3	3-6	Silt	5.3×10^{-8}
BH18	232.61	6.4	3-6	Silt	7.7×10^{-8}
MW3-17	235.5	5.9	3-6	Silt	7.2×10^{-8}
MW4-17S	234.8	5.9	3-6	Silt	1.4×10^{-7}
MW8	231.94	5.15	3.5-5	Silt till	5.6×10^{-7}
MW9	235.69	5.15	3.7-5.2	Silty sand	7.1×10^{-7}
MW4-17D	234.8	12.2	9-12	Silt	2.9×10^{-7}

2.5.2 Hydraulic Conductivity from Grain Size Analysis

The K-values of sampled soils were estimated with the results of grain size analysis tests which was completed by Pinchin. Soil samples for grain size analysis were taken different depths, representing shallow to deep soil conditions. The results of grain size analysis were used to get K-values through the following empirical equation, and the estimation results are presented in **Table 9**. It should be noted that the K-values from grain size analysis is substantially lower than K-values from slug tests, which may be attributed to the lack of structures such as joints, fractures, burrows and rootholes, as well as the reconstitution of grain size analysis samples.

$$K \text{ (Sauerbrei, 1932)} = \frac{\rho g}{\mu} [(3.75 \times 10^{-5}) \times \tau] \left[\frac{n^3}{(1-n)^2} \right] d_{17}^2 \frac{cm}{s}$$

Where K	=	hydraulic conductivity (cm/s)
ρ	=	$3.1 \times 10^{-8}T^3 - 7.0 \times 10^{-6}T^2 + 4.19 \times 10^{-5}T + 0.99985$
g	=	980 cms ⁻²
μ	=	$-7.0 \times 10^{-8}T^3 + 1.002 \times 10^{-5}T^2 - 5.7 \times 10^{-4}T + 0.0178$
τ	=	$1.093 \times 10^{-4}T^2 + 2.102 \times 10^{-2}T + 0.5889$
n	=	porosity as a fraction of aquifer volume
T	=	water temperature (°C)

Table 9 Hydraulic Conductivity from Grain Size Analysis

Well ID	Sample ID	Depth (mbgs)	Soil Classification	K-value (m/s)
BH4	SS4	3.0-3.5	Silt	6.0×10^{-10}
BH6	SS1	0.0-0.6	Silt	7.0×10^{-10}
BH14	SS5	4.5-4.7	Silt	1.0×10^{-8}
BH18	SS4	3.0-3.5	Silt	1.7×10^{-9}

2.5.3 Hydraulic Conductivity for Different Formations

Different methods of hydraulic conductivity tests were targeted to soil formations of different depths in different water content states. Based on above test results, the K-values for each formation were summarised and listed **Table 10**.

Table 10. Hydraulic Conductivity Summary

Unit Name	Investigation Point ID	Test	Depth Range (mbgs)	K-value (m/s)	Geometric Mean K-value (m/s)	90th Percentile K-value (m/s)
Clayey silt	BH6	Grain Size Analysis	0.0-0.6	7.0×10^{-10}	8.9×10^{-10}	1.5×10^{-9}
Silt and clay	BH4	Grain Size Analysis	3.0-3.5	6.0×10^{-10}		
Silt	BH18	Grain Size Analysis	3.0-3.5	1.7×10^{-9}		
Silt	BH14	Grain Size Analysis	4.5-4.7	1.0×10^{-8}	5.5×10^{-8}	3.5×10^{-7}
Silt	BH9	Slug Test	3-6	6.6×10^{-7}		
Silt	BH12	Slug Test	3-6	5.7×10^{-9}		
Silt	BH15	Slug Test	3-6	5.3×10^{-8}		
Silt	BH18	Slug Test	3-6	7.7×10^{-8}		
Silt	MW3-17	Slug Test	3-6	7.2×10^{-8}		
Silt	MW4-17S	Slug Test	3-6	1.4×10^{-7}		
Sandy silt till	MW8	Slug Test	3.5-5	5.6×10^{-7}	4.9×10^{-7}	6.8×10^{-7}
Silty sand	MW9	Slug Test	3.7-5.2	7.1×10^{-7}		
Silt	MW4-17D	Slug Test	9-12	2.9×10^{-7}		

2.6 Infiltration Rate

Infiltration rates were estimated through the following empirical equation correlating K-values and infiltration rate provided in Ontario Ministry of Municipal Affairs and Housing (OMMAH) Supplementary Guidelines to the Ontario Building Code 1997, and in the Low Impact Development Stormwater Management Planning and Design Guide (TRCA/CVC, 2010). The estimated infiltrate rates are listed in **Table 11**.

$$K = (6 \times 10^{-11})I^{3.7363}$$

Where:

K = hydraulic conductivity (cm/s)

I = infiltration rate (mm/hr)

Rearranging for infiltration rate, we obtain the following relationship:

$$I = \left[\frac{K}{6 \times 10^{-11}} \right]^{3.7363}$$

Table 11. Infiltration Rate

Unit Name	Investigation Point ID	Depth Range (mbgs)	K-value (m/s)	Infiltration Rate		Geometric Mean	
				cm/min	T(min/cm)	cm/min	T(min/cm)
Clayey silt to silt	BH6	0.0-0.6	7.0×10^{-10}	1.1	91	1.19	85
	BH4	3.0-3.5	6.0×10^{-10}	1.1	94		
	BH18	3.0-3.5	1.7×10^{-9}	1.4	71		
Silt	BH14	4.5-4.7	1.0×10^{-8}	2.2	44	3.5	27
	BH9	3-6	6.6×10^{-7}	6.9	14		
	BH12	3-6	5.7×10^{-9}	1.9	52		
	BH15	3-6	5.3×10^{-8}	3.5	28		
	BH18	3-6	7.7×10^{-8}	3.9	26		
	MW3-17	3-6	7.2×10^{-8}	3.8	26		
	MW4-17S	3-6	1.4×10^{-7}	4.6	22		

2.7 Groundwater Chemistry

Groundwater analytical results for the current study (BH13) were assessed against Ontario Drinking Water Standards (ODWS) and Ontario Provincial Water Quality Objectives (PWQO), the exceedance is shown in **Table 12**. In addition, groundwater chemistry data for the two samples (MW3-17 and MW4-17D) from the hydrogeological assessment by IBI were also assessed against ODWS and PWQO, and their exceedances are shown in **Table 12**.

Table 12. Exceedances Over ODWQS

Parameters	Unit	PWQO	ODWS	BH13	MW3-17	MW4-17D
Color	CU	-	5	40	-	-
Total Dissolved Solid (TDS)	mg/L	-	500	689	-	-
Turbidity	NTU	-	5	21.4	-	-
Total Manganese	mg/L	-	0.05	0.12	-	-
Field pH	-	6.5-8.5	-	-	8.17	8.58
Total Phosphorus	mg/L	0.01	-	-	1.4	3.3
Total Boron	ug/L	200	-	-	260	ND
Total Cobalt	ug/L	0.9	-	-	ND	2.5
Total Copper	ug/L	5	-	-	ND	5.5
Total Iron	ug/L	300	-	-	ND	5400
Total Uranium	ug/L	5	-	-	3.4	1.2
Total Vanadium	ug/L	6	-	-	2.1	7.4

These exceedances are associated with either agricultural operation or high concentration of particulate materials of raw groundwater. The exceedances associated with agriculture are expected to improve with the cessation of agricultural operation. The exceedances associated with groundwater turbidity can be easily eliminated through filtering and settling.

2.8 Water Levels from Mini-Piezometers

Monitoring data from the mini-piezometers installed along the creek beds and wetlands include groundwater levels within the mini-piezometer pipes and surface water levels outside the mini-piezometer pipes, both groundwater and surface water levels being measured manually as meters from top of the pipes and converted to meters from the ground surface. **Table 13** summarises the monitoring results. As the monitoring results show, surface water features are dry during most of monitoring events and groundwater levels are below ground surface during all monitoring events, indicating that groundwater does not support surface water features.

It should be noted that WL2-17 was installed only 20 cm into ground. Recordings from WL2-17 do not represent actual water conditions.

Table 13. Water Level Monitoring Results for MPs

MP ID		Water Levels (mbgs)				
		Nov 9, 22	Nov 29, 22	Feb 8, 23	May 12, 23	July 31, 23
SF2-17S	In	-		-	0.01	0.06
	Out	-		-	Dry	Dry
	Gradient				Downward	Downward
SF2-17D	In	0.14		0.1	0	-0.08
	Out	0		dry	-0.06	-0.11
	Gradient	Downward		Downward	Downward	Downward
SF5-17S	In	Dry		0.04	0.12	0.05
	Out	Dry		Dry	Dry	Dry
	Gradient	-		Downward	Downward	Downward
SF5-17D	In	Dry		0.03	0.08	0.07
	Out	Dry		Dry	Dry	Dry
	Gradient	-		Downward	Downward	Downward
WL2-17	In	-0.69	Dry	0.16	-0.07	-0.46
	Out	dry	Dry	Dry	Dry	Dry
	Gradient	Upward	-	Downward	Upward	Upward

In – groundwater levels within MP.

Out – surface water levels outside the MP.

Negative values for in/out measurements indicate water levels above ground surface.

Gradient: minus-downgradient, positive-upgradient.

*No measurement due to frozen.

3. Construction Dewatering Assessment

Dewatering for construction is conducted to fulfil three purposes: provide a dry working condition, help maintain ground stability and help maintain healthy and safe working environment. Based on the above characterization of site conditions, the recorded groundwater levels range from 0.1 to 2.7 mbgs, and from 230.0 to 238.3 masl. As the proposed industrial buildings will be built on slab-on-grade foundations, the

requirement for construction dewatering for the buildings is not anticipated. However, the trenches for storm and sanitary sewers will extend below groundwater levels, and construction dewatering should be assessed for trench excavation. The following will discuss construction dewatering for trench excavation.

3.1 Dewatering Rate and Influence Zone

Dewatering rate (L/day) and influence zone are the key parameters for implementing construction dewatering and impact assessment. The dewatering rate incorporates three kinds of potential water flow or seepage into trench excavations, including static groundwater seepage, storage of groundwater that has to be depleted before groundwater flow reaches a static state, and storm water. The following calculations and estimation are based on the assumptions:

- Depth of trenches – 4.0 m;
- Typical length of trenches – 30 m; and
- Width of trenches – 2.0 m.

Based on the Grading Plan, the building grade will be 238.78 masl.

Static Groundwater Seepage and Influence Zone:

Based on the above delineation of excavation dimensions and stratigraphy, the excavation will penetrate through fill and silt to clay till unit. The major saturated soil body to be excavated is silt till. Therefore, the hydraulic conductivity value of silt to clay till (**Table 10**) will be used for calculation of dewatering rate and influence zone.

The static groundwater seepage for trench excavation for linear development features such as utilities and storm and sanitary sewers is estimated with the following Dupuit-Thiem equation, which include an item for two ends of the trench and the item for the trench length:

$$Q = K(H^2 - h_w^2) / [\log(R / r_w)] + xK(H^2 - h^2)/L$$

Q = pumping rate

K = hydraulic conductivity (m/s)

$K_v = K/10$

H = original water level (m) above lower aquitard

h_w = targeted level (m) above the lower aquitard

R = influence radius (combined) (m)

r_w = well radius or equivalent radius (m)

x=length of trench (m)

w=width of trench (m)

L=line source distance (m) which is the greater of $R_0/2$ or 10 m

Radius of influence zone is estimated with Sichardt and Kryieleis formula:

$$R_0 = C(H - h_w)K^{1/2}$$

Storage of Groundwater:

The storage of groundwater was estimated based on porosity of excavated soil, the volume of excavated saturated soil and the volume of saturated soil enclosed by the drawdown cone and influence zone column. Based on the classification of soil encountered in the boreholes, no wet and saturated zones were identified under the site within the zone of excavation. The soil encountered in boreholes are mostly fine-grained. Free gravity flow of groundwater during construction is not anticipated. Consequently, storage of groundwater will be insignificant and should be ignored.

Stormwater:

25 mm/day rainfall intensity has been used to estimate potential stormwater that may accumulate in the excavations as this rainfall intensity represent 95% storm events in southern Ontario. The potential stormwater accumulation is meant to direct the client to make a contingency plan for the construction executed during wet season and will not be considered in assessing if a PTTW or EASR is required.

Dewatering Summary:

Table 14 lists the input parameters and output values for dewatering rate and influence zone calculation for trenches of linear development features such as utilities and storm and sanitary sewers. The maximal required pumping rate will be 6,018 L/day after applying an uncertainty factor of 1.5 to the static flow rate, corresponding 0.1 L/s.

Table 14. Summary of Dewatering Analysis for Typical Length of Trenches

Parameters	Values
Excavation Area (m)	30 x 2
Excavation Depth (mbgs)	4.0
GW Level (masl)	239.3
Groundwater Level Target (masl)	233.78
K (m/s)	3.5×10^{-7}
H (m)	5.5
h (m)	0
x (m)	30
W (m)	2
Storm (mm/day)	25
R ₀ (m)	8.0
Q _{static} (L/day)	4,012
Q _{StaticFOU=1.5} (L/day)	6,018
Q _{storm=25mm} (L/day)	1,500

3.2 Location of Discharge and Dewatering Methods

MECP construction dewatering guides provided several options for discharging pumped water, including:

- Discharge to a sewage works that has the appropriate environmental compliance approval (ECA);

- Transfer to a waste management system that has the appropriate environmental compliance approval (ECA) or is registered under the non-hazardous waste transportation systems EASR;
- Discharge to a municipal sanitary sewer or storm sewer in accordance with any municipal requirements; and
- Discharge to land surface and managed on-site.

Based on the understanding of site conditions and the low dewatering rate, it is recommended that the pumped water be managed on site through an infiltration swale or pond. The contractor is responsible for design and construction of infiltration facilities. Best management practices should be exercised to prevent erosion, flooding and groundwater contamination. Based on the predicted pumping rate, Sump pumps should be adequate for controlling groundwater that may accumulate in the excavation pits or trenches.

3.3 PTTW, EASR and Municipal Permits

Water taking in Ontario is governed with Section 34 of Ontario Water Resources Act and its Regulation 387/04. The act and regulation require that no person shall take more than 50,000 litres of water on any day by any means except in accordance with a permit.

Construction dewatering is governed with Part II. 2 of Environmental Protection Act and its Regulation 63/16. Based on the act and regulation, construction dewatering with rates between 50,000 and 400,000 L/day can go through Environmental Activity and Sector Registry (EASR) and do not have to apply for a PTTW if the impact to natural resource and environment is not significant and no sensitive features are involved.

Based on the above analysis and understanding of the water taking legislations, construction dewatering for this project is expected to be below 50,000 L/day, and therefore neither an ESAR registration nor a PTTW application are required.

4. Site Water Balance Assessment

As presented above, the site is not located in WHPA-Q, and therefore, source protection water balance policies do not apply to the proposed development. The site water balance assessment was conducted to address concerns from agencies regarding stormwater management, and to provide inputs to stormwater management design. The water balance assessment was conducted in general accordance with the Hydrogeological Assessment Submissions, Conservation Authority Guidelines to Support Development Applications (2013) and Stormwater Management Planning and Design Manual of MECP (2003), and consists of the following steps:

- Water surplus determination;
- Land use unit delineation and infiltration factor determination for pre- and post-development scenarios;
- Pre- and post-development water balance analysis; and
- Low Impact Development (LID) considerations.

4.1 Water Surplus

Water surplus for pervious vegetated areas is estimated with Thornthwaite and Mather water balance method (1957) or based on Water Balance Tool developed by Toronto and Region Source Protection Area (TRSPA). Thornthwaite and Mather method is an accounting procedure to quantify components of the hydrologic cycle as expressed in the following equation:

$$P = ET + R + I + \Delta S$$

P= Precipitation (mm/year)

ET= Evapotranspiration (mm/year)

R= Runoff (mm/year)

I= Infiltration (mm/year)

R+I=Water surplus (mm/year)

ΔS = Change in groundwater storage (mm/year)

Palmer developed its own spreadsheet program to execute the analysis. The input data includes:

- Long term (30 years) monthly average precipitation and temperature collected from closest climate station (Toronto Lester B. Pearson International Airport) for the period between 1981 and 2010 (Section 3.1)
- Degrees of altitude = 44.51°.
- Soil moisture storage capacity for predominant land coverage = 100 mm.

Soil moisture storage capacity of 100 mm was selected based on shallow rooted bean and landscaping features in clayey silt soil. **Table 15** sums up the results of the analysis.

Table 15. Water Surplus for pervious Soil

Month	Mean Temperature (°C)	Total Precipitation (mm)	Actual Evapotranspiration (mm)	Water Surplus (mm)
January	-5.5	51.8	0.0	51.8
February	-4.5	47.7	0.0	47.7
March	0.1	49.8	0.3	49.5
April	7.1	68.5	34.7	33.8
May	13.1	74.3	97.3	-23.0
June	18.6	71.5	88.5	-17.0
July	21.5	75.7	81.7	-6.0
August	20.6	78.1	74.1	4.0
September	16.2	74.5	59.5	15.0
October	9.5	61.1	40.5	20.6
November	3.7	75.1	11.8	63.3
December	-2.2	57.9	0.0	57.9
YEAR		786	488	298

November 21, 2024

TRSPA provided the following water balance values for the site and nearby area:

- Total precipitation – 863 mm/year;
- Evapotranspiration – 575 mm/year;
- Runoff – 234 mm/year;
- Recharge – 54 mm/year;
- Water surplus – 288 mm/year.

TRSPA water balance results are fairly close to the results from the Thornthwaite and Mather method. Considering TRSPA used a higher and more recent precipitation value, TRSPA water balance values are used for the water balance analysis.

Water surplus for impervious areas (building roof, impervious pavement etc.) was calculated based on the assumption that 10% of total precipitation will evaporate on impervious surface (acceptable range is 10% to 20%), or with a runoff rate of 90%, and no precipitation will infiltrate. Total precipitation from TRSPA is 863 mm/year, and the water surplus on impervious at the site is 777 mm/year.

4.2 Land Use Unit Delineation and Infiltration Factor

Delineation of land use units was based on topography, surficial soil and land cover at the site for current site conditions (pre-development) and the conditions after the completion of the proposed development (post-development). Infiltration factor for each catchment was calculated based on the scoring table presented in the Page 3-4 of the Stormwater Management Planning and Design Manual of MECP (2003) and in the Page 4-62 of MECP Hydrogeological Technical Information Requirements for Land Development Applications (1995). **Table 16** summarizes the results of land unit delineation and infiltration factors for pre- and post- development scenarios.

As the Site Plans (**Appendix A**) show, only Phase 1 will be developed, therefore the water balance will focus on the Phase 1 development area. The Phase 2 and 3 development areas are treated as farmland.

Table 16. Land Use Units and Infiltration Factor for Pre- and Post-Development

Pre-Development					
Land Use Unit	Area (ha)	Slope Gradient	Soil	Land Cover	Infiltration Factor
Farmland	71.79	0.2	0.1	0.1	0.4
Woodland	2.98	0.2	0.1	0.2	0.5
Wetland	1.42	0.2	0.1	0.2	0.5
Grassland	0.64	0.2	0.1	0.2	0.5
Grass Channel	0.84	0.1	0.1	0.2	0.4
Pond	0.79	0.2	0.1	0.2	0.5
Total	78.46	-	-	-	-
Post-Development					
Land Use Unit	Area	Slope Gradient	Soil	Land Cover	Infiltration Factor*

Pre-Development					
	(ha)				
Phase 1 Building	14.23	-	-	-	0
Phase 1 Pavement	12.99	-	-	-	0
Phase 2 A	11.38	0.2	0.1	0.1	0.4
Phase 2 B	10.92	0.2	0.1	0.1	0.4
Phase 3	13.55	0.2	0.1	0.1	0.4
Woodland	2.32	0.2	0.1	0.2	0.5
Wetland	1.42	0.2	0.1	0.2	0.5
Wetland Buffer	3.19	0.2	0.2	0.2	0.6
NHS	4.08	0.2	0.2	0.2	0.6
Pond	0.79	0.2	0.1	0.2	0.5
Landscape	3.59	0.2	0.2	0.2	0.6
Total	78.46	-	-	-	-

*Applies only to pervious areas.

4.3 Water Balance for Pre-Development and Post-Development

With water surplus, areas of land use units and infiltration factors being determined, water balance for pre- and post-development scenarios is a simple process of accounting.

It should be noted that the land use unit post-development includes buildings and paved areas with zero infiltration and landscaped areas usually with increased infiltration owing to grading, vegetation and topsoil application. Following generally accepted practices, the impervious factors adopted for the land use units are as follows:

- Low density residential – 0.41;
- Low-medium density residential – 0.42;
- Medium density residential – 0.43;
- High density residential – 0.44;
- Commercial – 1.0;
- School – 1.0;
- Parks – 0;
- Wetland – 0;
- Stormwater Management facilities – 0.5;
- Vistas – 0.5;
- Trails – 0.5;
- Roads – 1.0;
- Natural heritage – 0;
- Farmland – 0;
- Woodland – 0;

Table 17 lists the results, which shows that the proposed development will cause a reduction of infiltration of 25,476 m³/year and an increase in runoff of 158,582 m³/year.

Table 17. Site Water Balance for Pre- and Post-Development

Pre-Development					
Land Use Unit	Area (ha)	Water Surplus (mm/year)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Farmland	71.79	288	0.4	124,053	82,702
Woodland	2.98	288	0.5	4,291	4,291
Wetland	1.42	288	0.5	2,045	2,045
Grassland	0.64	288	0.5	922	922
Grass Channel	0.84	288	0.4	1,452	968
Pond	0.79	288	0.5	1,138	1,138
Total	78.46	-	-	133,900	92,065
Post-Development					
Land Use Unit	Area (ha)	Water Surplus (mm)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Phase 1 Building	14.23	777	0	110,567	0
Phase 1 Pavement	12.99	778	0	100,932	0
Phase 2 A	11.38	288	0.4	19,665	13,110
Phase 2 B	10.92	288	0.4	18,870	12,580
Phase 3	13.55	288	0.4	23,414	15,610
Woodland	2.32	288	0.5	3,341	3,341
Wetland	1.42	288	0.5	2,045	2,045
Wetland Buffer	3.19	288	0.6	3,675	5,512
NHS	4.08	288	0.6	4,700	7,050
Pond	0.79	288	0.5	1,138	1,138
Landscape	3.59	288	0.6	4,136	6,204
Total	78.46	-	-	292,482	66,588
Pre- to Post- Development Change				+158,582	-25,476
Pre- to Post- Development Change (%)				+118%	-28%

4.4 LID Design Considerations

As mentioned above, the site is not located in any designation area of source protection, to maintain pre-development water balance is not a mandatory condition for the proposed development under the source protection plan. However, considering the large increased runoff and reduces infiltration due to the proposed development, Low Impact Development (LID) features, as a best management practice, should be considered to control flooding and erosion at downstream areas and to maintain infiltration as far as reasonably practical.

Based on the Low Impact Development Stormwater Management Planning and Design Guide (CVC and TRCA), the major site constraints are low infiltration rate and shallow groundwater table. As presented above, the infiltration rate of soil samples at the site ranges from 1.19 to 3.5 cm/min (T-time of 27 to 85), indicating the soils are weak in taking in water. Therefore, LID features with shallow depth and large area should be considered.

Groundwater level monitoring recorded shallow groundwater table depths ranging from 0.1 to 2.7 mbgs (**Table 6**). In general, the bottom of LID features should stay 1 m above groundwater table. As the site is partly located within an HVA as presented in Section 3.3, clean water is preferred to be directed to infiltration-based LIDs. This would include rooftop runoff and runoff from grassed and vegetated areas.

To boost infiltration, the client proposed a three rainwater harvesting tanks (Tank A, B, D) and three infiltration tanks (Tank C, E, F). The three infiltration tanks have invert elevations ranging from 236.85 masl for Tank C, 236.03 masl for Tank E and 236.06 masl for Tank F. Based on recorded groundwater levels, the one meter of separation could be maintained.

Based on the Stormwater Management Implementation Report (Crozier 2024), the three infiltration tanks have a combined footprint of 1,500 m². Based on infiltration of 0.94 cm/min, the Phase 1 Building could provide clean roof runoff of 110,567 m³/year (142,300 x 0.777 = 110,567 m³/yr). Both infiltration capacity of the infiltration tanks and the available clean roof runoff are greater than the infiltration deficit, therefore the infiltration deficit will be fully compensated.

5. Feature-Based Water Balance Assessment

Feature-Based Water Balance Assessment (FBWBA) was conducted in general accordance with the guidelines of Hydrogeological Assessment Submissions, Conservation Authority Guidelines to Support Development Applications (2013) and the Overview of Water Balance Practices in the Greenbelt (Ryan Post and Devon Owens, 2020). Basically, the FBWBA for this study breaks into following steps:

- Water surplus estimation;
- Catchment area delineation and infiltration factor determination for pre- and post-development scenarios; and
- Pre- and post-development Water balance analysis.

The FBWBA will focus on Phase 1 development as no post-development drainage information is available for future Phase 2 and Phase 3 developments.

5.1 Water Surplus

Water surplus values used for FBWBA will be the same as what had been derived for site water balance analysis as presented above, which includes:

- 288 mm/year for pervious area.
- 777 mm/year for impervious area.

5.2 Catchment Delineation and Infiltration Factor

Delineation of units of catchment to each subject wetland was based on topography, surficial soil, land cover and storm sewers alignment at the site for current site conditions (pre-development) and the conditions after the completion of the proposed development (post-development). **Figure 10** and **Figure 11** shows the delineation of catchment areas for pre-development and post-development.


The area of catchment units was measured with the aid of GIS and available site plans (**Appendix A**). It should be noted that the roof of Building 1 accounts for substantial part of the catchment area post-development. It was assumed that half of the area of Building 1 roof discharges into East Wetland catchment and the other half discharges into West Wetland catchment.

The Infiltration factor for each catchment units was calculated based on the scoring table presented in the Page 3-4 of the Stormwater Management Planning and Design Manual of MECP (2003) and in the Page 4-62 of MECP Hydrogeological Technical Information Requirements for Land Development Applications (1995). **Table 18** summarizes the results of catchment area delineation and infiltration factors for pre- and post- development scenarios for the East Wetland.

Table 18. Catchment Areas and Infiltration Factor for East Wetland



Pre-Development					
Catchment Unit	Area (ha)	Slope Gradient	Soil	Land Cover	Infiltration Factor
Wetland	0.46	0.2	0.1	0.2	0.5
Woodland/Shrub	0.07	0.2	0.1	0.2	0.5
Farmland	5.54	0.2	0.1	0.1	0.4
Total	6.08	-	-	-	-
Post-Development					
Catchment Unit	Area (ha)	Slope Gradient	Soil	Land Cover	Infiltration Factor*
Roof of Building 1	7.16	-	-	-	0.0
Paved Area	3.98	-	-	-	0.0
Woodland/Shrub	0.07	0.2	0.1	0.2	0.5
Wetland	0.46	0.2	0.1	0.2	0.5
Landscaped Area	1.59	0.2	0.1	0.2	0.5
Wetland Buffer	3.08	0.2	0.1	0.1	0.4
Total	16.34	-	-	-	-

*Apply to pervious area only.



LEGEND

-  Site Boundary
-  East Wetland
-  West Wetland
-  Topo Contour (1m)
-  Catchment of East Wetland
-  Catchment of West Wetland




North American Datum 1983, UTM Zone 17N (EPSG: 26917)

Scale: 1:7,000
Page Size: Letter (11 x 8.5 inches)





Drawn: FL
Checked: JC
Date: Aug 2024
Source Notes:
Basemap - Google Satellite (2020)
Topo Contour - Peel Region (Spring 2021)




CLIENT	Prologis
PROJECT	12519 & 12713 Humber Station Road, Bolton, Ontario
TITLE	Pre-Development Catchment Delineation



LEGEND

-  Site Boundary
-  East Wetland
-  West Wetland
-  Topo Contour (1m)
-  Catchment of East Wetland
-  Catchment of West Wetland



North American Datum 1983
 Universal Transverse Mercator Projection Zone 17

Scale: 1:7,000
 Page Size: Letter (11 x 8.5 inches)

Drawn: FL
 Checked: JC
 Date: Aug 2024
 Source Notes:
 Basemap - Google Satellite (2020)
 Topo Contour - Peel Region (Spring 2021)



CLIENT	Prologis
PROJECT	12519 & 12713 Humber Station Road, Bolton, Ontario
TITLE	Post-Development Catchment Delineation

Table 19. Catchment Areas and Infiltration Factor for West Wetland

Pre-Development					
Catchment Unit	Area (ha)	Slope Gradient	Soil	Land Cover	Infiltration Factor
Grassland	0.94	0.2	0.1	0.1	0.4
Woodland/shrub	2.30	0.2	0.1	0.2	0.5
Wetland	0.78	0.2	0.1	0.2	0.5
Farmland	16.46	0.2	0.1	0.1	0.4
Total	20.48	-	-	-	-
Post-Development					
Catchment Unit	Area (ha)	Slope Gradient	Soil	Land Cover	Infiltration Factor*
Roof of Building 1	7.16	-	-	-	0.0
Paved Area	3.50	-	-	-	0.0
Grassland	0.94	0.2	0.1	0.2	0.5
Woodland/shrub	2.30	0.2	0.1	0.2	0.5
Wetland	0.78	0.2	0.1	0.2	0.5
Landscaped Area	0.19	0.2	0.1	0.2	0.5
Farmland	15.45	0.2	0.1	0.1	0.4
Total	30.32	-	-	-	-

5.3 Feature-Based Water Balance for Pre-Development and Post-Development

With water surplus, area of catchment units and infiltration factors being determined, water balance for pre- and post-development scenarios are a process of accounting. **Table 20** and **Table 21** list the water balance results for East and West Wetlands for pre- and post-development conditions. The water balance results show that the proposed Phase One development will result in an increased runoff of 86,633 m³/year and reduced infiltration of 1,012 m³/year in the East Wetland catchment, and an increased runoff of 81,353 m³/year and reduced infiltration of 678 m³/year in the East Wetland catchment.

Table 20. Feature Water Balance for East Wetland

Pre-Development					
Catchment Unit	Area (ha)	Water Surplus (mm/year)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Wetland	0.46	288	0.5	661	661
Woodland/Shrub	0.07	288	0.5	105	105
Farmland	5.54	288	0.4	9,581	6,387
Total	6.08			10,347	7,153
Post-Development					

November 21, 2024

Pre-Development					
Catchment Unit	Area (ha)	Water Surplus (mm)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Roof of Building 1	7.16	777	0.0	55,642	0
Paved Area	3.98	777	0.0	30,955	0
Woodland/Shrub	0.07	288	0.5	105	105
Wetland	0.46	288	0.5	661	661
Landscaped Area	1.59	288/777	0.5	4,302	1,831
Wetland Buffer	3.08	288	0.4	5,315	3,543
Total	16.34			96,980	6,141
Pre- to Post- Development Change				86,633	-1,012
Pre- to Post- Development Change (%)				837%	-14%

Table 21. Feature Water Balance for West Wetland

Pre-Development					
Catchment Unit	Area (ha)	Water Surplus (mm/year)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Grassland	0.94	288	0.40	1,630	1,086
Woodland/shrub	2.30	288	0.50	3,313	3,313
Wetland	0.78	288	0.50	1,122	1,122
Farmland	16.46	288	0.40	28,443	18,962
Total	20.48			34,508	24,484
Post-Development					
Catchment Unit	Area (ha)	Water Surplus (mm)	Infiltration Factor	Runoff (m ³ /year)	Infiltration (m ³ /year)
Roof of Building 1	7.16	777	0.00	55,642	0
Paved Area	3.50	777	0.00	27,223	0
Grassland	0.94	288	0.50	1,358	1,358
Woodland/shrub	2.30	288	0.50	3,313	3,313
Wetland	0.78	288	0.50	1,122	1,122
Landscaped Area	0.19	288/777	0.50	512	218
Farmland	15.45	288	0.40	26,691	17,794
Total	30.32			115,861	23,805
Pre- to Post- Development Change				81,353	-678
Pre- to Post- Development Change (%)				221%	-4%

5.4 Retained Natural Heritage Features Protection

The above FBWB shows that the proposed Phase One development will result in an increased runoff of 86,633 m³/year and reduced infiltration of 1,012 m³/year in the East Wetland catchment, and an increased runoff of 81,353 m³/year and reduced infiltration of 678 m³/year in the East Wetland catchment. Monitoring results, site observation and stratigraphy all proved that both wetlands do not receive groundwater discharge contribution. Therefore, the reduced infiltration will not have impact to the hydroperiod of both wetlands. Consequently, the minor reduction of infiltration within the catchment of each wetland will not adversely impact the wetlands. Runoff should be properly managed through the proposed SWM Plan to prevent the increased runoff to end up in both wetlands. Through the establishment of wetland setbacks and new compensation areas in the Eastern Wetland catchment, and the creation of a new, higher functioning drainage channel in the Western Wetland catchment, no impacts to wetland hydrology or hydrogeology is expected.

6. Impact Assessment and Mitigation

The construction and operation of the proposed development both have the potential to cause quantity and quality impact of groundwater to natural heritage, municipal water sources and private water supply. Impact assessment is based on the understanding of the physical and environmental settings of the site, the knowledge of the site subsurface condition, results of dewatering assessment and water balance assessment, as well as the nature of construction and operation of the proposed development. The following presents the assessment of impact to each major resource and environmental features and ways of mitigation if the impact is negative.

6.1 Natural Heritage Features

The major heritage features identified within and nearby the site include Goreway Drive Tributary, Clarkway Drive Tributary and associated West Wetland and East Wetland.

The above FBWB shows that the proposed Phase One development will lead to an increased runoff of 86,633 m³/year and reduced infiltration of 1,012 m³/year in the East Wetland catchment, and an increased runoff of 81,353 m³/year and reduced infiltration of 678 m³/year in the East Wetland catchment. If the stormwater is managed as recommended, the impact to the wetland and creeks will be insignificant,

The construction dewatering is of short term and will be discharged on site. The impact of construction dewatering to natural heritage features is not anticipated.

No impacts to groundwater supported natural heritage features is expected from the proposed development.

6.2 Source Water Protection

As presented above, the site is not located in WHPA-Q1 and WHPA-Q2, and to maintain site water balance post-development is not mandatory by source protection policies. The proposed infiltration tanks will fully compensate the infiltration deficit caused by the increased impervious area.

Two isolated areas within the site are located above a Highly Vulnerable Aquifer with a vulnerable score of 6. To prevent the potential impact to the HVA, a spill management plan generated and executed by the contractors should be enough to protect the HVA.

6.3 Private Water Wells

As presented above, the water supply for the area surrounding the site was provided by Peel Region through Palgrave - Caledon East Drinking Water System, and all domestic wells were constructed before 1994. Using private wells for drinking water supply is not anticipated within and surrounding the site. However, it can not be ruled out that certain wells are still being used for livestock and other purposes. Considering the low groundwater recharge, small dewatering rate and influence zone, the impact of reduced groundwater recharge and the short-term construction dewatering to the private water wells are not expected.

A private well survey and if needed, a monitoring program, can occur during the construction phase of the project.

6.4 Discharge Receiver

As presented above, the pumped water for the purpose of conduction dewatering is recommended to be discharged onto surface land. The major potential impact of the discharged water is flooding and erosion. Considering the limited dewatering rate and influence zones, flooding and erosion are not expected.

7. Conclusions and Recommendations

Based on the above site characterization, dewatering assessment and site and site water balance assessment, conclusions and recommendations are presented as follows:

- The site is underlain with over 20 m thick overburden sediments that consist of silt to clay till and silt of the Halton Till formation within investigation depths. Significant aquifers are not identified under the site;
- Groundwater levels from monitoring wells range from 0.2 to 2.9 mbgs at the site with a predominant horizontal groundwater flow direction from northwest to southeast, towards the tributary of West Humber River. Weak vertical gradients were identified in certain depths and certain area within and surrounding the site;
- Groundwater level and surface water level data from mini-piezometers do not show hydraulic connection between groundwater and surface water, indicating that groundwater does not support stream flow and associated wetlands and shallow ponds. Therefore, groundwater does not take part in forming the hydroperiod of these features;
- Hydraulic conductivity values range from the orders of 6.0×10^{-10} to 6.6×10^{-7} m/s, generally increasing with depths and grain size of formations. The infiltration rate for shallow formations has a geometric value of 2.3 cm/min and T-time of 56;

- Groundwater quality is fresh and no visual or olfactory evidence of contamination such as visible petroleum hydrocarbon film or sheen as well as smell and odor were recorded during drilling or sampling. A number of exceedances were identified over ODWS and PWQO. These exceedances are mostly associated with fine particle materials in natural groundwater caused by the sampling process or agricultural operation and will be easily removed through settling and filtration;
- The construction dewatering analysis shows that the required dewatering rate for a typical construction working face is 6,018 L/day, which is far under the threshold of 50,000 L/day for consideration of EASR and PTTW. Therefore, neither an EASR registration nor a PTTW application is required. Potential possible stormwater accumulation is provided for client's reference only;
- The site water balance analysis shows the proposed Phase 1 development will cause a reduction of infiltration of 25,476 m³/year and an increase in runoff of 158,582 m³/year. The proposed infiltration tank will fully compensate the infiltration deficit.
- FBWB conducted for Phase One development shows that the development will result in an increased runoff of 86,633 m³/year and reduced infiltration of 1,012 m³/year in the East Wetland catchment, and an increased runoff of 81,353 m³/year and reduced infiltration of 678 m³/year in the West Wetland catchment. As neither the East Wetland and West Wetland receive groundwater discharge contribution, the minor reduction of infiltration within the catchment of each wetland will not adversely impact the wetlands. Runoff should be properly managed through the proposed SWM Plan to prevent the increased runoff to end up in the both wetlands. Through the establishment of wetland setbacks and new compensation areas in the Eastern Wetland catchment, and the creation of a new, higher functioning drainage channel in the Western Wetland catchment, no impacts to wetland hydrology or hydrogeology is expected;
- The water taking for construction dewatering is of short term, and of limited quantity and influence zones. The impacts of construction dewatering to natural heritage features and private wells are not expected.

The above hydrogeological assessment is based on the assumptions that the client and the contractors will undertake the execution and construction of the project following all applicable codes, regulations, guidelines and BPMs, and these assumptions will end up being realized through actual construction activities. This hydrogeological report should be considered preliminary until the final project design can be assessed. Groundwater systems and other natural systems are highly complex and can have significant uncertainties between borehole locations. Additional hydrogeological testing is expected to be required as the project moves forward.

8. Signatures

This report was prepared, reviewed and approved by the undersigned.



Prepared By: _____

Frank C. Liu, P.Eng.
Senior Hydrogeologist



Reviewed By: _____

Jason Cole, M.Sc., P.Geo.
Technical Discipline Manager, Hydrology and Hydrogeology

Limitations of Report

The extent of this study was limited to the specific scope of work for which we were retained and that is described in this report. Palmer has assumed that the information provided by the client or any secondary sources of information are factual and accurate. Palmer accepts no responsibility for any deficiency, misstatement or inaccuracy contained in this report as a result of omissions, misinterpretations or negligent acts from relied upon data. Judgment has been used by Palmer in the interpretation of the information provided but subsurface physical and chemical characteristics may differ from regional scale geology mapping and vary between or beyond well/borehole locations given the inherent variability in geological conditions.

Palmer is not a guarantor of the geological or groundwater conditions at the subject site, but warrants only that its work was undertaken and its report prepared in a manner consistent with the level of skill and diligence normally exercised by competent geoscience professionals practicing in the Province of Ontario. Our findings, conclusions and recommendations should be evaluated in light of the limited scope of our work.

The information and opinions expressed in the Report are for the sole benefit of the Client. NO OTHER PARTY MAY USE OR RELY UPON THE REPORT OR ANY PORTION THEREOF WITHOUT PALMER'S WRITTEN CONSENT AND SUCH USE SHALL BE ON SUCH TERMS AND CONDITIONS AS PALMER MAY EXPRESSLY APPROVE. Ownership in and copyright for the contents of the Report belongs to Palmer. Any use which a third party makes of the Report is the sole responsibility of such third party. Palmer accepts no responsibility whatsoever for damages suffered by any third party resulting from use of the Report without Palmer's express written permission. Should the project design change following issuance of the Report, Palmer must be provided the opportunity to review and revise the Report in light of such alteration or variation.


References

- Geotechnical Investigation Report by Pinchin in 2022
- Supplemental Geotechnical Investigation – Proposed Industrial Development, Pinchin 2023
- Hydrogeological Investigation Report by IBI Group in 2022
- Armstrong D.K. and Dodge J.E.P. 2007:
Paleozoic geology of southern Ontario; Ontario Geological Survey, Miscellaneous Release-Data 219.
- Bedrock Geology, OGSEarth, Ministry of Energy, Northern Development and Mines, August 2019
- Chapman, L.J. and Putnam, D.F.
The Physiography of Southern Ontario, 1984, Ontario Geological Survey.
- MNDM. Ontario Geology Survey, Central Database
- MECP. MAP Well Records of Ontario
- MECP. Ontario Source Protection Atlas.
- MECP. Provincial Groundwater Monitoring Network
- Ontario Regulation 63/16, MECP
- Ontario Geological Survey (OGS). 2007:
Paleozoic geology of Southern Ontario; Ontario Geological Survey, Map 2544
- Surficial Geology, OGSEarth, Ministry of Energy, Northern Development and Mines, August 2019
- Water Well Information System (WWIS) of Ontario, Dataset

Appendix A


Site Plans

(Prologis 2023, Crozier 2024)



300 TOWN CENTRE BLVD.
SUITE 300
MARKHAM, ONTARIO
L3R 9R9
P. 905.470.2000
F. 905.470.2000
www.petroff.com

PETROFF



ADDRESS:
PLAN OF SURVEY OF
1519-072 HUMBER STATION ROAD
TOWN OF CALEDON
REGIONAL MUNICIPALITY OF PEEL

SITE SPECIFIC ZONING TO BE DETERMINED UPON CONSULTATION WITH TOWN OF CALEDON.
MASTER PLAN LAYOUT TO BE SUBJECT TO IMPLEMENTATION OF ENVIRONMENTAL, STORM WATER MANAGEMENT, ETC. REQUIREMENTS UPON CONSULTATION WITH AUTHORITIES HAVING JURISDICTION.

NOTE: ALL SURVEY INFORMATION FROM DAVID B. CHARLES SURVEYORS INC. (DATE: JULY 4, 2022), ONTARIO LAND SURVEYOR.

REV #	DATE	REVISION TITLE
1	NOV 14, 2023	ISSUED FOR CLIENT
2	APR 19, 2014	ISSUED FOR PERMITS

PROJECT NO.: 220505
DRAWN BY: EB
CHECKED BY: RL

NOT RELEASED FOR CONSTRUCTION
RELEASED FOR CONSTRUCTION



PROJECT TITLE:
HUMBER STATION DISTRIBUTION CENTRE
TOR900009
HUMBER STATION ROAD
CALEDON, ONTARIO

PROLOGIS
Prologis Inc. (Canada)
105 The West End, Suite 700, Toronto
M6C 2S6, ONTARIO
https://www.prologis.com

SHEET TITLE:
SITE PLAN





SEAL:
Professional Engineer
Ontario
Date of Issue: 2023-11-14

SHEET NO.:
A100.0



ZONING COMPLIANCE CHART

	REQUIRED	PROPOSED		
ZONING		MP		
LOT AREAS			SITE AREA	±178.46 HA
EXT. SIDE YARD (MIN)	925 SM	±143,215 SM	UNDEVELOPABLE AREA	±11.71 HA
REAR YARD (MIN)	30 M	1,129 M	STREET A	±17.74 HA
INT. SIDE YARD (MIN)			PHASE 1	±29.16 HA
BUILDING HEIGHTS (MAX)			PHASE 2A	±11.38 HA
LANDSCAPE (MIN)	15 M (RES), 7.5 M	368 M	PHASE 2 B	±10.92 HA
PLANTING STRIP WIDTH (MIN)	15 M	81 M	PHASE 3	±13.55 HA
DRIVEWAY SETBACK (MIN)	1.5 M, 4.5 M (RES)	58 M	PROP. IND. BUILDING 1	±143,222 SM
PARKING SETBACK (MIN)	6M (FRONT YARD), 3M	208 M	PARKING	678 CARS
			TRAILER PARKING	391 SPACES
			LOADING DOCKS	172 SPACES
			TOTAL LANDSCAPE	±43,062 SM
			SOFTSCAPE	±40,067 SM
			HARDSCAPE	±2,995 SM
			COVERAGE	18.25% (TOTAL SITE)



NOT FOR CONSTRUCTION

1. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF C.F. CROZIER & ASSOCIATES INC. AND THE MODIFICATION AND/OR REPRODUCTION OF ANY PART OF THIS DRAWING IS STRICTLY PROHIBITED WITHOUT WRITTEN AUTHORIZATION FROM THIS OFFICE.
 2. THE DIGITAL FILES CONTAIN INTELLECTUAL AND DIGITAL DATA PROPERTY THAT IS THE EXCLUSIVE PROPERTY OF C.F. CROZIER & ASSOCIATES INC. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, LEVELS, AND DATUMS ON SITE AND REPORT ANY DISCREPANCIES OR OMISSIONS TO C.F. CROZIER & ASSOCIATES INC. PRIOR TO CONSTRUCTION.
 3. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH ALL OTHER PLANS AND DOCUMENTS APPLICABLE TO THIS PROJECT.
 4. ALL EXISTING UNDERGROUND UTILITIES TO BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
 5. DO NOT SCALE DRAWINGS.

TEMPORARY BENCHMARKS:
 ELEVATION ARE REFERRED TO THE REGION OF PEEL BENCHMARK NO. 40 LOCATED ON THE SOUTH FACE AT THE WEST CORNER OF SOUTH END OF A CONCRETE BOX COLLECTOR ACROSS HAVFIELD ROAD APPROXIMATELY 0.56 KM EAST OF CLARKWAY DRIVE, HAVING AN ELEVATION OF 222.165 m. VERTICAL DATUM: CANADIAN GEODETIC DATUM, 1928 (1978 SOUTHERN ONTARIO READJUSTMENT)


SITE PLAN NOTES:
 DESIGN ELEMENTS ARE BASED ON SITE PLAN PLATOFF.
 DRAWING No.: A102.0, DATED: 18/APR/2024
 PROJECT No.: 22095.00

No.	ISSUE	DATE: MM/DD/YYYY	Prepared	Engineer	Project
0	ISSUED FOR DRAFT PLAN OF SUBDIVISION	APR/19/2024			

HUMBER STATION DISTRIBUTION CENTRE
 TOWN OF CALEDON

Overall Servicing Plan

Drawn By: V.M./J.G. Design By: V.M./J.G. Project: 624-6777
 Check By: H.S. Date By: H.S. Drawn: C200



1. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF C.F. CROZIER & ASSOCIATES INC. AND THE MODIFICATION AND/OR REPRODUCTION OF ANY PART OF THIS DRAWING IS STRICTLY PROHIBITED WITHOUT WRITTEN AUTHORIZATION FROM THIS OFFICE.
 2. THE DIGITAL FILES CONTAIN INTELLECTUAL AND DIGITAL DATA PROPERTY THAT IS THE EXCLUSIVE PROPERTY OF C.F. CROZIER & ASSOCIATES INC. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, LEVELS, AND DATUMS ON SITE AND REPORT ANY DISCREPANCIES OR OMISSIONS TO C.F. CROZIER & ASSOCIATES INC. PRIOR TO CONSTRUCTION.
 3. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH ALL OTHER PLANS AND DOCUMENTS APPLICABLE TO THIS PROJECT.
 4. ALL EXISTING UNDERGROUND UTILITIES TO BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
 5. DO NOT SCALE DRAWINGS.

TEMPORARY BENCHMARKS:
 ELEVATION ARE REFERRED TO THE REGION OF PEEL BENCHMARK NO. 40 LOCATED ON THE SOUTH FACE AT THE WEST CORNER OF SOUTH END OF A CONCRETE BOX CULVERT ACROSS HAVFIELD ROAD APPROXIMATELY 0.56 KM EAST OF CLARKWAY DRIVE, HAVING AN ELEVATION OF 222.165 m. VERTICAL DATUM: CANADIAN GEODESIC DATUM, 1928 (1978 SOUTHERN ONTARIO READJUSTMENT)

SITE PLAN NOTES:
 DESIGN ELEMENTS ARE BASED ON SITE PLAN PLT/07F.
 DRAWING NO.: A100.0, DATED: 18/APR/2024
 PROJECT NO.: 22095.00

No.	ISSUE	DATE: MM/DD/YYYY	Engineer
0	ISSUED FOR DRAFT PLAN OF SUBDIVISION	APR/19/2024	

HUMBER STATION DISTRIBUTION CENTRE
 TOWN OF CALEDON

Overall Grading Plan

NOT FOR CONSTRUCTION

Drawn By: V.M./J.G. Design By: V.M./J.G. Project: 624-6777
 Check By: M.S. Check By: H.S. Drawn: C300

Appendix B

Well Logs

(Pinchin 2022, IBI 2022)



Log of Borehole: BH1

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation

Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario

Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength		Water Content		
									□	20	40	60	△	kPa	△	•
0		Ground Surface	239.28													
0		Topsoil Dark brown silt, trace sand, with organics - 150 mm	238.52		SS	1	80	5								
1		Silt Brown with some grey mottling clayey silt trace sand and gravel, with some oxidation, firm, WTPL	237.76		SS	2	100	15								
2		Silt, some clay, trace sand and gravel, compact, moist	237.00		SS	3	100	22								
2		Silt, trace sand, gravel and clay	237.00		SS	4	100	35								
3		Brownish grey, dense	236.24		SS	5	100	35								
3		Grey, trace orange oxidation	236.24		SS	6	100	24								
4			234.71													
5		compact	234.71		SS	7	100	>50								
6		Silt some sand and gravel, moist	233.19													
6			232.73													
7		End of Borehole														
7		Borehole terminated at 6.6 mbgs.														
8																
9																

Contractor: TEC

Grade Elevation: 239.28 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 240.36 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH9

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation

Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario

Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE							
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value	Shear Strength kPa	Water Content %
									□ 20 40 60 □	△ 100 200 △	● 10 20 ●
0		Ground Surface	235.57								
0		Topsoil Dark brown silt, trace sand, with organics - 150 mm	234.81		SS	1	100	8			
1		Silt Brown with some grey mottling silt, some clay, trace sand with some oxidation, loose, moist	234.05		SS	2	100	25			
1.5		Compact			SS	3	100	28			
2		Silt, some clay, trace sand and gravel	233.28		SS	4	100	37			
2.5		Dense			SS	5	100	38			
3		Brownish grey silt, trace sand, gravel and clay	232.52		SS	6	100	56			
4.5		Grey, very dense	231.00		SS	7	100	64			
6.6		End of Borehole Borehole terminated at 6.6 mbgs.	229.02								
8				Water level = 1.78 mbgs. As measured on April 25, 2022							

Contractor: TEC

Grade Elevation: 235.57 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 236.69 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH12

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation


Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario


Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength		Water Content		
									□	20	40	60	△	kPa	△	•
0		Ground Surface	237.15													
		Topsoil Dark brown silt, trace sand, with organics - 150 mm	236.39		SS	1	100	8								
1		Silt Brown with some grey mottling silt, some clay, trace sand and gravel with some oxidation, loose, wet	235.63		SS	2	100	21								
2		Reddish brown clayey silt, trace sand, very stiff, APL-WTPL	234.86		SS	3	100	15								
		Brown, silt some sand trace clay, compact, moist	234.10		SS	4	100	53								
3		Greyish brown sandy silt, trace gravel, very dense	232.58		SS	5	100	30								
4		Silt some clay and sand, trace gravel, dense, moist	231.05		SS	6	100	>50								
5		Wet, very dense	230.60		SS	7	100	81								
6		Grey sandy silt some clay, trace gravel														
7		End of Borehole														
8		Borehole terminated at 6.6 mbgs.														
9																



Water level = 1.15 mbgs. As measured on April 25, 2022



Contractor: TEC

Grade Elevation: 237.15 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 238.17 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH13

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation


Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario


Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength kPa		Water Content %		
									□	20	40	60	△	100	200	△
0		Ground Surface	237.42													
0		Topsoil Dark brown silt, trace sand, with organics - 150 mm	236.66		SS	1	80	7								
1		Silt Reddish brown with some grey mottling silt, some clay, trace sand, loose, wet	235.90		SS	2	60	16								
2		Compact Silt, some clay, trace sand and gravel	234.37		SS	3	50	23								
3		Silt, trace sand, gravel and clay, dense, moist	232.85		SS	4	50	50								
4		Grey silt, trace sand and gravel	231.32		SS	5	10	>50								
6		End of Borehole														
7		Borehole terminated at 6.1 mbgs.														
8																
9																



Water level = 1.38 mbgs, As measured on April 25, 2022



Contractor: TEC

Grade Elevation: 237.42 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 238.49 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH15

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation

Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario

Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE							
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value	Shear Strength kPa	Water Content %
									□ 20 40 60 □	△ 100 200 △	● 10 20 ●
0		Ground Surface	234.02								
0		Topsoil Dark brown silt, trace sand, with organics - 150 mm	233.26		SS	1	100	11			
1		Silt Reddish brown clayey silt, trace sand and gravel, very stiff, APL	232.50		SS	2	100	21			
1		brown silt, some clay, trace sand and gravel, compact, moist			SS	3	100	20			
2		Reddish brown									
3		Greyish brown, dense	230.97		SS	4	100	31			
4											
5					SS	5	100	32			
6		Grey silt, trace sand, very dense, moist	227.92								
6			227.47		SS	6	100	>50			
7		End of Borehole									
7		Borehole terminated at 6.6 mbgs.									
8				Water level = 2.0 mbgs, as measured on April 25, 2022							
9											

Contractor: TEC

Grade Elevation: 234.02 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 235.12 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH18

Project #: 308567.001

Logged By: KS

Project: Geotechnical Investigation

Client: Prologis

Location: 12519 & 12713 Humber Station Drive, Caledon, Ontario

Drill Date: April 16, 2022

Project Manager: SA

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength		Water Content		
									□	20	40	60	△	kPa	△	●
0		Ground Surface	232.61													
0		Topsoil Dark brown silt, trace sand, with organics - 150 mm	231.85		SS	1	75	6								
1		Silt Reddish brown with some grey mottling clayey silt, firm, WTPL	231.09		SS	2	60	19								
2		Mottled grey/brownsilt some clay, trace sand and gravel, compact, moist			SS	3	80	22								
2		Silt, some clay, trace sand and gravel														
3		Dense	229.56		SS	5	80	43								
4																
5		Grey sandy silt, some clay, trace gravel	228.04		SS	6	20	>50								
6																
7		End of Borehole	226.06		SS	7	10	>50								
7		Borehole terminated at 6.6 mbgs.														
8																
9																

Contractor: TEC

Grade Elevation: 232.61 masl

Drilling Method: Solid Stem Augers

Top of Casing Elevation: 233.66 masl

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH103(MW)

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: January 27, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis
									20	40	60					
0		Ground Surface	238.72													
0		Topsoil Dark brown silt, trace sand, with organics - 150mm	0.00		SS	1	65	6					20.9			
1		Silty Clay Till Brown with some grey mottling silty clay, trace gravel, firm, DTPL	237.20		SS	2	95	19					14.8			
2		with black staining, trace oxidation, hard	236.44		SS	3	85	34					15.9			
2		trace gravel and rock, hard, APL	236.44		SS	4	80	31					13.4			
3		trace orange oxidation, very stiff, DTPL	235.67		SS	5	100	27					13.1			
4			234.15													
5		Grey	4.57		SS	6	100	28					12.8			
6		Silty Sand Grey silty sand, trace gravel, very dense, moist	232.63		SS	7	100	>50					6.9			
6		End of Borehole	6.10													
8		Borehole terminated at approximately 6.4 mbgs.														
9		Water Level Reading Date Water Depth (mbgs) May 26, 2023 0.6														

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 238.7 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH108(MW)

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: January 31, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE													
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ 100200	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis	
0		Ground Surface	236.71						20	40	60						
0.00		Topsoil Dark brown silt, trace sand, with organics - 150mm			SS	1	55	12					16.4				
1		Silty Clay Till Brown with some grey mottling silty clay, trace gravel, very stiff, DTPL	235.49		SS	2	55	16					16.3				
1.22		trace layer of sand with black staining, trace orange oxidation			SS	3	75	19					15.4				
2		trace grey mottling	233.66		SS	4	80	16					15.4				
3			3.05		SS	5	100	27					17.1				
4					SS	6	100	26					15.1				
5		trace rock	231.68														
5.03																	
6		Grey, hard, APL	230.62														
6.10																	
7		End of Borehole															
		Borehole terminated at approximately 6.4 mbgs.															
		Water Level Reading															
8		Date Water Depth (mbgs)															
		May 26, 2023 0.7															
9																	
10																	

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 236.7 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH123

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: January 20, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE													
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis	
									20	40	60						
0		Ground Surface	238.09	↑ No Monitoring Well Installed ↓													
		Topsoil Dark brown silt, trace sand, with organics - 150mm	0.00		SS	1	50	7					19.2				
1		Silty Clay Till Brown silty clay with sand, trace gravel, firm, DTPL	237.33 0.76		SS	2	80	20					19.5				
2		with some grey mottling and black staining, trace orange oxidation, very stiff	236.57 1.52		SS	3	90	40					13.4				
		hard	235.80 2.29		SS	4	75	44					12.4				
3		trace black crystal Grey	235.04 3.05		SS	5	75	31					12.9				
4		End of Borehole	234.43 3.66														
5		Borehole terminated at approximately 3.7 mbgs. At drilling completion, the borehole was open and dry.															
6																	
7																	
8																	
9																	
10																	

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 238.1 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: N/A

Sheet: 1 of 1



Log of Borehole: BH124

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: January 20, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE													
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength △ kPa △ 100 200	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis	
									20	40	60						
0		Ground Surface	239.14														
0.00		Topsoil Dark brown silt, trace sand, with organics - 150mm	238.38		SS	1	50	7					23.5				
0.76		Silty Clay Till Brown silty clay with sand, trace gravel, firm, DTPL	237.62		SS	2	75	24					16.6				
1.52		with some grey mottling, trace rock, trace orange oxidation, very stiff	236.86		SS	3	100	28					16.0				
2.29		with black staining	236.86		SS	4	100	37					13.1				
3		hard			SS	5	100	57					15.1				
4			234.57														
4.57		Sand Grey sand, trace silt, dense, moist	233.05		SS	6	15	40					12.7				
5																	
6		Sandy Silt Grey sandy silt, very dense, moist	233.05		SS	7	100	>50					6.3				
6.10		End of Borehole															
7																	
8		Borehole terminated at approximately 6.4 mbgs.															
9		Water Level Reading Date May 26, 2023 Water Depth (mbgs) 1.5															
10																	

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 239.1 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH160(MW)

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: February 8, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis
									20	40	60					
0		Ground Surface	234.19													
0.00		Topsoil Dark brown silt, trace sand, with organics - 255mm	233.43		SS	1	50	4					20.2			
0.76		Silty Clay Till Brown silty clay, some sand, soft, APL	232.67		SS	2	65	19					12.4			
1.52		trace gravel, very stiff	231.91		SS	3	80	28					13.3			
2.29		with some grey mottling and black staining, trace orange oxidation layer of sand	231.15		SS	4	100	28					12.0			
3.05		hard	229.62		SS	5	100	40					9.8			
4.57		Sandy Silt Grey sandy silt, trace gravel, very dense, moist	228.10		SS	6	75	>50					6.7			
6.10		Silt Grey silt, trace sand, very dense, moist			SS	7	100	>50					12.2			
7		End of Borehole														
8		Borehole terminated at approximately 6.4 mbgs.														
9		Water Level Reading Date May 26, 2023 Water Depth (mbgs) 1.0														
10																

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 234.2 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH161(MW)

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: February 8, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE													
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ 100200	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis	
									20	40	60						
0		Ground Surface	232.78														
		Topsoil Dark brown silt, trace sand, with organics - 255mm	0.00		SS	1	60	6					15.4				
			232.02														
			0.76														
1		Silty Clay Till Brown silty clay, firm, APL	231.26		SS	2	80	17					15.1				
		with some grey mottling, trace gravel, very stiff	1.52														
2		with black staining, trace orange oxidation	230.50		SS	3	75	28					12.3				
		Brown, hard, DTPL	2.29														
3			229.28		SS	4	40	31					11.4				
		trace rock	3.51														
4			228.21														
		Grey, very stiff	4.57		SS	6	70	20					8.4				
5			226.69														
		hard	6.10		SS	7	100	31					17.8				
			226.08														
			6.71														
7		End of Borehole															
		Borehole terminated at approximately 6.7 mbgs.															
8		Water Level Reading															
		Date Water Depth (mbgs)															
		May 26, 2023 0.6															
9																	
10																	

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 232.8 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm

Sheet: 1 of 1



Log of Borehole: BH168(MW)

Project #: 308567.002

Logged By: SL

Project: Geotechnical Investigation for Proposed Industrial Development

Client: Prologis

Location: 12519 & 12713 Humber Station Road, Caledon, Ontario

Drill Date: February 2, 2023

Project Manager: JD

SUBSURFACE PROFILE				SAMPLE												
Depth (m)	Symbol	Description	Elevation (m)	Monitoring Well Details	Sample Type	Sampler #	Recovery (%)	SPT N-Value	Standard Penetration N-Value			Shear Strength Δ kPa Δ	Water Content (%)	Sample ID	Soil Vapour Concentration (ppm)	Laboratory Analysis
									20	40	60					
0		Ground Surface	231.95													
0.00		Topsoil Dark brown silt, trace sand, with organics - 150mm			SS	1	50	5					17.2			
1		Silty Clay Till Brown with some grey mottling silty clay with sand, trace gravel, firm, APL	230.43		SS	2	50	19					14.8			
1.52					SS	3	65	24					12.3			
2		with black staining, trace orange oxidation, very stiff	229.67		SS	4	100	26					14.0			
2.29		Brown			SS	5	65	27					13.4			
3		Grey	228.91		SS	6	65	24					15.4			
3.05																
4																
5																
6		No recovery	225.86		SS	7	0	47					N/A			
6.10																
7		End of Borehole Borehole terminated at approximately 6.7 mbgs.	225.25													
6.71																
8		Water Level Reading Date May 26, 2023 Water Depth (mbgs) 0.8														
9																
10																

Contractor: Geo-Environmental Drilling Inc.

Grade Elevation: 232.0 masl

Drilling Method: Split Spoon / Hollow Stem Auger

Top of Casing Elevation: N/A

Well Casing Size: 51 mm


Sheet: 1 of 1


PROJECT DESCRIPTION: Monitoring Wells Installation

METHOD OF BORING: Hollow-Stem

PROJECT LOCATION: East side of Humber Station Road, south of Healey Road
Town of Caledon

DRILLING DATE: August 17, 2017





JOB NO.: 1707-S200

LOG OF BOREHOLE NO.: MW4-17S FIGURE NO.: 6

PROJECT DESCRIPTION: Monitoring Wells Installation

METHOD OF BORING: Hollow-Stem

PROJECT LOCATION: East side of Humber Station Road, south of Healey Road
Town of Caledon

DRILLING DATE: August 16, 2017

El. (m)	Depth (m)	SOIL DESCRIPTION	SAMPLES			Depth Scale (m)	Dynamic Cone (blows/30 cm)		Atterberg Limits		WATER LEVEL
			Number	Type	N-Value		10	30	50	70	
234.8	0.0	Ground Surface 23 cm TOPSOIL Brown _weathered SILTY CLAY TILL some sand to sandy, a trace of gravel occ. wet sand and silt seams and layers, cobbles and boulders				0					
231.2	3.6	Grey SILT some clay, a trace of sand occ. clay layers — brown grey				4					
228.8	6.0	END OF AUGER HOLE Installed 50 mm Ø monitoring well to 6.0 m completed with 3.0 m screen Sand backfill from 2.4 m to 6.0 m Bentonite seal from 0.0 m to 2.4 m Provided with a protective steel monument casing				6					

Dry on completion
 W.L. @ El. 233.6 m on August 17, 2017



Soil Engineers Ltd.

LOG OF DRILLING OPERATIONS



R.J. Burnside & Associates Limited
 16 Guelph, Ontario, N1G 3M1
 Telephone: (519) 841-8131 Fax: (519) 841-8130

MW9

Page 1 of 1

Client: Solmar Development Corp.	Project Name: Hydrogeological Investigation	Logged by: S. Goemans
Project No.: PTA 11575	Location: Caledon, Ontario	Ground (m amsl): 235.69
Drilling Co.: Lantech Drilling Services Inc.	Date Started: 11/6/2006	Static Water Level (m amsl): 234.22
Drilling Method: Hollow Stem Auger	Date Completed: 11/6/2006	Sand Pack (m amsl): 232.53 - 229.46

Depth Scale (ft) (m)	Stratigraphic Description	Strat. Plot	Depth (m)	[Diagram]	SAMPLE				Depth Scale (ft) (m)
					Num.	Type	Int.	%Recov.	
	Surface Elevation (m): 235.69								
	Dark brown TOPSOIL, moist. SS-1 (3, 3, 3, 8)		0.15		1	SS	X	40	
	Grey brown silty CLAY TILL, with pebbles and pockets of sand. Vertical fractures, iron staining, moist.								
1.0	SS-2 (6, 12, 18, 22)				2	SS	X	100	1.0
	SS-3 (6, 12, 23, 29)								
5.0	SS-4 (9, 22, 32, 40)								5.0
	SS-5 (7, 19, 41, 50)				3	SS	X	100	2.0
2.0									
					4	SS	X	100	
10.0									10.0
3.0					5	SS	X	100	3.0
4.0	Brown silty SAND, coarse to medium sand, some gravel. Wet.		3.81		6	SS	X	100	4.0
	SS-6 (30, 97)								
15.0									15.0
5.0	SS-7 (2, 7, 30, 40)				7	SS	X	100	5.0
	Brown medium sand and gravel. Saturated.		5.18						
	SS-8 (7, 18, 50)								
	Grey CLAY, uniform, wet.		5.56		8	SS	X	100	
			5.86						

Prepared By: **S. Goemans** Checked By: **D. Gevaert** Date Prepared: **11/13/2006**
 This borehole log was prepared for hydrogeological and/or environmental purposes and does not necessarily contain information suitable for a geotechnical assessment of the subsurface conditions. Borehole data requires interpretation by R. J. Burnside & Associates Limited personnel before use by others.


LEGEND Water found @ time of drilling Static Water Level - 1/11/2007	MONITORING WELL DATA Pipe: 51 mm dia. PVC Screen: 51 mm dia. PVC #10 slot	SAMPLE TYPE AC Auger Cutting CS Continuous RC Rock Core SS Split Spoon AR Air Rotary WC Wash Cuttings
---	--	---

B:\LOG GUELPH\PROJECTS\PTA11575.GPJ TEMPLATE.GDT 31/05/07

Appendix C

Single Well Response Tests

(Palmer 2022)



WELL TEST ANALYSIS

Data Set: G:\...\BH12_selfconfing.aqt

Date: 11/27/22

Time: 12:59:13

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: BH12

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 6.16 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (BH12)

Initial Displacement: 0.3656 m

Static Water Column Height: 6.16 m

Total Well Penetration Depth: 5.56 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bower-Rice

K = 5.706E-9 m/sec

y0 = 0.3101 m



WELL TEST ANALYSIS

Data Set: G:\...\BH12_selfconfing.aqt

Date: 11/30/22

Time: 17:16:10

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: BH12

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 6.16 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (BH12)

Initial Displacement: 0.3656 m

Static Water Column Height: 6.16 m

Total Well Penetration Depth: 5.66 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 5.706E-9 m/sec

y0 = 0.3101 m



WELL TEST ANALYSIS

Data Set: G:\...\BH15_selfconfining.aqt

Date: 11/30/22

Time: 17:29:11

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: BH15

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 3.77 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (bh15)

Initial Displacement: 0.5545 m

Static Water Column Height: 3.41 m

Total Well Penetration Depth: 3.41 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 5.353E-8 m/sec

y0 = 0.517 m



WELL TEST ANALYSIS

Data Set: G:\...\BH18_Self Confining.aqt

Date: 11/30/22

Time: 14:59:34

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Date: Nov 29, 2022

AQUIFER DATA

Saturated Thickness: 4.78 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (BH18)

Initial Displacement: 0.4408 m

Static Water Column Height: 4.52 m

Total Well Penetration Depth: 4.52 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 7.683E-8 m/sec

y0 = 0.4283 m



WELL TEST ANALYSIS

Data Set: G:\...\BH9_self-confing.aqt

Date: 11/30/22

Time: 17:00:09

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: BH9

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 4.44 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (BH9)

Initial Displacement: 0.4972 m

Static Water Column Height: 3.96 m

Total Well Penetration Depth: 3.96 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 6.692E-7 m/sec

y0 = 0.3063 m



WELL TEST ANALYSIS

Data Set: G:\...\MW14-D_Confined_Beginning.aqt

Date: 11/30/22

Time: 20:17:41

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: MW4-17D

Test Date: Nov 29, 2022

AQUIFER DATA

Saturated Thickness: 9.1 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW14-D)

Initial Displacement: 0.5646 m

Static Water Column Height: 10.1 m

Total Well Penetration Depth: 8.62 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 2.928E-7 m/sec

y0 = 0.5001 m



WELL TEST ANALYSIS

Data Set: G:\...\MW14-D_Confined_End.aqt

Date: 11/30/22

Time: 20:19:14

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: MW4-17D

Test Date: Nov 29, 2022

AQUIFER DATA

Saturated Thickness: 9.1 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW14-D)

Initial Displacement: 0.5646 m

Static Water Column Height: 10.1 m

Total Well Penetration Depth: 8.62 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 1.134E-7 m/sec

y0 = 0.3781 m



WELL TEST ANALYSIS

Data Set: G:\...\MW3-17_selfconfined.aqt

Date: 11/27/22

Time: 14:27:04

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: MW3-17

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 5.99 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW3-17)

Initial Displacement: 0.266 m

Static Water Column Height: 5.5 m

Total Well Penetration Depth: 5.59 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bower-Rice

K = 7.175E-8 m/sec

y0 = 0.2716 m



WELL TEST ANALYSIS

Data Set: G:\...\MW4-17S_Selfconfining_Nov29.aqt

Date: 11/30/22

Time: 17:34:17

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: MW4-17S

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 4. m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW4-17S)

Initial Displacement: 0.6475 m

Static Water Column Height: 3.85 m

Total Well Penetration Depth: 3.85 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 1.414E-7 m/sec

y0 = 0.6065 m



WELL TEST ANALYSIS

Data Set: G:\...\MW8_self_confing.aqt

Date: 11/30/22

Time: 15:41:35

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Date: Nov 29, 2022

AQUIFER DATA

Saturated Thickness: 3.41 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW8)

Initial Displacement: 0.5431 m

Static Water Column Height: 3.32 m

Total Well Penetration Depth: 3.32 m

Screen Length: 1.5 m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.


SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 5.602E-7 m/sec

y0 = 0.3842 m



WELL TEST ANALYSIS

Data Set: G:\...\MW9_attempt1.aqt

Date: 11/30/22

Time: 17:58:51

PROJECT INFORMATION

Company: Palmer

Client: Prologis

Project: 2008102

Location: Caledon, On

Test Well: MW9

Test Date: Nov 21, 2022

AQUIFER DATA

Saturated Thickness: 2.05 m

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW9)

Initial Displacement: 0.4632 m

Static Water Column Height: 2.48 m

Total Well Penetration Depth: 1.54 m

Screen Length: 1.5 m

Casing Radius: 0.0254 m

Well Radius: 0.0254 m

Gravel Pack Porosity: 0.

SOLUTION

Aquifer Model: Confined

Solution Method: Hvorslev

K = 7.129E-7 m/sec


y0 = 0.05517 m

Appendix D

Grain Size Distributions and K-value Estimation

(Pinchin and Palmer 2022)

Unified Soil Classification System



Sample ID	Depth (ft)	% Gravel	% Sand	% Silt	% Clay
BH4 SS4	3.0-3.5	2.0	16.3	45.7	36.0
BH6 SS1	0.0-0.6	3.0	19.7	49.3	28.0
BH14 SS5	4.5-4.7	1.0	7.2	77.8	14.0
BH18 SS4	3.0-3.5	4.0	27.9	46.1	22.0



Pinchin Waterloo - 225 Labrador Drive,
Unit 1, Waterloo, Ontario N2K 4M8

PARTICLE SIZE DISTRIBUTION ANALYSIS

Proposed Industrial Development - 12519 & 12713 Humber Station Dr, Caledon, ON
Prologis

Figure No. 1

308567.001

Reviewed By: *al*

More information available upon request

Hydraulic Conductivity Report


Sample ID: BH14/SS5

Date: Feb 2023

Sample Mass (g):

T (oC): 20

Poorly sorted clay low in fines



Estimation of Hydraulic Conductivity	cm/s	m/s	m/d
Hazen	.124E-05	.124E-07	0.00
Hazen K (cm/s) = d ₁₀ (mm)	.165E-05	.165E-07	0.00
Slichter	.267E-06	.267E-08	0.00
Terzaghi	.418E-06	.418E-08	0.00
Beyer	.140E-05	.140E-07	0.00
Sauerbrei	.103E-05	.103E-07	0.00
Kruger	.128E-04	.128E-06	0.01
Kozeny-Carmen	.868E-05	.868E-07	0.01
Zunker	.613E-05	.613E-07	0.01
Zamarin	.757E-05	.757E-07	0.01
USBR	.751E-06	.751E-08	0.00
Barr	.302E-06	.302E-08	0.00
Alyamani and Sen	.494E-06	.494E-08	0.00
Chapuis	.109E-07	.109E-09	0.00
Krumbein and Monk	.296E-05	.296E-07	0.00
geometric mean	.110E-05	.110E-07	0.00
arithmetic mean	.314E-05	.314E-07	0.00

Hydraulic Conductivity Report


Sample ID: BH18/SS4

Date: Feb 2023

Sample Mass (g):

T (oC): 20

Poorly sorted silt low in fines



Estimation of Hydraulic Conductivity	cm/s	m/s	m/d
Hazen	.252E-06	.252E-08	0.00
Hazen K (cm/s) = d ₁₀ (mm)	.444E-06	.444E-08	0.00
Slichter	.495E-07	.495E-09	0.00
Terzaghi	.705E-07	.705E-09	0.00
Beyer	.185E-06	.185E-08	0.00
Sauerbrei	.166E-06	.166E-08	0.00
Kruger	.142E-04	.142E-06	0.01
Kozeny-Carmen	.482E-05	.482E-07	0.00
Zunker	.373E-05	.373E-07	0.00
Zamarin	.447E-05	.447E-07	0.00
USBR	.147E-06	.147E-08	0.00
Barr	.530E-07	.530E-09	0.00
Alyamani and Sen	.209E-04	.209E-06	0.02
Chapuis	.707E-09	.707E-11	0.00
Krumbein and Monk	.133E-05	.133E-07	0.00
geometric mean	.416E-06	.416E-08	0.00
arithmetic mean	.360E-05	.360E-07	0.00

Hydraulic Conductivity Report


Sample ID: BH4/SS4

Date: Feb 2023

Sample Mass (g):

T (oC): 20

Poorly sorted clay low in fines



Estimation of Hydraulic Conductivity	cm/s	m/s	m/d
Hazen	.972E-07	.972E-09	0.00
Hazen K (cm/s) = d ₁₀ (mm)	.160E-06	.160E-08	0.00
Slichter	.195E-07	.195E-09	0.00
Terzaghi	.285E-07	.285E-09	0.00
Beyer	.117E-06	.117E-08	0.00
Sauerbrei	.599E-07	.599E-09	0.00
Kruger	.917E-05	.917E-07	0.01
Kozeny-Carmen	.259E-05	.259E-07	0.00
Zunker	.194E-05	.194E-07	0.00
Zamarin	.233E-05	.233E-07	0.00
USBR	.359E-07	.359E-09	0.00
Barr	.211E-07	.211E-09	0.00
Alyamani and Sen	.341E-06	.341E-08	0.00
Chapuis	.210E-09	.210E-11	0.00
Krumbein and Monk	.244E-06	.244E-08	0.00
geometric mean	.133E-06	.133E-08	0.00
arithmetic mean	.121E-05	.121E-07	0.00

Hydraulic Conductivity Report


Sample ID: BH6/SS1

Date: Feb 2023

Sample Mass (g):

T (oC): 20

Poorly sorted clay low in fines



Estimation of Hydraulic Conductivity	cm/s	m/s	m/d
Hazen	.117E-06	.117E-08	0.00
Hazen K (cm/s) = d ₁₀ (mm)	.207E-06	.207E-08	0.00
Slichter	.230E-07	.230E-09	0.00
Terzaghi	.328E-07	.328E-09	0.00
Beyer	.108E-06	.108E-08	0.00
Sauerbrei	.700E-07	.700E-09	0.00
Kruger	.174E-04	.174E-06	0.02
Kozeny-Carmen	.375E-05	.375E-07	0.00
Zunker	.288E-05	.288E-07	0.00
Zamarin	.343E-05	.343E-07	0.00
USBR	.482E-07	.482E-09	0.00
Barr	.247E-07	.247E-09	0.00
Alyamani and Sen	.324E-05	.324E-07	0.00
Chapuis	.241E-09	.241E-11	0.00
Krumbein and Monk	.468E-06	.468E-08	0.00
geometric mean	.202E-06	.202E-08	0.00
arithmetic mean	.225E-05	.225E-07	0.00

Appendix E

Groundwater Chemistry Analyses

(ALS 2022, Maxxam 2017)



CERTIFICATE OF ANALYSIS (GUIDELINE EVALUATION)

<p>Work Order : WT2222750</p> <p>Client : Palmer Environmental Consulting Group Inc.</p> <p>Contact : Lauren Bourke</p> <p>Address : 74 Berkeley Street Toronto ON Canada M5V 1E3</p> <p>Telephone : ----</p> <p>Project : 2008162-HUMBER STATION RD</p> <p>PO : ----</p> <p>C-O-C number : 17-792826</p> <p>Sampler : ----</p> <p>Site : ----</p> <p>Quote number : (Q88296) PALMER 2022 STANDING OFFER</p> <p>No. of samples received : 1</p> <p>No. of samples analysed : 1</p>	<p>Page : 1 of 9</p> <p>Laboratory : Waterloo - Environmental</p> <p>Account Manager : Andrew Martin</p> <p>Address : 60 Northland Road, Unit 1 Waterloo, Ontario Canada N2V 2B8</p> <p>Telephone : +1 519 886 6910</p> <p>Date Samples Received : 21-Nov-2022 16:10</p> <p>Date Analysis Commenced : 23-Nov-2022</p> <p>Issue Date : 28-Nov-2022 17:34</p>
---	---

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results
- Guideline Comparison

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QC Interpretive report to assist with Quality Review and Sample Receipt Notification (SRN).

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

<u>Signatories</u>	<u>Position</u>	<u>Laboratory Department</u>
Amanda Ganouri-Lumsden	Department Manager - Microbiology and Prep	Microbiology, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Inorganics, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Metals, Waterloo, Ontario



Summary of Guideline Breaches by Sample

SampleID/Client ID	Matrix	Analyte	Analyte Summary	Guideline	Category	Result	Limit
BH13	Water	colour, apparent	May interfere with disinfection; removal is important to ensure effective treatment.	ONDWS	AO/OG	40.0 CU	5 CU
	Water	solids, total dissolved [TDS]	Based on taste; TDS above 500 mg/L results in excessive scaling in water pipes, water heaters, boilers and appliances; TDS is composed of calcium, magnesium, sodium, potassium, carbonate, bicarbonate, chloride, sulphate and nitrate.	ONDWS	AO/OG	689 mg/L	500 mg/L
	Water	turbidity	Filtration systems should be designed and operated to reduce turbidity levels as low as reasonably achievable and strive to achieve a treated water turbidity target from individual filters of less than 0.1 NTU. Particles can harbour microorganisms, protecting them from disinfection, and can entrap heavy metals and biocides; elevated or fluctuating turbidity in filtered water can indicate a problem with the water treatment process and a potential increased risk of pathogens in treated water.	ONDWS	AO/OG	21.4 NTU	5 NTU
	Water	manganese, total	Based on taste and staining of laundry and plumbing fixtures.	ONDWS	AO/OG	0.120 mg/L	0.05 mg/L
	Water	coliforms, total	Total coliforms are not used as indicators of potential health effects from pathogenic microorganisms; they are used as a tool to determine how well the drinking water treatment system is operating and to indicate water quality changes in the distribution system. Detection of total coliforms from consecutive samples from the same site or from more than 10% of the samples collected in a given sampling period should be investigated.	ONDWS	MAC	<10	1 CFU/100mL
	Water	sodium, total	Based on taste; where a sodium-based water softener is used, a separate unsoftened supply for cooking and drinking purposes is recommended.	ONDWS	MAC	58.4 mg/L	20 mg/L



General Comments

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Refer to the ALS Quality Control Interpretive report (QCI) for applicable references and methodology summaries. Reference methods may incorporate modifications to improve performance.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to fitness for a particular purpose, or non-infringement. ALS assumes no responsibility for errors or omissions in the information. Guidelines are not adjusted for the hardness, pH or temperature of the sample (the most conservative values are used). Measurement uncertainty is not applied to test results prior to comparison with specified criteria values.

Key : LOR: Limit of Reporting (detection limit).

<i>Unit</i>	<i>Description</i>
-	no units
%	percent
µS/cm	microsiemens per centimetre
CFU/100mL	colony forming units per hundred millilitres
CU	colour units (1 cu = 1 mg/l pt)
meq/L	milliequivalents per litre
mg/L	milligrams per litre
NTU	nephelometric turbidity units
pH units	pH units

>: greater than.

<: less than.

Red shading is applied where the result is greater than the Guideline Upper Limit or the result is lower than the Guideline Lower Limit.

For drinking water samples, Red shading is applied where the result for E.coli, fecal or total coliforms is greater than or equal to the Guideline Upper Limit.

Qualifiers

<i>Qualifier</i>	<i>Description</i>
DLDS	Detection Limit Raised: Dilution required due to high Dissolved Solids / Electrical Conductivity.
DLHC	Detection Limit Raised: Dilution required due to high concentration of test analyte(s).
DLM	Detection Limit Adjusted due to sample matrix effects (e.g. chemical interference, colour, turbidity).



Analytical Results Evaluation

Matrix: Water		Client sample ID	BH13	----	----	----	----	----	----
		Sampling date/time	21-Nov-2022 14:45	----	----	----	----	----	----
		Sub-Matrix	Water	----	----	----	----	----	----
Analyte	CAS Number	Unit	WT2222750-001	-----	-----	-----	-----	-----	-----
Physical Tests									
alkalinity, bicarbonate (as HCO3)	71-52-3	mg/L	608	----	----	----	----	----	----
alkalinity, carbonate (as CO3)	3812-32-6	mg/L	<1.0	----	----	----	----	----	----
alkalinity, hydroxide (as OH)	14280-30-9	mg/L	<1.0	----	----	----	----	----	----
alkalinity, total (as CaCO3)	----	mg/L	498	----	----	----	----	----	----
colour, apparent	----	CU	40.0	----	----	----	----	----	----
conductivity	----	µS/cm	1230	----	----	----	----	----	----
hardness (as CaCO3), from total Ca/Mg	----	mg/L	664	----	----	----	----	----	----
pH	----	pH units	7.94	----	----	----	----	----	----
solids, total dissolved [TDS]	----	mg/L	689 ^{DLDS}	----	----	----	----	----	----
solids, total dissolved [TDS], calculated	----	mg/L	800	----	----	----	----	----	----
turbidity	----	NTU	21.4	----	----	----	----	----	----
Langelier index (@ 20°C)	----	-	1.03	----	----	----	----	----	----
Langelier index (@ 4°C)	----	-	0.784	----	----	----	----	----	----
pH, saturation (@ 20°C)	----	pH units	6.91	----	----	----	----	----	----
pH, saturation (@ 4°C)	----	pH units	7.16	----	----	----	----	----	----
Anions and Nutrients									
ammonia, total (as N)	7664-41-7	mg/L	0.0642	----	----	----	----	----	----
bromide	24959-67-9	mg/L	<0.50 ^{DLDS}	----	----	----	----	----	----
chloride	16887-00-6	mg/L	9.33 ^{DLDS}	----	----	----	----	----	----
fluoride	16984-48-8	mg/L	0.228 ^{DLDS}	----	----	----	----	----	----
nitrate (as N)	14797-55-8	mg/L	<0.100 ^{DLDS}	----	----	----	----	----	----
nitrate + nitrite (as N)	----	mg/L	<0.112	----	----	----	----	----	----
nitrite (as N)	14797-65-0	mg/L	<0.050 ^{DLDS}	----	----	----	----	----	----
phosphate, ortho-, dissolved (as P)	14265-44-2	mg/L	<0.0030	----	----	----	----	----	----
sulfate (as SO4)	14808-79-8	mg/L	202 ^{DLDS}	----	----	----	----	----	----
Microbiological Tests									
coliforms, Escherichia coli [E. coli]	----	CFU/100mL	<1	----	----	----	----	----	----



Analytical Results Evaluation

Matrix: Water		Client sample ID	BH13	----	----	----	----	----	----
		Sampling date/time	21-Nov-2022 14:45	----	----	----	----	----	----
		Sub-Matrix	Water	----	----	----	----	----	----
Analyte	CAS Number	Unit	WT2222750-001	-----	-----	-----	-----	-----	-----
Microbiological Tests									
coliforms, total	---	CFU/100mL	<10 ^{DLM}	----	----	----	----	----	----
coliforms, total background	---	CFU/100mL	10 ^{DLM}	----	----	----	----	----	----
Metals									
sodium adsorption ratio [SAR]	----	-	0.98	----	----	----	----	----	----
Ion Balance									
anion sum	----	meq/L	14.4	----	----	----	----	----	----
cation sum (total)	----	meq/L	16.0	----	----	----	----	----	----
ion balance (APHA)	----	%	5.26	----	----	----	----	----	----
ion balance (cations/anions)	----	%	111	----	----	----	----	----	----
Total Metals									
aluminum, total	7429-90-5	mg/L	<0.0300 ^{DLHC}	----	----	----	----	----	----
antimony, total	7440-36-0	mg/L	0.00161 ^{DLHC}	----	----	----	----	----	----
arsenic, total	7440-38-2	mg/L	0.00225 ^{DLHC}	----	----	----	----	----	----
barium, total	7440-39-3	mg/L	0.0776 ^{DLHC}	----	----	----	----	----	----
beryllium, total	7440-41-7	mg/L	<0.000200 ^{DLHC}	----	----	----	----	----	----
bismuth, total	7440-69-9	mg/L	<0.000500 ^{DLHC}	----	----	----	----	----	----
boron, total	7440-42-8	mg/L	0.102 ^{DLHC}	----	----	----	----	----	----
cadmium, total	7440-43-9	mg/L	<0.0000500 ^{DLHC}	----	----	----	----	----	----
calcium, total	7440-70-2	mg/L	79.8 ^{DLHC}	----	----	----	----	----	----
cesium, total	7440-46-2	mg/L	<0.000100 ^{DLHC}	----	----	----	----	----	----
chromium, total	7440-47-3	mg/L	<0.00500 ^{DLHC}	----	----	----	----	----	----
cobalt, total	7440-48-4	mg/L	<0.00100 ^{DLHC}	----	----	----	----	----	----
copper, total	7440-50-8	mg/L	<0.00500 ^{DLHC}	----	----	----	----	----	----
iron, total	7439-89-6	mg/L	<0.100 ^{DLHC}	----	----	----	----	----	----
lead, total	7439-92-1	mg/L	<0.000500 ^{DLHC}	----	----	----	----	----	----
lithium, total	7439-93-2	mg/L	0.0479 ^{DLHC}	----	----	----	----	----	----
magnesium, total	7439-95-4	mg/L	113 ^{DLHC}	----	----	----	----	----	----
manganese, total	7439-96-5	mg/L	0.120 ^{DLHC}	----	----	----	----	----	----
molybdenum, total	7439-98-7	mg/L	0.0457 ^{DLHC}	----	----	----	----	----	----



Analytical Results Evaluation

Matrix: Water			Client sample ID	BH13	----	----	----	----	----	----
			Sampling date/time	21-Nov-2022 14:45	----	----	----	----	----	----
			Sub-Matrix	Water	----	----	----	----	----	----
Analyte	CAS Number	Unit	WT2222750-001	-----	-----	-----	-----	-----	-----	-----
Total Metals										
nickel, total	7440-02-0	mg/L	<0.00500 DLHC	----	----	----	----	----	----	----
phosphorus, total	7723-14-0	mg/L	<0.500 DLHC	----	----	----	----	----	----	----
potassium, total	7440-09-7	mg/L	6.68 DLHC	----	----	----	----	----	----	----
rubidium, total	7440-17-7	mg/L	0.00227 DLHC	----	----	----	----	----	----	----
selenium, total	7782-49-2	mg/L	<0.000500 DLHC	----	----	----	----	----	----	----
silicon (as SiO2), total	7631-86-9	mg/L	20.7	----	----	----	----	----	----	----
silicon, total	7440-21-3	mg/L	9.70 DLHC	----	----	----	----	----	----	----
silver, total	7440-22-4	mg/L	<0.000100 DLHC	----	----	----	----	----	----	----
sodium, total	7440-23-5	mg/L	58.4 DLHC	----	----	----	----	----	----	----
strontium, total	7440-24-6	mg/L	0.886 DLHC	----	----	----	----	----	----	----
sulfur, total	7704-34-9	mg/L	72.9 DLHC	----	----	----	----	----	----	----
tellurium, total	13494-80-9	mg/L	<0.00200 DLHC	----	----	----	----	----	----	----
thallium, total	7440-28-0	mg/L	<0.000100 DLHC	----	----	----	----	----	----	----
thorium, total	7440-29-1	mg/L	<0.00100 DLHC	----	----	----	----	----	----	----
tin, total	7440-31-5	mg/L	<0.00100 DLHC	----	----	----	----	----	----	----
titanium, total	7440-32-6	mg/L	<0.00300 DLHC	----	----	----	----	----	----	----
tungsten, total	7440-33-7	mg/L	<0.00100 DLHC	----	----	----	----	----	----	----
uranium, total	7440-61-1	mg/L	0.00836 DLHC	----	----	----	----	----	----	----
vanadium, total	7440-62-2	mg/L	<0.00500 DLHC	----	----	----	----	----	----	----
zinc, total	7440-66-6	mg/L	<0.0300 DLHC	----	----	----	----	----	----	----
zirconium, total	7440-67-7	mg/L	<0.00200 DLHC	----	----	----	----	----	----	----

Please refer to the General Comments section for an explanation of any qualifiers detected.



Summary of Guideline Limits

Analyte	CAS Number	Unit	ONDWS AO/OG	ONDWS MAC					
Physical Tests									
alkalinity, bicarbonate (as HCO ₃)	71-52-3	mg/L							
alkalinity, carbonate (as CO ₃)	3812-32-6	mg/L							
alkalinity, hydroxide (as OH)	14280-30-9	mg/L							
alkalinity, total (as CaCO ₃)	----	mg/L	30 - 500 mg/L						
colour, apparent	----	CU	5 CU						
conductivity	----	µS/cm							
hardness (as CaCO ₃), from total Ca/Mg	----	mg/L							
Langelier index (@ 20°C)	----	-							
Langelier index (@ 4°C)	----	-							
pH, saturation (@ 20°C)	----	pH units							
pH, saturation (@ 4°C)	----	pH units							
pH	----	pH units	6.5 - 8.5 pH units						
solids, total dissolved [TDS], calculated	----	mg/L							
solids, total dissolved [TDS]	----	mg/L	500 mg/L						
turbidity	----	NTU	5 NTU						
Anions and Nutrients									
ammonia, total (as N)	7664-41-7	mg/L							
bromide	24959-67-9	mg/L							
chloride	16887-00-6	mg/L	250 mg/L						
fluoride	16984-48-8	mg/L		1.5 mg/L					
nitrate (as N)	14797-55-8	mg/L		10 mg/L					
nitrate + nitrite (as N)	----	mg/L		10 mg/L					
nitrite (as N)	14797-65-0	mg/L		1 mg/L					
phosphate, ortho-, dissolved (as P)	14265-44-2	mg/L							
sulfate (as SO ₄)	14808-79-8	mg/L							
Microbiological Tests									
coliforms, Escherichia coli [E. coli]	----	CFU/100mL		1 CFU/100mL					
coliforms, total background	----	CFU/100mL							
coliforms, total	----	CFU/100mL		1 CFU/100mL					
Metals									
sodium adsorption ratio [SAR]	----	-							
Ion Balance									
anion sum	----	meq/L							
cation sum (total)	----	meq/L							
ion balance (APHA)	----	%							
ion balance (cations/anions)	----	%							



Analyte	CAS Number	Unit	ONDWS AO/OG	ONDWS MAC					
Total Metals									
aluminum, total	7429-90-5	mg/L	0.1 mg/L						
antimony, total	7440-36-0	mg/L		0.006 mg/L					
arsenic, total	7440-38-2	mg/L		0.01 mg/L					
barium, total	7440-39-3	mg/L		1 mg/L					
beryllium, total	7440-41-7	mg/L							
bismuth, total	7440-69-9	mg/L							
boron, total	7440-42-8	mg/L		5 mg/L					
cadmium, total	7440-43-9	mg/L		0.005 mg/L					
calcium, total	7440-70-2	mg/L							
cesium, total	7440-46-2	mg/L							
chromium, total	7440-47-3	mg/L		0.05 mg/L					
cobalt, total	7440-48-4	mg/L							
copper, total	7440-50-8	mg/L	1 mg/L						
iron, total	7439-89-6	mg/L	0.3 mg/L						
lead, total	7439-92-1	mg/L		0.01 mg/L					
lithium, total	7439-93-2	mg/L							
magnesium, total	7439-95-4	mg/L							
manganese, total	7439-96-5	mg/L	0.05 mg/L						
molybdenum, total	7439-98-7	mg/L							
nickel, total	7440-02-0	mg/L							
phosphorus, total	7723-14-0	mg/L							
potassium, total	7440-09-7	mg/L							
rubidium, total	7440-17-7	mg/L							
selenium, total	7782-49-2	mg/L		0.05 mg/L					
silicon (as SiO2), total	7631-86-9	mg/L							
silicon, total	7440-21-3	mg/L							
silver, total	7440-22-4	mg/L							
sodium, total	7440-23-5	mg/L	200 mg/L	20 mg/L					
strontium, total	7440-24-6	mg/L							
sulfur, total	7704-34-9	mg/L							
tellurium, total	13494-80-9	mg/L							
thallium, total	7440-28-0	mg/L							
thorium, total	7440-29-1	mg/L							
tin, total	7440-31-5	mg/L							
titanium, total	7440-32-6	mg/L							
tungsten, total	7440-33-7	mg/L							
uranium, total	7440-61-1	mg/L		0.02 mg/L					
vanadium, total	7440-62-2	mg/L							
zinc, total	7440-66-6	mg/L	5 mg/L						



QUALITY CONTROL INTERPRETIVE REPORT

<p>Work Order : WT2222750</p> <p>Client : Palmer Environmental Consulting Group Inc.</p> <p>Contact : Lauren Bourke</p> <p>Address : 74 Berkeley Street Toronto ON Canada M5V 1E3</p> <p>Telephone : ----</p> <p>Project : 2008162-HUMBER STATION RD</p> <p>PO : ----</p> <p>C-O-C number : 17-792826</p> <p>Sampler : ----</p> <p>Site : ----</p> <p>Quote number : (Q88296) PALMER 2022 STANDING OFFER</p> <p>No. of samples received : 1</p> <p>No. of samples analysed : 1</p>	<p>Page : 1 of 10</p> <p>Laboratory : Waterloo - Environmental</p> <p>Account Manager : Andrew Martin</p> <p>Address : 60 Northland Road, Unit 1 Waterloo, Ontario Canada N2V 2B8</p> <p>Telephone : +1 519 886 6910</p> <p>Date Samples Received : 21-Nov-2022 16:10</p> <p>Issue Date : 28-Nov-2022 17:34</p>
---	--

This report is automatically generated by the ALS LIMS (Laboratory Information Management System) through evaluation of Quality Control (QC) results and other QA parameters associated with this submission, and is intended to facilitate rapid data validation by auditors or reviewers. The report highlights any exceptions and outliers to ALS Data Quality Objectives, provides holding time details and exceptions, summarizes QC sample frequencies, and lists applicable methodology references and summaries.

Key

- Anonymous: Refers to samples which are not part of this work order, but which formed part of the QC process lot.
- CAS Number: Chemical Abstracts Service number is a unique identifier assigned to discrete substances.
- DQO: Data Quality Objective.
- LOR: Limit of Reporting (detection limit).
- RPD: Relative Percent Difference.

Workorder Comments

Holding times are displayed as "----" if no guidance exists from CCME, Canadian provinces, or broadly recognized international references.

Summary of Outliers

Outliers : Quality Control Samples

- No Method Blank value outliers occur.
- No Duplicate outliers occur.
- No Laboratory Control Sample (LCS) outliers occur
- No Matrix Spike outliers occur.
- No Test sample Surrogate recovery outliers exist.

Outliers: Reference Material (RM) Samples

- No Reference Material (RM) Sample outliers occur.

Outliers : Analysis Holding Time Compliance (Breaches)

- Analysis Holding Time Outliers exist - please see following pages for full details.

Outliers : Frequency of Quality Control Samples

- Quality Control Sample Frequency Outliers occur - please see following pages for full details.



Analysis Holding Time Compliance

This report summarizes extraction / preparation and analysis times and compares each with ALS recommended holding times, which are selected to meet known provincial and /or federal requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by organizations such as CCME, US EPA, APHA Standard Methods, ASTM, or Environment Canada (where available). Dates and holding times reported below represent the first dates of extraction or analysis. If subsequent tests or dilutions exceeded holding times, qualifiers are added (refer to COA).

If samples are identified below as having been analyzed or extracted outside of recommended holding times, measurement uncertainties may be increased, and this should be taken into consideration when interpreting results.

Where actual sampling date is not provided on the chain of custody, the date of receipt with time at 00:00 is used for calculation purposes.

Where only the sample date without time is provided on the chain of custody, the sampling date at 00:00 is used for calculation purposes.

Matrix: **Water** Evaluation: * = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
Anions and Nutrients : Ammonia by Fluorescence										
Amber glass total (sulfuric acid) BH13	E298	21-Nov-2022	24-Nov-2022	----	----		25-Nov-2022	28 days	4 days	✓
Anions and Nutrients : Bromide in Water by IC										
HDPE [ON MECP] BH13	E235.Br	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	28 days	3 days	✓
Anions and Nutrients : Chloride in Water by IC										
HDPE [ON MECP] BH13	E235.Cl	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	28 days	3 days	✓
Anions and Nutrients : Dissolved Orthophosphate by Colourimetry (0.003 mg/L)										
HDPE [ON MECP] BH13	E378-T	21-Nov-2022	----	----	----		24-Nov-2022	7 days	3 days	✓
Anions and Nutrients : Fluoride in Water by IC										
HDPE [ON MECP] BH13	E235.F	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	28 days	3 days	✓
Anions and Nutrients : Nitrate in Water by IC										
HDPE [ON MECP] BH13	E235.NO3	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	7 days	3 days	✓
Anions and Nutrients : Nitrite in Water by IC										
HDPE [ON MECP] BH13	E235.NO2	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	7 days	3 days	✓



Matrix: **Water** Evaluation: * = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
Anions and Nutrients : Sulfate in Water by IC											
HDPE [ON MECP] BH13	E235.SO4	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	28 days	3 days	✓	
Microbiological Tests : E. coli (MF-mFC-BCIG)											
Sterile HDPE (Sodium thiosulphate) [ON MECP] BH13	E012A.EC	21-Nov-2022	----	----	----		23-Nov-2022	48 hrs	46 hrs	✓	
Microbiological Tests : Total Coliforms (MF-mEndo)											
Sterile HDPE (Sodium thiosulphate) [ON MECP] BH13	E012.TC	21-Nov-2022	----	----	----		23-Nov-2022	48 hrs	46 hrs	✓	
Microbiological Tests : Total Coliforms Background (MF-mEndo)											
Sterile HDPE (Sodium thiosulphate) [ON MECP] BH13	E012.BG.TC	21-Nov-2022	----	----	----		23-Nov-2022	48 hrs	46 hrs	✓	
Physical Tests : Alkalinity Species by Titration											
HDPE [ON MECP] BH13	E290	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	14 days	3 days	✓	
Physical Tests : Colour (Apparent) by Spectrometer											
HDPE [ON MECP] BH13	E330	21-Nov-2022	----	----	----		28-Nov-2022	48 hrs	170 hrs	* EHT	
Physical Tests : Conductivity in Water											
HDPE [ON MECP] BH13	E100	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	28 days	3 days	✓	
Physical Tests : pH by Meter											
HDPE [ON MECP] BH13	E108	21-Nov-2022	23-Nov-2022	----	----		24-Nov-2022	14 days	3 days	✓	
Physical Tests : TDS by Gravimetry											
HDPE [ON MECP] BH13	E162	21-Nov-2022	----	----	----		24-Nov-2022	7 days	3 days	✓	



Matrix: **Water** Evaluation: * = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
Physical Tests : Turbidity by Nephelometry										
HDPE [ON MECP] BH13	E121	21-Nov-2022	----	----	----		25-Nov-2022	3 days	4 days	* EHT
Total Metals : Total metals in Water by CRC ICPMS										
HDPE total (nitric acid) BH13	E420	21-Nov-2022	23-Nov-2022	----	----		23-Nov-2022	180 days	2 days	✓

Legend & Qualifier Definitions

EHT: Exceeded ALS recommended hold time prior to analysis.

Rec. HT: ALS recommended hold time (see units).



Quality Control Parameter Frequency Compliance

The following report summarizes the frequency of laboratory QC samples analyzed within the analytical batches (QC lots) in which the submitted samples were processed. The actual frequency should be greater than or equal to the expected frequency.

Matrix: **Water** Evaluation: ✖ = QC frequency outside specification; ✔ = QC frequency within specification.

Quality Control Sample Type	Method	QC Lot #	Count		Frequency (%)		
			QC	Regular	Actual	Expected	Evaluation
Analytical Methods							
Laboratory Duplicates (DUP)							
Alkalinity Species by Titration	E290	754835	1	4	25.0	5.0	✔
Ammonia by Fluorescence	E298	756310	1	20	5.0	5.0	✔
Bromide in Water by IC	E235.Br	754832	1	2	50.0	5.0	✔
Chloride in Water by IC	E235.Cl	754829	1	9	11.1	5.0	✔
Colour (Apparent) by Spectrometer	E330	760306	1	20	5.0	5.0	✔
Conductivity in Water	E100	754834	1	4	25.0	5.0	✔
Dissolved Orthophosphate by Colourimetry (0.003 mg/L)	E378-T	755801	1	18	5.5	5.0	✔
E. coli (MF-mFC-BCIG)	E012A.EC	754757	1	11	9.0	5.0	✔
Fluoride in Water by IC	E235.F	754827	1	10	10.0	5.0	✔
Nitrate in Water by IC	E235.NO3	754830	1	3	33.3	5.0	✔
Nitrite in Water by IC	E235.NO2	754831	1	3	33.3	5.0	✔
pH by Meter	E108	754833	1	18	5.5	5.0	✔
Sulfate in Water by IC	E235.SO4	754828	1	14	7.1	5.0	✔
TDS by Gravimetry	E162	756131	1	19	5.2	5.0	✔
Total Coliforms (MF-mEndo)	E012.TC	754762	0	8	0.0	5.0	✖
Total Coliforms Background (MF-mEndo)	E012.BG.TC	754763	0	6	0.0	5.0	✖
Total metals in Water by CRC ICPMS	E420	755030	1	6	16.6	5.0	✔
Turbidity by Nephelometry	E121	757299	1	20	5.0	5.0	✔
Laboratory Control Samples (LCS)							
Alkalinity Species by Titration	E290	754835	1	4	25.0	5.0	✔
Ammonia by Fluorescence	E298	756310	1	20	5.0	5.0	✔
Bromide in Water by IC	E235.Br	754832	1	2	50.0	5.0	✔
Chloride in Water by IC	E235.Cl	754829	1	9	11.1	5.0	✔
Colour (Apparent) by Spectrometer	E330	760306	1	20	5.0	5.0	✔
Conductivity in Water	E100	754834	1	4	25.0	5.0	✔
Dissolved Orthophosphate by Colourimetry (0.003 mg/L)	E378-T	755801	1	18	5.5	5.0	✔
Fluoride in Water by IC	E235.F	754827	1	10	10.0	5.0	✔
Nitrate in Water by IC	E235.NO3	754830	1	3	33.3	5.0	✔
Nitrite in Water by IC	E235.NO2	754831	1	3	33.3	5.0	✔
pH by Meter	E108	754833	1	18	5.5	5.0	✔
Sulfate in Water by IC	E235.SO4	754828	1	14	7.1	5.0	✔
TDS by Gravimetry	E162	756131	1	19	5.2	5.0	✔
Total metals in Water by CRC ICPMS	E420	755030	1	6	16.6	5.0	✔
Turbidity by Nephelometry	E121	757299	1	20	5.0	5.0	✔
Method Blanks (MB)							



Matrix: **Water**

Evaluation: * = QC frequency outside specification; ✓ = QC frequency within specification.

Quality Control Sample Type	Method	QC Lot #	Count		Frequency (%)		
			QC	Regular	Actual	Expected	Evaluation
Analytical Methods							
Method Blanks (MB) - Continued							
Alkalinity Species by Titration	E290	754835	1	4	25.0	5.0	✓
Ammonia by Fluorescence	E298	756310	1	20	5.0	5.0	✓
Bromide in Water by IC	E235.Br	754832	1	2	50.0	5.0	✓
Chloride in Water by IC	E235.Cl	754829	1	9	11.1	5.0	✓
Colour (Apparent) by Spectrometer	E330	760306	1	20	5.0	5.0	✓
Conductivity in Water	E100	754834	1	4	25.0	5.0	✓
Dissolved Orthophosphate by Colourimetry (0.003 mg/L)	E378-T	755801	1	18	5.5	5.0	✓
E. coli (MF-mFC-BCIG)	E012A.EC	754757	1	11	9.0	5.0	✓
Fluoride in Water by IC	E235.F	754827	1	10	10.0	5.0	✓
Nitrate in Water by IC	E235.NO3	754830	1	3	33.3	5.0	✓
Nitrite in Water by IC	E235.NO2	754831	1	3	33.3	5.0	✓
Sulfate in Water by IC	E235.SO4	754828	1	14	7.1	5.0	✓
TDS by Gravimetry	E162	756131	1	19	5.2	5.0	✓
Total Coliforms (MF-mEndo)	E012.TC	754762	1	8	12.5	5.0	✓
Total Coliforms Background (MF-mEndo)	E012.BG.TC	754763	1	6	16.6	5.0	✓
Total metals in Water by CRC ICPMS	E420	755030	1	6	16.6	5.0	✓
Turbidity by Nephelometry	E121	757299	1	20	5.0	5.0	✓
Matrix Spikes (MS)							
Ammonia by Fluorescence	E298	756310	1	20	5.0	5.0	✓
Bromide in Water by IC	E235.Br	754832	1	2	50.0	5.0	✓
Chloride in Water by IC	E235.Cl	754829	1	9	11.1	5.0	✓
Dissolved Orthophosphate by Colourimetry (0.003 mg/L)	E378-T	755801	1	18	5.5	5.0	✓
Fluoride in Water by IC	E235.F	754827	1	10	10.0	5.0	✓
Nitrate in Water by IC	E235.NO3	754830	1	3	33.3	5.0	✓
Nitrite in Water by IC	E235.NO2	754831	1	3	33.3	5.0	✓
Sulfate in Water by IC	E235.SO4	754828	1	14	7.1	5.0	✓
Total metals in Water by CRC ICPMS	E420	755030	1	6	16.6	5.0	✓



Methodology References and Summaries

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Reference methods may incorporate modifications to improve performance (indicated by "mod").

Analytical Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
Total Coliforms Background (MF-mEndo)	E012.BG.TC Waterloo - Environmental	Water	APHA 9222B (mod)	Noncoliform bacteria observed on Total Coliform plates are enumerated.
Total Coliforms (MF-mEndo)	E012.TC Waterloo - Environmental	Water	APHA 9222B (mod)	Following filtration (0.45 µm), and incubation at 35.0 ± 0.5°C for 24 hours, colonies exhibiting characteristic morphology of the target organism are enumerated and confirmed.
E. coli (MF-mFC-BCIG)	E012A.EC Waterloo - Environmental	Water	ON E3433 (mod)	Following filtration (0.45 µm), and incubation at 44.5 ± 0.2°C for 24 hours, colonies exhibiting characteristic morphology of the target organism are enumerated.
Conductivity in Water	E100 Waterloo - Environmental	Water	APHA 2510 (mod)	Conductivity, also known as Electrical Conductivity (EC) or Specific Conductance, is measured by immersion of a conductivity cell with platinum electrodes into a water sample. Conductivity measurements are temperature-compensated to 25°C.
pH by Meter	E108 Waterloo - Environmental	Water	APHA 4500-H (mod)	pH is determined by potentiometric measurement with a pH electrode, and is conducted at ambient laboratory temperature (normally 20 ± 5°C). For high accuracy test results, pH should be measured in the field within the recommended 15 minute hold time.
Turbidity by Nephelometry	E121 Waterloo - Environmental	Water	APHA 2130 B (mod)	Turbidity is measured by the nephelometric method, by measuring the intensity of light scatter under defined conditions.
TDS by Gravimetry	E162 Waterloo - Environmental	Water	APHA 2540 C (mod)	Total Dissolved Solids (TDS) are determined by filtering a sample through a glass fibre filter, with evaporation of the filtrate at 180 ± 2°C for 16 hours or to constant weight, with gravimetric measurement of the residue.
Bromide in Water by IC	E235.Br Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Chloride in Water by IC	E235.Cl Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Fluoride in Water by IC	E235.F Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.



Analytical Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
Nitrite in Water by IC	E235.NO2 Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Nitrate in Water by IC	E235.NO3 Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Sulfate in Water by IC	E235.SO4 Waterloo - Environmental	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Alkalinity Species by Titration	E290 Waterloo - Environmental	Water	APHA 2320 B (mod)	Total alkalinity is determined by potentiometric titration to a pH 4.5 endpoint. Bicarbonate, carbonate and hydroxide alkalinity are calculated from phenolphthalein alkalinity and total alkalinity values.
Ammonia by Fluorescence	E298 Waterloo - Environmental	Water	Method Fialab 100, 2018	Ammonia in water is determined by automated continuous flow analysis with membrane diffusion and fluorescence detection, after reaction with OPA (ortho-phthalaldehyde). This method is approved under US EPA 40 CFR Part 136 (May 2021)
Colour (Apparent) by Spectrometer	E330 Waterloo - Environmental	Water	APHA 2120 C (mod)	Colour (Apparent) is measured in an unfiltered sample spectrophotometrically using the single wavelength method. The colour contribution of settleable solids are not included in the result. This method is intended for potable waters. Colour measurements can be highly pH dependent, and apply to the pH of the sample as received (at time of testing), without pH adjustment.
Dissolved Orthophosphate by Colourimetry (0.003 mg/L)	E378-T Waterloo - Environmental	Water	APHA 4500-P E (mod)	Dissolved Orthophosphate is determined colourimetrically on a water sample that has been lab or field filtered through a 0.45 micron membrane filter. Field filtration is recommended to ensure test results represent conditions at time of sampling.
Total metals in Water by CRC ICPMS	E420 Waterloo - Environmental	Water	EPA 200.2/6020B (mod)	Water samples are digested with nitric and hydrochloric acids, and analyzed by Collision/Reaction Cell ICPMS. Method Limitation (re: Sulfur): Sulfide and volatile sulfur species may not be recovered by this method.
Hardness (Calculated) from Total Ca/Mg	EC100A Waterloo - Environmental	Water	APHA 2340B	"Hardness (as CaCO ₃), from total Ca/Mg" is calculated from the sum of total Calcium and Magnesium concentrations, expressed in CaCO ₃ equivalents. "Total Hardness" refers to the sum of Calcium and Magnesium Hardness. Hardness is normally or preferentially calculated from dissolved Calcium and Magnesium concentrations, because it is a property of water due to dissolved divalent cations. Hardness from total Ca/Mg is normally comparable to Dissolved Hardness in non-turbid waters.



<i>Analytical Methods</i>	<i>Method / Lab</i>	<i>Matrix</i>	<i>Method Reference</i>	<i>Method Descriptions</i>
Ion Balance using Total Metals	EC101A Waterloo - Environmental	Water	APHA 1030E	Cation Sum (using total metals), Anion Sum, and Ion Balance are calculated based on guidance from APHA Standard Methods (1030E Checking Correctness of Analysis). Minor ions are included where data is present. Ion Balance cannot be calculated accurately for waters with very low electrical conductivity (EC).
Sodium Adsorption Ratio [SAR] from Total Metals	EC102 Waterloo - Environmental	Water	CCME Sodium Adsorption Ratio (SAR)	The Sodium Adsorption Ratio (SAR) for a water sample is calculated from the Sodium, Calcium, and Magnesium concentrations of the water, using the same calculations as would be used for a sediment paste extract.
TDS calculated from conductivity	EC103A Waterloo - Environmental	Water	APHA 1030 E	Total dissolved solids (as mg/L) can be estimated by multiplying electrical conductance (in umhos/cm) by 0.65.
Langelier Index using Laboratory pH (Ca-T)	EC105A Waterloo - Environmental	Water	APHA 2330B	Langelier Index provides an indication of scale formation potential at a given pH and temperature, and is calculated as per APHA 2330B Saturation Index. Positive values indicate oversaturation with respect to CaCO ₃ . Negative values indicate undersaturation of CaCO ₃ . This calculation uses laboratory pH measurements and provides estimates of Langelier Index at temperatures of 4, 15, 20, 25, 66, and 77°C.
Nitrate and Nitrite (as N) (Calculation)	EC235.N+N Waterloo - Environmental	Water	EPA 300.0	Nitrate and Nitrite (as N) is a calculated parameter. Nitrate and Nitrite (as N) = Nitrite (as N) + Nitrate (as N).
Total Silicon as Silica (Calculation)	EC420.SiO2 Waterloo - Environmental	Water	N/A	Total Silicon (as SiO ₂) is a calculated parameter. Total Silicon (as SiO ₂ mg/L) = 2.139 x Total Silicon (mg/L).
<i>Preparation Methods</i>	<i>Method / Lab</i>	<i>Matrix</i>	<i>Method Reference</i>	<i>Method Descriptions</i>
Preparation for Ammonia	EP298 Waterloo - Environmental	Water		Sample preparation for Preserved Nutrients Water Quality Analysis.

QUALITY CONTROL REPORT

Work Order	: WT2222750	Page	: 1 of 13
Client	: Palmer Environmental Consulting Group Inc.	Laboratory	: Waterloo - Environmental
Contact	: Lauren Bourke	Account Manager	: Andrew Martin
Address	: 74 Berkeley Street Toronto ON Canada M5V 1E3	Address	: 60 Northland Road, Unit 1 Waterloo, Ontario Canada N2V 2B8
Telephone	:	Telephone	: +1 519 886 6910
Project	: 2008162-HUMBER STATION RD	Date Samples Received	: 21-Nov-2022 16:10
PO	: ----	Date Analysis Commenced	: 23-Nov-2022
C-O-C number	: 17-792826	Issue Date	: 28-Nov-2022 17:34
Sampler	: ---- ----		
Site	: ----		
Quote number	: (Q88296) PALMER 2022 STANDING OFFER		
No. of samples received	: 1		
No. of samples analysed	: 1		

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Quality Control Report contains the following information:

- Laboratory Duplicate (DUP) Report; Relative Percent Difference (RPD) and Data Quality Objectives
- Matrix Spike (MS) Report; Recovery and Data Quality Objectives
- Method Blank (MB) Report; Recovery and Data Quality Objectives
- Laboratory Control Sample (LCS) Report; Recovery and Data Quality Objectives

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Laboratory Department</i>
Amanda Ganouri-Lumsden	Department Manager - Microbiology and Prep	Waterloo Microbiology, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Waterloo Inorganics, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Waterloo Metals, Waterloo, Ontario

Page : 2 of 13
Work Order : WT2222750
Client : Palmer Environmental Consulting Group Inc.
Project : 2008162-HUMBER STATION RD



General Comments

The ALS Quality Control (QC) report is optionally provided to ALS clients upon request. ALS test methods include comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against predetermined Data Quality Objectives (DQOs) to provide confidence in the accuracy of associated test results. This report contains detailed results for all QC results applicable to this sample submission. Please refer to the ALS Quality Control Interpretation report (QCI) for applicable method references and methodology summaries.

Key :

Anonymous = Refers to samples which are not part of this work order, but which formed part of the QC process lot.

CAS Number = Chemical Abstracts Service number is a unique identifier assigned to discrete substances.

DQO = Data Quality Objective.

LOR = Limit of Reporting (detection limit).

RPD = Relative Percent Difference

= Indicates a QC result that did not meet the ALS DQO.

Workorder Comments

Holding times are displayed as "---" if no guidance exists from CCME, Canadian provinces, or broadly recognized international references.



Laboratory Duplicate (DUP) Report

A Laboratory Duplicate (DUP) is a randomly selected intralaboratory replicate sample. Laboratory Duplicates provide information regarding method precision and sample heterogeneity. ALS DQOs for Laboratory Duplicates are expressed as test-specific limits for Relative Percent Difference (RPD), or as an absolute difference limit of 2 times the LOR for low concentration duplicates within ~ 4-10 times the LOR (cut-off is test-specific).

Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
Physical Tests (QC Lot: 754833)											
WT2222750-001	BH13	pH	----	E108	0.10	pH units	7.94	7.94	0.00%	4%	----
Physical Tests (QC Lot: 754834)											
WT2222750-001	BH13	conductivity	----	E100	1.0	µS/cm	1230	1220	0.981%	10%	----
Physical Tests (QC Lot: 754835)											
WT2222750-001	BH13	alkalinity, total (as CaCO3)	----	E290	1.0	mg/L	498	487	2.24%	20%	----
Physical Tests (QC Lot: 756131)											
HA2200039-003	Anonymous	solids, total dissolved [TDS]	----	E162	13	mg/L	80	89	9	Diff <2x LOR	----
Physical Tests (QC Lot: 757299)											
WT2222460-014	Anonymous	turbidity	----	E121	0.10	NTU	8.95	9.04	1.00%	15%	----
Anions and Nutrients (QC Lot: 754827)											
WT2222750-001	BH13	fluoride	16984-48-8	E235.F	0.100	mg/L	0.228	0.237	0.009	Diff <2x LOR	----
Anions and Nutrients (QC Lot: 754828)											
WT2222750-001	BH13	sulfate (as SO4)	14808-79-8	E235.SO4	1.50	mg/L	202	203	0.391%	20%	----
Anions and Nutrients (QC Lot: 754829)											
WT2222750-001	BH13	chloride	16887-00-6	E235.Cl	2.50	mg/L	9.33	8.93	0.40	Diff <2x LOR	----
Anions and Nutrients (QC Lot: 754830)											
WT2222750-001	BH13	nitrate (as N)	14797-55-8	E235.NO3	0.100	mg/L	<0.100	<0.100	0	Diff <2x LOR	----
Anions and Nutrients (QC Lot: 754831)											
WT2222750-001	BH13	nitrite (as N)	14797-65-0	E235.NO2	0.050	mg/L	<0.050	<0.050	0	Diff <2x LOR	----
Anions and Nutrients (QC Lot: 754832)											
WT2222750-001	BH13	bromide	24959-67-9	E235.Br	0.50	mg/L	<0.50	<0.50	0	Diff <2x LOR	----
Anions and Nutrients (QC Lot: 755801)											
WT2222604-001	Anonymous	phosphate, ortho-, dissolved (as P)	14265-44-2	E378-T	0.300	mg/L	43.9	44.1	0.495%	20%	----
Anions and Nutrients (QC Lot: 756310)											
WT2222602-001	Anonymous	ammonia, total (as N)	7664-41-7	E298	0.0050	mg/L	0.0507	0.0509	0.394%	20%	----
Microbiological Tests (QC Lot: 754757)											
WT2222619-001	Anonymous	coliforms, Escherichia coli [E. coli]	----	E012A.EC	1	CFU/100mL	2	1	1	Diff <2x LOR	----
Total Metals (QC Lot: 755030)											
TY2204274-001	Anonymous	aluminum, total	7429-90-5	E420	0.0030	mg/L	0.961	0.950	1.17%	20%	----
		antimony, total	7440-36-0	E420	0.00010	mg/L	0.00014	0.00015	0.000008	Diff <2x LOR	----



Sub-Matrix: **Water**

Laboratory Duplicate (DUP) Report

Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
Total Metals (QC Lot: 755030) - continued											
TY2204274-001	Anonymous	arsenic, total	7440-38-2	E420	0.00010	mg/L	0.00119	0.00114	3.99%	20%	----
		barium, total	7440-39-3	E420	0.00010	mg/L	0.0215	0.0211	1.82%	20%	----
		beryllium, total	7440-41-7	E420	0.000020	mg/L	0.000026	0.000026	0.0000009	Diff <2x LOR	----
		bismuth, total	7440-69-9	E420	0.000050	mg/L	<0.000050	<0.000050	0	Diff <2x LOR	----
		boron, total	7440-42-8	E420	0.010	mg/L	0.024	0.022	0.001	Diff <2x LOR	----
		cadmium, total	7440-43-9	E420	0.0000050	mg/L	0.0000218	0.0000210	0.0000008	Diff <2x LOR	----
		calcium, total	7440-70-2	E420	0.050	mg/L	39.0	37.0	5.19%	20%	----
		cesium, total	7440-46-2	E420	0.000010	mg/L	0.000219	0.000203	7.68%	20%	----
		chromium, total	7440-47-3	E420	0.00050	mg/L	0.00277	0.00303	0.00026	Diff <2x LOR	----
		cobalt, total	7440-48-4	E420	0.00010	mg/L	0.00129	0.00126	2.25%	20%	----
		copper, total	7440-50-8	E420	0.00050	mg/L	0.00759	0.00733	3.38%	20%	----
		iron, total	7439-89-6	E420	0.010	mg/L	1.24	1.22	1.60%	20%	----
		lead, total	7439-92-1	E420	0.000050	mg/L	0.000807	0.000764	5.41%	20%	----
		lithium, total	7439-93-2	E420	0.0010	mg/L	<0.0010	<0.0010	0	Diff <2x LOR	----
		magnesium, total	7439-95-4	E420	0.0050	mg/L	4.59	4.49	2.17%	20%	----
		manganese, total	7439-96-5	E420	0.00010	mg/L	0.0726	0.0706	2.89%	20%	----
		molybdenum, total	7439-98-7	E420	0.000050	mg/L	0.000671	0.000654	2.50%	20%	----
		nickel, total	7440-02-0	E420	0.00050	mg/L	0.00292	0.00283	0.00009	Diff <2x LOR	----
		phosphorus, total	7723-14-0	E420	0.050	mg/L	<0.050	<0.050	0	Diff <2x LOR	----
		potassium, total	7440-09-7	E420	0.050	mg/L	2.87	2.78	3.12%	20%	----
		rubidium, total	7440-17-7	E420	0.00020	mg/L	0.00636	0.00613	3.72%	20%	----
		selenium, total	7782-49-2	E420	0.000050	mg/L	0.000199	0.000204	0.000006	Diff <2x LOR	----
		silicon, total	7440-21-3	E420	0.10	mg/L	3.99	4.00	0.224%	20%	----
		silver, total	7440-22-4	E420	0.000010	mg/L	0.000014	0.000013	0.0000008	Diff <2x LOR	----
		sodium, total	7440-23-5	E420	0.050	mg/L	4.32	4.26	1.60%	20%	----
		strontium, total	7440-24-6	E420	0.00020	mg/L	0.122	0.116	5.28%	20%	----
		sulfur, total	7704-34-9	E420	0.50	mg/L	7.17	7.14	0.431%	20%	----
		tellurium, total	13494-80-9	E420	0.00020	mg/L	<0.00020	<0.00020	0	Diff <2x LOR	----
		thallium, total	7440-28-0	E420	0.000010	mg/L	0.000024	0.000018	0.000005	Diff <2x LOR	----
		thorium, total	7440-29-1	E420	0.00010	mg/L	0.00031	0.00030	0.00001	Diff <2x LOR	----
		tin, total	7440-31-5	E420	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		titanium, total	7440-32-6	E420	0.00030	mg/L	0.0371	0.0364	1.94%	20%	----
		tungsten, total	7440-33-7	E420	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		uranium, total	7440-61-1	E420	0.000010	mg/L	0.000423	0.000401	5.34%	20%	----

Page : 5 of 13
 Work Order : WT2222750
 Client : Palmer Environmental Consulting Group Inc.
 Project : 2008162-HUMBER STATION RD



Sub-Matrix: **Water**

					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
Total Metals (QC Lot: 755030) - continued											
TY2204274-001	Anonymous	vanadium, total	7440-62-2	E420	0.00050	mg/L	0.00280	0.00272	0.00007	Diff <2x LOR	----
		zinc, total	7440-66-6	E420	0.0030	mg/L	0.0064	0.0065	0.0001	Diff <2x LOR	----
		zirconium, total	7440-67-7	E420	0.00020	mg/L	0.00054	0.00049	0.00005	Diff <2x LOR	----



Method Blank (MB) Report

A Method Blank is an analyte-free matrix that undergoes sample processing identical to that carried out for test samples. Method Blank results are used to monitor and control for potential contamination from the laboratory environment and reagents. For most tests, the DQO for Method Blanks is for the result to be < LOR.

Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
Physical Tests (QCLot: 754834)						
conductivity	---	E100	1	µS/cm	<1.0	---
Physical Tests (QCLot: 754835)						
alkalinity, total (as CaCO3)	---	E290	1	mg/L	<1.0	---
Physical Tests (QCLot: 756131)						
solids, total dissolved [TDS]	---	E162	10	mg/L	<10	---
Physical Tests (QCLot: 757299)						
turbidity	---	E121	0.1	NTU	<0.10	---
Physical Tests (QCLot: 760306)						
colour, apparent	---	E330	2	CU	<2.0	---
Anions and Nutrients (QCLot: 754827)						
fluoride	16984-48-8	E235.F	0.02	mg/L	<0.020	---
Anions and Nutrients (QCLot: 754828)						
sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	<0.30	---
Anions and Nutrients (QCLot: 754829)						
chloride	16887-00-6	E235.Cl	0.5	mg/L	<0.50	---
Anions and Nutrients (QCLot: 754830)						
nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	<0.020	---
Anions and Nutrients (QCLot: 754831)						
nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	<0.010	---
Anions and Nutrients (QCLot: 754832)						
bromide	24959-67-9	E235.Br	0.1	mg/L	<0.10	---
Anions and Nutrients (QCLot: 755801)						
phosphate, ortho-, dissolved (as P)	14265-44-2	E378-T	0.003	mg/L	<0.0030	---
Anions and Nutrients (QCLot: 756310)						
ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	<0.0050	---
Microbiological Tests (QCLot: 754757)						
coliforms, Escherichia coli [E. coli]	---	E012A.EC	1	CFU/100mL	<1	---
Microbiological Tests (QCLot: 754762)						
coliforms, total	---	E012.TC	1	CFU/100mL	<1	---
Microbiological Tests (QCLot: 754763)						
coliforms, total background	---	E012.BG.TC	1	CFU/100mL	<1	---
Total Metals (QCLot: 755030)						



Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
Total Metals (QCLot: 755030) - continued						
aluminum, total	7429-90-5	E420	0.003	mg/L	<0.0030	---
antimony, total	7440-36-0	E420	0.0001	mg/L	<0.00010	---
arsenic, total	7440-38-2	E420	0.0001	mg/L	<0.00010	---
barium, total	7440-39-3	E420	0.0001	mg/L	<0.00010	---
beryllium, total	7440-41-7	E420	0.00002	mg/L	<0.000020	---
bismuth, total	7440-69-9	E420	0.00005	mg/L	<0.000050	---
boron, total	7440-42-8	E420	0.01	mg/L	<0.010	---
cadmium, total	7440-43-9	E420	0.000005	mg/L	<0.0000050	---
calcium, total	7440-70-2	E420	0.05	mg/L	<0.050	---
cesium, total	7440-46-2	E420	0.00001	mg/L	<0.000010	---
chromium, total	7440-47-3	E420	0.0005	mg/L	<0.00050	---
cobalt, total	7440-48-4	E420	0.0001	mg/L	<0.00010	---
copper, total	7440-50-8	E420	0.0005	mg/L	<0.00050	---
iron, total	7439-89-6	E420	0.01	mg/L	<0.010	---
lead, total	7439-92-1	E420	0.00005	mg/L	<0.000050	---
lithium, total	7439-93-2	E420	0.001	mg/L	<0.0010	---
magnesium, total	7439-95-4	E420	0.005	mg/L	<0.0050	---
manganese, total	7439-96-5	E420	0.0001	mg/L	<0.00010	---
molybdenum, total	7439-98-7	E420	0.00005	mg/L	<0.000050	---
nickel, total	7440-02-0	E420	0.0005	mg/L	<0.00050	---
phosphorus, total	7723-14-0	E420	0.05	mg/L	<0.050	---
potassium, total	7440-09-7	E420	0.05	mg/L	<0.050	---
rubidium, total	7440-17-7	E420	0.0002	mg/L	<0.00020	---
selenium, total	7782-49-2	E420	0.00005	mg/L	<0.000050	---
silicon, total	7440-21-3	E420	0.1	mg/L	<0.10	---
silver, total	7440-22-4	E420	0.00001	mg/L	<0.000010	---
sodium, total	7440-23-5	E420	0.05	mg/L	<0.050	---
strontium, total	7440-24-6	E420	0.0002	mg/L	<0.00020	---
sulfur, total	7704-34-9	E420	0.5	mg/L	<0.50	---
tellurium, total	13494-80-9	E420	0.0002	mg/L	<0.00020	---
thallium, total	7440-28-0	E420	0.00001	mg/L	<0.000010	---
thorium, total	7440-29-1	E420	0.0001	mg/L	<0.00010	---
tin, total	7440-31-5	E420	0.0001	mg/L	<0.00010	---
titanium, total	7440-32-6	E420	0.0003	mg/L	<0.00030	---
tungsten, total	7440-33-7	E420	0.0001	mg/L	<0.00010	---



Sub-Matrix: **Water**

<i>Analyte</i>	<i>CAS Number</i>	<i>Method</i>	<i>LOR</i>	<i>Unit</i>	<i>Result</i>	<i>Qualifier</i>
Total Metals (QCLot: 755030) - continued						
uranium, total	7440-61-1	E420	0.00001	mg/L	<0.000010	----
vanadium, total	7440-62-2	E420	0.0005	mg/L	<0.00050	----
zinc, total	7440-66-6	E420	0.003	mg/L	<0.0030	----
zirconium, total	7440-67-7	E420	0.0002	mg/L	<0.00020	----



Laboratory Control Sample (LCS) Report

A Laboratory Control Sample (LCS) is an analyte-free matrix that has been fortified (spiked) with test analytes at known concentration and processed in an identical manner to test samples. LCS results are expressed as percent recovery, and are used to monitor and control test method accuracy and precision, independent of test sample matrix.

Sub-Matrix: Water

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
Physical Tests (QCLot: 754833)									
pH	----	E108	----	pH units	7 pH units	100	98.0	102	----
Physical Tests (QCLot: 754834)									
conductivity	----	E100	1	µS/cm	1409 µS/cm	102	90.0	110	----
Physical Tests (QCLot: 754835)									
alkalinity, total (as CaCO3)	----	E290	1	mg/L	150 mg/L	99.6	85.0	115	----
Physical Tests (QCLot: 756131)									
solids, total dissolved [TDS]	----	E162	10	mg/L	1000 mg/L	99.4	85.0	115	----
Physical Tests (QCLot: 757299)									
turbidity	----	E121	0.1	NTU	200 NTU	96.4	85.0	115	----
Physical Tests (QCLot: 760306)									
colour, apparent	----	E330	2	CU	25 CU	99.3	70.0	130	----
Anions and Nutrients (QCLot: 754827)									
fluoride	16984-48-8	E235.F	0.02	mg/L	1 mg/L	100	90.0	110	----
Anions and Nutrients (QCLot: 754828)									
sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	100 mg/L	99.8	90.0	110	----
Anions and Nutrients (QCLot: 754829)									
chloride	16887-00-6	E235.Cl	0.5	mg/L	100 mg/L	99.8	90.0	110	----
Anions and Nutrients (QCLot: 754830)									
nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	2.5 mg/L	98.6	90.0	110	----
Anions and Nutrients (QCLot: 754831)									
nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	0.5 mg/L	98.5	90.0	110	----
Anions and Nutrients (QCLot: 754832)									
bromide	24959-67-9	E235.Br	0.1	mg/L	0.5 mg/L	103	85.0	115	----
Anions and Nutrients (QCLot: 755801)									
phosphate, ortho-, dissolved (as P)	14265-44-2	E378-T	0.003	mg/L	0.0212 mg/L	106	80.0	120	----
Anions and Nutrients (QCLot: 756310)									
ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	0.2 mg/L	96.5	85.0	115	----
Total Metals (QCLot: 755030)									
aluminum, total	7429-90-5	E420	0.003	mg/L	0.1 mg/L	103	80.0	120	----
antimony, total	7440-36-0	E420	0.0001	mg/L	0.05 mg/L	103	80.0	120	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
Total Metals (QCLot: 755030) - continued									
arsenic, total	7440-38-2	E420	0.0001	mg/L	0.05 mg/L	108	80.0	120	----
barium, total	7440-39-3	E420	0.0001	mg/L	0.0125 mg/L	101	80.0	120	----
beryllium, total	7440-41-7	E420	0.00002	mg/L	0.005 mg/L	99.2	80.0	120	----
bismuth, total	7440-69-9	E420	0.00005	mg/L	0.05 mg/L	103	80.0	120	----
boron, total	7440-42-8	E420	0.01	mg/L	0.05 mg/L	95.6	80.0	120	----
cadmium, total	7440-43-9	E420	0.000005	mg/L	0.005 mg/L	104	80.0	120	----
calcium, total	7440-70-2	E420	0.05	mg/L	2.5 mg/L	101	80.0	120	----
cesium, total	7440-46-2	E420	0.00001	mg/L	0.0025 mg/L	104	80.0	120	----
chromium, total	7440-47-3	E420	0.0005	mg/L	0.0125 mg/L	104	80.0	120	----
cobalt, total	7440-48-4	E420	0.0001	mg/L	0.0125 mg/L	105	80.0	120	----
copper, total	7440-50-8	E420	0.0005	mg/L	0.0125 mg/L	102	80.0	120	----
iron, total	7439-89-6	E420	0.01	mg/L	0.05 mg/L	107	80.0	120	----
lead, total	7439-92-1	E420	0.00005	mg/L	0.025 mg/L	104	80.0	120	----
lithium, total	7439-93-2	E420	0.001	mg/L	0.0125 mg/L	98.9	80.0	120	----
magnesium, total	7439-95-4	E420	0.005	mg/L	2.5 mg/L	108	80.0	120	----
manganese, total	7439-96-5	E420	0.0001	mg/L	0.0125 mg/L	104	80.0	120	----
molybdenum, total	7439-98-7	E420	0.00005	mg/L	0.0125 mg/L	101	80.0	120	----
nickel, total	7440-02-0	E420	0.0005	mg/L	0.025 mg/L	104	80.0	120	----
phosphorus, total	7723-14-0	E420	0.05	mg/L	0.5 mg/L	104	80.0	120	----
potassium, total	7440-09-7	E420	0.05	mg/L	2.5 mg/L	104	80.0	120	----
rubidium, total	7440-17-7	E420	0.0002	mg/L	0.005 mg/L	107	80.0	120	----
selenium, total	7782-49-2	E420	0.00005	mg/L	0.05 mg/L	103	80.0	120	----
silicon, total	7440-21-3	E420	0.1	mg/L	0.5 mg/L	106	80.0	120	----
silver, total	7440-22-4	E420	0.00001	mg/L	0.005 mg/L	92.6	80.0	120	----
sodium, total	7440-23-5	E420	0.05	mg/L	2.5 mg/L	108	80.0	120	----
strontium, total	7440-24-6	E420	0.0002	mg/L	0.0125 mg/L	103	80.0	120	----
sulfur, total	7704-34-9	E420	0.5	mg/L	2.5 mg/L	99.4	80.0	120	----
tellurium, total	13494-80-9	E420	0.0002	mg/L	0.005 mg/L	94.6	80.0	120	----
thallium, total	7440-28-0	E420	0.00001	mg/L	0.05 mg/L	105	80.0	120	----
thorium, total	7440-29-1	E420	0.0001	mg/L	0.005 mg/L	99.3	80.0	120	----
tin, total	7440-31-5	E420	0.0001	mg/L	0.025 mg/L	100	80.0	120	----
titanium, total	7440-32-6	E420	0.0003	mg/L	0.0125 mg/L	100	80.0	120	----
tungsten, total	7440-33-7	E420	0.0001	mg/L	0.005 mg/L	101	80.0	120	----
uranium, total	7440-61-1	E420	0.00001	mg/L	0.00025 mg/L	105	80.0	120	----
vanadium, total	7440-62-2	E420	0.0005	mg/L	0.025 mg/L	106	80.0	120	----
zinc, total	7440-66-6	E420	0.003	mg/L	0.025 mg/L	103	80.0	120	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
Total Metals (QCLot: 755030) - continued									
zirconium, total	7440-67-7	E420	0.0002	mg/L	0.005 mg/L	100	80.0	120	----



Matrix Spike (MS) Report

A Matrix Spike (MS) is a randomly selected intra-laboratory replicate sample that has been fortified (spiked) with test analytes at known concentration, and processed in an identical manner to test samples. Matrix Spikes provide information regarding analyte recovery and potential matrix effects. MS DQO exceedances due to sample matrix may sometimes be unavoidable; in such cases, test results for the associated sample (or similar samples) may be subject to bias. ND – Recovery not determined, background level >= 1x spike level.

Sub-Matrix: **Water**

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
Anions and Nutrients (QCLot: 754827)										
WT2222750-001	BH13	fluoride	16984-48-8	E235.F	5.11 mg/L	5 mg/L	102	75.0	125	----
Anions and Nutrients (QCLot: 754828)										
WT2222750-001	BH13	sulfate (as SO4)	14808-79-8	E235.SO4	508 mg/L	500 mg/L	102	75.0	125	----
Anions and Nutrients (QCLot: 754829)										
WT2222750-001	BH13	chloride	16887-00-6	E235.Cl	507 mg/L	500 mg/L	101	75.0	125	----
Anions and Nutrients (QCLot: 754830)										
WT2222750-001	BH13	nitrate (as N)	14797-55-8	E235.NO3	12.4 mg/L	12.5 mg/L	98.9	75.0	125	----
Anions and Nutrients (QCLot: 754831)										
WT2222750-001	BH13	nitrite (as N)	14797-65-0	E235.NO2	2.44 mg/L	2.5 mg/L	97.8	75.0	125	----
Anions and Nutrients (QCLot: 754832)										
WT2222750-001	BH13	bromide	24959-67-9	E235.Br	2.49 mg/L	2.5 mg/L	99.5	75.0	125	----
Anions and Nutrients (QCLot: 755801)										
WT2222604-001	Anonymous	phosphate, ortho-, dissolved (as P)	14265-44-2	E378-T	ND mg/L	0.0196 mg/L	ND	70.0	130	----
Anions and Nutrients (QCLot: 756310)										
WT2222602-001	Anonymous	ammonia, total (as N)	7664-41-7	E298	0.104 mg/L	0.1 mg/L	104	75.0	125	----
Total Metals (QCLot: 755030)										
TY2204274-001	Anonymous	aluminum, total	7429-90-5	E420	ND mg/L	0.1 mg/L	ND	70.0	130	----
		antimony, total	7440-36-0	E420	0.0519 mg/L	0.05 mg/L	104	70.0	130	----
		arsenic, total	7440-38-2	E420	0.0537 mg/L	0.05 mg/L	107	70.0	130	----
		barium, total	7440-39-3	E420	ND mg/L	0.0125 mg/L	ND	70.0	130	----
		beryllium, total	7440-41-7	E420	0.00474 mg/L	0.005 mg/L	94.9	70.0	130	----
		bismuth, total	7440-69-9	E420	0.0499 mg/L	0.05 mg/L	99.8	70.0	130	----
		boron, total	7440-42-8	E420	0.045 mg/L	0.05 mg/L	89.3	70.0	130	----
		cadmium, total	7440-43-9	E420	0.00522 mg/L	0.005 mg/L	104	70.0	130	----
		calcium, total	7440-70-2	E420	ND mg/L	2.5 mg/L	ND	70.0	130	----
		cesium, total	7440-46-2	E420	0.00260 mg/L	0.0025 mg/L	104	70.0	130	----
		chromium, total	7440-47-3	E420	0.0130 mg/L	0.0125 mg/L	104	70.0	130	----
		cobalt, total	7440-48-4	E420	0.0128 mg/L	0.0125 mg/L	102	70.0	130	----
		copper, total	7440-50-8	E420	0.0121 mg/L	0.0125 mg/L	97.0	70.0	130	----



Sub-Matrix: **Water**

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
Total Metals (QCLot: 755030) - continued										
TY2204274-001	Anonymous	iron, total	7439-89-6	E420	ND mg/L	0.05 mg/L	ND	70.0	130	----
		lead, total	7439-92-1	E420	0.0250 mg/L	0.025 mg/L	99.9	70.0	130	----
		lithium, total	7439-93-2	E420	0.0115 mg/L	0.0125 mg/L	92.3	70.0	130	----
		magnesium, total	7439-95-4	E420	ND mg/L	2.5 mg/L	ND	70.0	130	----
		manganese, total	7439-96-5	E420	ND mg/L	0.0125 mg/L	ND	70.0	130	----
		molybdenum, total	7439-98-7	E420	0.0124 mg/L	0.0125 mg/L	99.4	70.0	130	----
		nickel, total	7440-02-0	E420	0.0254 mg/L	0.025 mg/L	102	70.0	130	----
		phosphorus, total	7723-14-0	E420	0.526 mg/L	0.5 mg/L	105	70.0	130	----
		potassium, total	7440-09-7	E420	ND mg/L	2.5 mg/L	ND	70.0	130	----
		rubidium, total	7440-17-7	E420	ND mg/L	0.005 mg/L	ND	70.0	130	----
		selenium, total	7782-49-2	E420	0.0527 mg/L	0.05 mg/L	105	70.0	130	----
		silicon, total	7440-21-3	E420	ND mg/L	0.5 mg/L	ND	70.0	130	----
		silver, total	7440-22-4	E420	0.00460 mg/L	0.005 mg/L	92.0	70.0	130	----
		sodium, total	7440-23-5	E420	ND mg/L	2.5 mg/L	ND	70.0	130	----
		strontium, total	7440-24-6	E420	ND mg/L	0.0125 mg/L	ND	70.0	130	----
		sulfur, total	7704-34-9	E420	ND mg/L	2.5 mg/L	ND	70.0	130	----
		tellurium, total	13494-80-9	E420	0.00460 mg/L	0.005 mg/L	92.0	70.0	130	----
		thallium, total	7440-28-0	E420	0.0511 mg/L	0.05 mg/L	102	70.0	130	----
		thorium, total	7440-29-1	E420	0.00472 mg/L	0.005 mg/L	94.4	70.0	130	----
		tin, total	7440-31-5	E420	0.0251 mg/L	0.025 mg/L	100	70.0	130	----
		titanium, total	7440-32-6	E420	ND mg/L	0.0125 mg/L	ND	70.0	130	----
		tungsten, total	7440-33-7	E420	0.00492 mg/L	0.005 mg/L	98.4	70.0	130	----
		uranium, total	7440-61-1	E420	ND mg/L	0.00025 mg/L	ND	70.0	130	----
		vanadium, total	7440-62-2	E420	0.0259 mg/L	0.025 mg/L	104	70.0	130	----
		zinc, total	7440-66-6	E420	0.0239 mg/L	0.025 mg/L	95.8	70.0	130	----
		zirconium, total	7440-67-7	E420	0.00410 mg/L	0.005 mg/L	82.1	70.0	130	----



Chain of Custody (COC) / Analytical Request Form

Canada Toll Free: 1 800 668 9878

www.alsglobal.com

COC Number: 17 - 792826

Page of

Affix ALS barcode label here (lab use only)

Report To Contact and company name below will appear on the final report Company: <u>Palace</u> Contact: <u>Laura Boule</u> Phone: <u>514 671-0005</u> Company address below will appear on the final report Street: <u>74 Beekley St</u> City/Province: <u>Toronto, ON</u> Postal Code: <u>M6A 2W7</u>		Report Format / Distribution Select Report Format: <input checked="" type="checkbox"/> PDF <input checked="" type="checkbox"/> EXCEL <input type="checkbox"/> ESD (DIGITAL) Quality Control (QC) Report with Report <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input checked="" type="checkbox"/> Compare Results to Criteria on Report - provide details below if box checked Select Distribution: <input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX Email 1 or Fax: <u>laura.boule@palace.ca</u> Email 2: <u>laura@palace.ca</u> Email 3:																																									
Invoice To Same as Report To <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO Copy of Invoice with Report <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO Company: <u>Palace</u> Contact: <u>Victoria Orsini</u> Project Information ALS Account # / Quote #: <u>WT2222750</u> Job #: <u>900162-Humber consumption</u> PO / A/E: LSD:		Invoice Distribution Select Invoice Distribution: <input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX Email 1 or Fax: <u>Victoria Orsini</u> Email 2: Oil and Gas Required Fields (client use) AFE/Case Center: Major/Minor Code: Requisitioner: Location: ALS Contact: Sampler: Date (dd-mm-yy): <u>8002-11-21 14:45</u> Time (hh:mm): Sample Type: <u>GW</u>																																									
ALS Lab Work Order # (lab use only): <u>WT2222750</u> ALS Sample # (lab use only): <u>3413</u> Sample identification and/or Coordinates (This description will appear on the report)		NUMBER OF CONTAINERS <table border="1"> <tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td><td>8</td><td>9</td><td>10</td><td>11</td><td>12</td><td>13</td><td>14</td><td>15</td><td>16</td><td>17</td><td>18</td><td>19</td><td>20</td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> </table>		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20																				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20																								
Shipping Information Drinking Water (DW) Samples (client use) Are samples taken from a Regulated DW System? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO Are samples for human consumption/ use? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO		Special Instructions / Specify Criteria to add on report by clicking on the drop-down list below (electronic COC only) <u>Compare to drinking water standard criteria</u>																																									
SHIPMENT RELEASE (client use) Released by: <u>Laura Boule</u> Date: <u>8002-11-21</u> Time: <u>16:00</u>		INITIAL SHIPMENT RECEPTION (lab use only) Received by: <u>[Signature]</u> Date: <u>21-NOV-22</u> Time: <u>16:10</u>																																									
SHIPPING INFORMATION REFER TO BACK PAGE FOR ALS LOCATIONS AND SAMPLING INFORMATION		FINAL SHIPMENT RECEPTION (lab use only) Received by: <u>R.M</u> Date: <u>22/11/22</u> Time: <u>3:15P</u>																																									

Standard TAT if received by 2 pm - business days - no surcharges apply

1 Business day [E - 100%]
 Same Day, Weekend or Statutory holiday [E - 200%]
 (Laboratory opening fees may apply)

Date and Time Required for all E&P TATs: dd-mm-yy hh:mm


For tests that can not be performed according to the service level select

Indicate Filtered (F), Preserved (P) or Fills

Environmental Division
 Waterloo
 Work Order Reference
WT2222750

Telephone: +1 519 886 8910

SUSPECTED HAZARD (see Special Instructions)



1. If any water samples are taken from a Regulated Drinking Water (DW) System, please submit using an Authorized DW COC form.



CERTIFICATE OF ANALYSIS (GUIDELINE EVALUATION)

<p>Work Order : WT2222750</p> <p>Client : Palmer Environmental Consulting Group Inc.</p> <p>Contact : Lauren Bourke</p> <p>Address : 74 Berkeley Street Toronto ON Canada M5V 1E3</p> <p>Telephone : ----</p> <p>Project : 2008162-HUMBER STATION RD</p> <p>PO : ----</p> <p>C-O-C number : 17-792826</p> <p>Sampler : ----</p> <p>Site : ----</p> <p>Quote number : (Q88296) PALMER 2022 STANDING OFFER</p> <p>No. of samples received : 1</p> <p>No. of samples analysed : 1</p>	<p>Page : 1 of 6</p> <p>Laboratory : Waterloo - Environmental</p> <p>Account Manager : Andrew Martin</p> <p>Address : 60 Northland Road, Unit 1 Waterloo, Ontario Canada N2V 2B8</p> <p>Telephone : +1 519 886 6910</p> <p>Date Samples Received : 21-Nov-2022 16:10</p> <p>Date Analysis Commenced : 23-Nov-2022</p> <p>Issue Date : 28-Nov-2022 17:34</p>
---	---

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results
- Guideline Comparison

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QC Interpretive report to assist with Quality Review and Sample Receipt Notification (SRN).

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Laboratory Department</i>
Amanda Ganouri-Lumsden	Department Manager - Microbiology and Prep	Microbiology, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Inorganics, Waterloo, Ontario
Greg Pokocky	Supervisor - Inorganic	Metals, Waterloo, Ontario

General Comments

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Refer to the ALS Quality Control Interpretive report (QCI) for applicable references and methodology summaries. Reference methods may incorporate modifications to improve performance.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to fitness for a particular purpose, or non-infringement. ALS assumes no responsibility for errors or omissions in the information. Guidelines are not adjusted for the hardness, pH or temperature of the sample (the most conservative values are used). Measurement uncertainty is not applied to test results prior to comparison with specified criteria values.

Key : LOR: Limit of Reporting (detection limit).

<i>Unit</i>	<i>Description</i>
-	no units
%	percent
µS/cm	microsiemens per centimetre
CFU/100mL	colony forming units per hundred millilitres
CU	colour units (1 cu = 1 mg/l pt)
meq/L	milliequivalents per litre
mg/L	milligrams per litre
NTU	nephelometric turbidity units
pH units	pH units

>: greater than.

<: less than.

Red shading is applied where the result is greater than the Guideline Upper Limit or the result is lower than the Guideline Lower Limit.

For drinking water samples, Red shading is applied where the result for E.coli, fecal or total coliforms is greater than or equal to the Guideline Upper Limit .

Qualifiers

<i>Qualifier</i>	<i>Description</i>
DLDS	<i>Detection Limit Raised: Dilution required due to high Dissolved Solids / Electrical Conductivity.</i>
DLHC	<i>Detection Limit Raised: Dilution required due to high concentration of test analyte(s).</i>
DLM	<i>Detection Limit Adjusted due to sample matrix effects (e.g. chemical interference, colour, turbidity).</i>



Analytical Results

Analyte	Method	LOR	Unit	Client sample ID	ONDWS	ONDWS				
				BH13	AO/OG	MAC				
Sub-Matrix: Water (Matrix: Water)				Sampling date/time						
				WT2222750-001						
Physical Tests										
alkalinity, bicarbonate (as HCO3)	E290	1.0	mg/L	608	--	--	--	--	--	--
alkalinity, carbonate (as CO3)	E290	1.0	mg/L	<1.0	--	--	--	--	--	--
alkalinity, hydroxide (as OH)	E290	1.0	mg/L	<1.0	--	--	--	--	--	--
alkalinity, total (as CaCO3)	E290	1.0	mg/L	498	30 - 500 mg/L	--	--	--	--	--
colour, apparent	E330	2.0	CU	40.0	5 CU	--	--	--	--	--
conductivity	E100	1.0	µS/cm	1230	--	--	--	--	--	--
hardness (as CaCO3), from total Ca/Mg	EC100A	0.50	mg/L	664	--	--	--	--	--	--
pH	E108	0.10	pH units	7.94	6.5 - 8.5 pH units	--	--	--	--	--
solids, total dissolved [TDS], calculated	EC103A	1.0	mg/L	800	--	--	--	--	--	--
solids, total dissolved [TDS]	E162	10	mg/L	689	DLDS 500 mg/L	--	--	--	--	--
turbidity	E121	0.10	NTU	21.4	5 NTU	--	--	--	--	--
Langelier index (@ 20°C)	EC105A	0.010	-	1.03	--	--	--	--	--	--
Langelier index (@ 4°C)	EC105A	0.010	-	0.784	--	--	--	--	--	--
pH, saturation (@ 20°C)	EC105A	0.010	pH units	6.91	--	--	--	--	--	--
pH, saturation (@ 4°C)	EC105A	0.010	pH units	7.16	--	--	--	--	--	--
Anions and Nutrients										
ammonia, total (as N)	E298	0.0050	mg/L	0.0642	--	--	--	--	--	--
bromide	E235.Br	0.10	mg/L	<0.50	DLDS	--	--	--	--	--
chloride	E235.Cl	0.50	mg/L	9.33	DLDS 250 mg/L	--	--	--	--	--
fluoride	E235.F	0.020	mg/L	0.228	DLDS	--	1.5 mg/L	--	--	--
nitrate (as N)	E235.NO3	0.020	mg/L	<0.100	DLDS	--	10 mg/L	--	--	--
nitrate + nitrite (as N)	EC235.N+N	0.0032	mg/L	<0.112		--	10 mg/L	--	--	--
nitrite (as N)	E235.NO2	0.010	mg/L	<0.050	DLDS	--	1 mg/L	--	--	--
phosphate, ortho-, dissolved (as P)	E378-T	0.0030	mg/L	<0.0030		--	--	--	--	--
sulfate (as SO4)	E235.SO4	0.30	mg/L	202	DLDS	--	--	--	--	--
Microbiological Tests										
coliforms, Escherichia coli [E. coli]	E012A.EC	1	CFU/100mL	<1	--	1 CFU/100mL	--	--	--	--



Analyte	Method	LOR	Unit	WT2222750-001 (Continued)		ONDWS AO/OG	ONDWS MAC				
Microbiological Tests - Continued											
coliforms, total background	E012.BG.TC	1	CFU/100mL	10	DLM	--	--	--	--	--	--
coliforms, total	E012.TC	1	CFU/100mL	<10	DLM	--	1 CFU/100mL	--	--	--	--
Metals											
sodium adsorption ratio [SAR]	EC102	0.10	-	0.98		--	--	--	--	--	--
Ion Balance											
anion sum	EC101A	0.10	meq/L	14.4		--	--	--	--	--	--
cation sum (total)	EC101A	0.10	meq/L	16.0		--	--	--	--	--	--
ion balance (APHA)	EC101A	0.010	%	5.26		--	--	--	--	--	--
ion balance (cations/anions)	EC101A	0.01	%	111		--	--	--	--	--	--
Total Metals											
aluminum, total	E420	0.0030	mg/L	<0.0300	DLHC	0.1 mg/L	--	--	--	--	--
antimony, total	E420	0.00010	mg/L	0.00161	DLHC	--	0.006 mg/L	--	--	--	--
arsenic, total	E420	0.00010	mg/L	0.00225	DLHC	--	0.01 mg/L	--	--	--	--
barium, total	E420	0.00010	mg/L	0.0776	DLHC	--	1 mg/L	--	--	--	--
beryllium, total	E420	0.000020	mg/L	<0.000200	DLHC	--	--	--	--	--	--
bismuth, total	E420	0.000050	mg/L	<0.000500	DLHC	--	--	--	--	--	--
boron, total	E420	0.010	mg/L	0.102	DLHC	--	5 mg/L	--	--	--	--
cadmium, total	E420	0.0000050	mg/L	<0.0000500	DLHC	--	0.005 mg/L	--	--	--	--
calcium, total	E420	0.050	mg/L	79.8	DLHC	--	--	--	--	--	--
cesium, total	E420	0.000010	mg/L	<0.000100	DLHC	--	--	--	--	--	--
chromium, total	E420	0.00050	mg/L	<0.00500	DLHC	--	0.05 mg/L	--	--	--	--
cobalt, total	E420	0.00010	mg/L	<0.00100	DLHC	--	--	--	--	--	--
copper, total	E420	0.00050	mg/L	<0.00500	DLHC	1 mg/L	--	--	--	--	--
iron, total	E420	0.010	mg/L	<0.100	DLHC	0.3 mg/L	--	--	--	--	--
lead, total	E420	0.000050	mg/L	<0.000500	DLHC	--	0.01 mg/L	--	--	--	--
lithium, total	E420	0.0010	mg/L	0.0479	DLHC	--	--	--	--	--	--
magnesium, total	E420	0.0050	mg/L	113	DLHC	--	--	--	--	--	--
manganese, total	E420	0.00010	mg/L	0.120	DLHC	0.05 mg/L	--	--	--	--	--
molybdenum, total	E420	0.000050	mg/L	0.0457	DLHC	--	--	--	--	--	--
nickel, total	E420	0.00050	mg/L	<0.00500	DLHC	--	--	--	--	--	--
phosphorus, total	E420	0.050	mg/L	<0.500	DLHC	--	--	--	--	--	--
potassium, total	E420	0.050	mg/L	6.68	DLHC	--	--	--	--	--	--
rubidium, total	E420	0.00020	mg/L	0.00227	DLHC	--	--	--	--	--	--
selenium, total	E420	0.000050	mg/L	<0.000500	DLHC	--	0.05 mg/L	--	--	--	--
silicon (as SiO2), total	EC420.SiO2	0.25	mg/L	20.7		--	--	--	--	--	--
silicon, total	E420	0.10	mg/L	9.70	DLHC	--	--	--	--	--	--



Analyte	Method	LOR	Unit	WT2222750-001 (Continued)		ONDWS AO/OG	ONDWS MAC				
Total Metals - Continued											
silver, total	E420	0.000010	mg/L	<0.000100	DLHC	--	--	--	--	--	--
sodium, total	E420	0.050	mg/L	58.4	DLHC	200 mg/L	20 mg/L	--	--	--	--
strontium, total	E420	0.00020	mg/L	0.886	DLHC	--	--	--	--	--	--
sulfur, total	E420	0.50	mg/L	72.9	DLHC	--	--	--	--	--	--
tellurium, total	E420	0.00020	mg/L	<0.00200	DLHC	--	--	--	--	--	--
thallium, total	E420	0.000010	mg/L	<0.000100	DLHC	--	--	--	--	--	--
thorium, total	E420	0.00010	mg/L	<0.00100	DLHC	--	--	--	--	--	--
tin, total	E420	0.00010	mg/L	<0.00100	DLHC	--	--	--	--	--	--
titanium, total	E420	0.00030	mg/L	<0.00300	DLHC	--	--	--	--	--	--
tungsten, total	E420	0.00010	mg/L	<0.00100	DLHC	--	--	--	--	--	--
uranium, total	E420	0.000010	mg/L	0.00836	DLHC	--	0.02 mg/L	--	--	--	--
vanadium, total	E420	0.00050	mg/L	<0.00500	DLHC	--	--	--	--	--	--
zinc, total	E420	0.0030	mg/L	<0.0300	DLHC	5 mg/L	--	--	--	--	--
zirconium, total	E420	0.00020	mg/L	<0.00200	DLHC	--	--	--	--	--	--

Please refer to the General Comments section for an explanation of any qualifiers detected.



Summary of Guideline Breaches by Sample

SampleID/Client ID	Matrix	Analyte	Analyte Summary	Guideline	Category	Result	Limit
BH13	Water	colour, apparent	May interfere with disinfection; removal is important to ensure effective treatment.	ONDWS	AO/OG	40.0 CU	5 CU
	Water	solids, total dissolved [TDS]	Based on taste; TDS above 500 mg/L results in excessive scaling in water pipes, water heaters, boilers and appliances; TDS is composed of calcium, magnesium, sodium, potassium, carbonate, bicarbonate, chloride, sulphate and nitrate.	ONDWS	AO/OG	689 mg/L	500 mg/L
	Water	turbidity	Filtration systems should be designed and operated to reduce turbidity levels as low as reasonably achievable and strive to achieve a treated water turbidity target from individual filters of less than 0.1 NTU. Particles can harbour microorganisms, protecting them from disinfection, and can entrap heavy metals and biocides; elevated or fluctuating turbidity in filtered water can indicate a problem with the water treatment process and a potential increased risk of pathogens in treated water.	ONDWS	AO/OG	21.4 NTU	5 NTU
	Water	manganese, total	Based on taste and staining of laundry and plumbing fixtures.	ONDWS	AO/OG	0.120 mg/L	0.05 mg/L
	Water	coliforms, total	Total coliforms are not used as indicators of potential health effects from pathogenic microorganisms; they are used as a tool to determine how well the drinking water treatment system is operating and to indicate water quality changes in the distribution system. Detection of total coliforms from consecutive samples from the same site or from more than 10% of the samples collected in a given sampling period should be investigated.	ONDWS	MAC	<10	1 CFU/100mL
	Water	sodium, total	Based on taste; where a sodium-based water softener is used, a separate unsoftened supply for cooking and drinking purposes is recommended.	ONDWS	MAC	58.4 mg/L	20 mg/L

Key:
 ONDWS Ontario Drinking Water Regulation (JAN, 2020)
 AO/OG Aesthetic Objective/Operational Guideline
 MAC Schedule 1 (Microbiological) and 2 (Chemical) Standards (JAN,2020)

Your Project #: 2017-0293
 Site#: BOLTON
 Site Location: SOLMAR
 Your C.O.C. #: 629279-01-01

Attention: Alireza Hejazi

Cole Engineering Group Ltd
 70 Valleywood Dr
 Markham, ON
 CANADA L3R 4T5

Report Date: 2017/09/29
 Report #: R4745503
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

Sample Matrix: Water
 # Samples Received: 1

Analyses	Quantity	Date		Laboratory Method	Reference
		Extracted	Analyzed		
Dissolved Aluminum (0.2 u, clay free)	1	N/A	2017/09/25	CAM SOP-00447	EPA 6020B m
Alkalinity	1	N/A	2017/09/26	CAM SOP-00448	SM 22 2320 B m
Chromium (VI) in Water	1	N/A	2017/09/28	CAM SOP-00436	EPA 7199 m
Free (WAD) Cyanide	1	N/A	2017/09/27	CAM SOP-00457	OMOE E3015 m
Dissolved Oxygen	1	2017/09/23	2017/09/23	CAM SOP-00427	SM 22 4500 O G m
Hardness (calculated as CaCO3)	1	N/A	2017/09/26	CAM SOP 00102/00408/00447	SM 2340 B
Mercury	1	2017/09/26	2017/09/27	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	1	N/A	2017/09/28	CAM SOP-00447	EPA 6020B m
Total Ammonia-N	1	N/A	2017/09/28	CAM SOP-00441	EPA GS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (1)	1	N/A	2017/09/28	CAM SOP-00440	SM 22 4500-NO3I/NO2B
pH	1	N/A	2017/09/26	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2017/09/26	CAM SOP-00444	OMOE E3179 m
Field pH (2)	1	N/A	2017/09/28		Field pH Meter
Sulphide	1	N/A	2017/09/26	CAM SOP-00455	SM 22 4500-S G m
Field Temperature (2)	1	N/A	2017/09/28		Field Thermometer
Total Phosphorus (Colourimetric)	1	2017/09/27	2017/09/27	CAM SOP-00407	SM 22 4500 P B H m
Turbidity	1	N/A	2017/09/24	CAM SOP-00417	SM 22 2130 B m
Un-ionized Ammonia	1	2017/09/23	2017/09/29		

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported: unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise

Your Project #: 2017-0293
Site#: BOLTON
Site Location: SOLMAR
Your C.O.C. #: 629279-01-01

Attention:Alireza Hejazi

Cole Engineering Group Ltd
70 Valleywood Dr
Markham, ON
CANADA L3R 4T5

Report Date: 2017/09/29
Report #: R4745503
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

(2) This is a field test, therefore, the results relate to items that were not analysed at Maxxam Analytics Inc.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Jolanta Goralczyk, Project Manager

Email: JGoralczyk@maxxam.ca

Phone# (905)817-5751

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK658		
Sampling Date			2017/09/22 10:15		
COC Number			629279-01-01		
	UNITS	Criteria	MW3-17	RDL	QC Batch
Calculated Parameters					
Hardness (CaCO3)	mg/L	-	560	1.0	5179429
Total Un-ionized Ammonia	mg/L	-	0.019	0.0022	5179420
Field Measurements					
Field Temperature	Celcius	-	13.79	N/A	ONSITE
Field pH	pH	6.5:8.5	8.17		ONSITE
Inorganics					
Total Ammonia-N	mg/L	-	0.44	0.050	5182709
Dissolved Oxygen	mg/L	-	4.47		5179915
pH	pH	6.5:8.5	8.05		5179875
Phenols-4AAP	mg/L	0.001	ND	0.0010	5183116
Total Phosphorus	mg/L	0.01	1.4	0.2	5184483
Sulphide	mg/L	0.02	ND	0.020	5181226
Turbidity	NTU	-	12	0.1	5179395
WAD Cyanide (Free)	ug/L	5	ND	1	5182547
Alkalinity (Total as CaCO3)	mg/L	-	250	1.0	5179872
Metals					
Dissolved (0.2u) Aluminum (Al)	ug/L	15	7	5	5179909
Chromium (VI)	ug/L	1	ND	0.50	5184085
Mercury (Hg)	ug/L	0.2	ND	0.1	5183039
Total Antimony (Sb)	ug/L	20	ND	0.50	5186729
Total Arsenic (As)	ug/L	100	2.2	1.0	5186729
Total Beryllium (Be)	ug/L	11	ND	0.50	5186729
Total Boron (B)	ug/L	200	260	10	5186729
Total Cadmium (Cd)	ug/L	0.2	ND	0.10	5186729
Total Chromium (Cr)	ug/L	-	ND	5.0	5186729
Total Cobalt (Co)	ug/L	0.9	ND	0.50	5186729
Total Copper (Cu)	ug/L	5	ND	1.0	5186729
No Fill	No Exceedance				
Grey	Exceeds 1 criteria policy/level				
Black	Exceeds both criteria/levels				
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Criteria: Ontario Provincial Water Quality Objectives					
Ref. to MOEE Water Management document dated Feb.1999					
ND = Not detected					
N/A = Not Applicable					

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK658		
Sampling Date			2017/09/22 10:15		
COC Number			629279-01-01		
	UNITS	Criteria	MW3-17	RDL	QC Batch
Total Iron (Fe)	ug/L	300	ND	100	5186729
Total Lead (Pb)	ug/L	5	ND	0.50	5186729
Total Molybdenum (Mo)	ug/L	40	11	0.50	5186729
Total Nickel (Ni)	ug/L	25	1.9	1.0	5186729
Total Selenium (Se)	ug/L	100	ND	2.0	5186729
Total Silver (Ag)	ug/L	0.1	ND	0.10	5186729
Total Thallium (Tl)	ug/L	0.3	ND	0.050	5186729
Total Tungsten (W)	ug/L	30	ND	1.0	5186729
Total Uranium (U)	ug/L	5	3.4	0.10	5186729
Total Vanadium (V)	ug/L	6	2.1	0.50	5186729
Total Zinc (Zn)	ug/L	30	ND	5.0	5186729
Total Zirconium (Zr)	ug/L	4	ND	1.0	5186729
No Fill	No Exceedance				
Grey	Exceeds 1 criteria policy/level				
Black	Exceeds both criteria/levels				
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Criteria: Ontario Provincial Water Quality Objectives					
Ref. to MOEE Water Management document dated Feb.1999					
ND = Not detected					

RESULTS OF ANALYSES OF WATER

Maxxam ID		FEK658		
Sampling Date		2017/09/22 10:15		
COC Number		629279-01-01		
	UNITS	MW3-17	RDL	QC Batch
Inorganics				
Nitrite (N)	mg/L	ND	0.010	5185563
Nitrate (N)	mg/L	ND	0.10	5185563
Nitrate + Nitrite (N)	mg/L	ND	0.10	5185563
RDL = Reportable Detection Limit QC Batch = Quality Control Batch ND = Not detected				

Draft

TEST SUMMARY

Maxxam ID: FEK656
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK656 Dup
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/25	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith

TEST SUMMARY

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK657 Dup
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
pH	AT	5179875	N/A	2017/09/25	Surinder Rai

Maxxam ID: FEK658
Sample ID: MW3-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/26	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5185563	N/A	2017/09/28	Chandra Nandlal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5183116	N/A	2017/09/26	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai

TEST SUMMARY

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181239	N/A	2017/09/25	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	13.3°C
-----------	--------

Results relate only to the items tested.

Draft

QUALITY ASSURANCE REPORT

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5179395	Turbidity	2017/09/24			101	85 - 115	ND, RDL=0.1	NTU	2.8	20		
5179872	Alkalinity (Total as CaCO3)	2017/09/25			97	85 - 115	ND, RDL=1.0	mg/L	0.70	20		
5179875	pH	2017/09/25			101	98 - 103			0.63	N/A		
5179909	Dissolved (0.2u) Aluminum (Al)	2017/09/25	110	80 - 120	102	80 - 120	ND, RDL=5	ug/L	NC	20		
5181226	Sulphide	2017/09/26	109	80 - 120	98	80 - 120	ND, RDL=0.020	mg/L	NC	20		
5181239	Sulphide	2017/09/25	96	80 - 120	105	80 - 120	ND, RDL=0.020	mg/L	3.8	20		
5181316	Nitrate (N)	2017/09/26	100	80 - 120	101	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5181316	Nitrite (N)	2017/09/26	101	80 - 120	100	80 - 120	ND, RDL=0.010	mg/L				
5182547	WAD Cyanide (Free)	2017/09/27	103	80 - 120	101	80 - 120	ND, RDL=1	ug/L	NC	20		
5182709	Total Ammonia-N	2017/09/28	99	80 - 120	99	85 - 115	ND, RDL=0.050	mg/L	6.1	20		
5183039	Mercury (Hg)	2017/09/27	100	75 - 125	102	80 - 120	ND, RDL=0.1	ug/L	NC	20		
5183116	Phenols-4AAP	2017/09/26	94	80 - 120	96	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5184085	Chromium (VI)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5184483	Total Phosphorus	2017/09/27	96	80 - 120	92	80 - 120	ND, RDL=0.004	mg/L	NC	20	93	80 - 120
5185031	Phenols-4AAP	2017/09/27	97	80 - 120	99	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5185563	Nitrate (N)	2017/09/28	84	80 - 120	98	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5185563	Nitrite (N)	2017/09/28	103	80 - 120	103	80 - 120	ND, RDL=0.010	mg/L				
5186729	Total Antimony (Sb)	2017/09/28	110	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Arsenic (As)	2017/09/28	104	80 - 120	99	80 - 120	ND, RDL=1.0	ug/L	10	20		
5186729	Total Beryllium (Be)	2017/09/28	106	80 - 120	101	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Boron (B)	2017/09/28	102	80 - 120	98	80 - 120	ND, RDL=10	ug/L	5.1	20		
5186729	Total Cadmium (Cd)	2017/09/28	105	80 - 120	99	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Chromium (Cr)	2017/09/28	104	80 - 120	100	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Cobalt (Co)	2017/09/28	107	80 - 120	103	80 - 120	ND, RDL=0.50	ug/L	5.4	20		
5186729	Total Copper (Cu)	2017/09/28	108	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	9.7	20		

QUALITY ASSURANCE REPORT(CONT'D)

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5186729	Total Iron (Fe)	2017/09/28	105	80 - 120	101	80 - 120	ND, RDL=100	ug/L	2.3	20		
5186729	Total Lead (Pb)	2017/09/28	102	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.80	20		
5186729	Total Molybdenum (Mo)	2017/09/28	108	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.14	20		
5186729	Total Nickel (Ni)	2017/09/28	100	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	8.1	20		
5186729	Total Selenium (Se)	2017/09/28	103	80 - 120	101	80 - 120	ND, RDL=2.0	ug/L	NC	20		
5186729	Total Silver (Ag)	2017/09/28	101	80 - 120	96	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Thallium (Tl)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.050	ug/L	NC	20		
5186729	Total Tungsten (W)	2017/09/28	112	80 - 120	108	80 - 120	ND, RDL=1.0	ug/L	NC	20		
5186729	Total Uranium (U)	2017/09/28	106	80 - 120	102	80 - 120	ND, RDL=0.10	ug/L	7.8	20		
5186729	Total Vanadium (V)	2017/09/28	101	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L	0.15	20		
5186729	Total Zinc (Zn)	2017/09/28	105	80 - 120	102	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Zirconium (Zr)	2017/09/28	106	80 - 120	95	80 - 120	ND, RDL=1.0	ug/L	NC	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Brad Newman, Scientific Service Specialist



Cristina Carriere, Scientific Service Specialist

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Draft

Your Project #: 2017-0293
 Site#: BOLTON
 Site Location: SOLMAR
 Your C.O.C. #: 629279-01-01

Attention: Alireza Hejazi

Cole Engineering Group Ltd
 70 Valleywood Dr
 Markham, ON
 CANADA L3R 4T5

Report Date: 2017/09/29
 Report #: R4745503
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

Sample Matrix: Water
 # Samples Received: 1

Analyses	Quantity	Date		Laboratory Method	Reference
		Extracted	Analyzed		
Dissolved Aluminum (0.2 u, clay free)	1	N/A	2017/09/25	CAM SOP-00447	EPA 6020B m
Alkalinity	1	N/A	2017/09/26	CAM SOP-00448	SM 22 2320 B m
Chromium (VI) in Water	1	N/A	2017/09/28	CAM SOP-00436	EPA 7199 m
Free (WAD) Cyanide	1	N/A	2017/09/27	CAM SOP-00457	OMOE E3015 m
Dissolved Oxygen	1	2017/09/23	2017/09/23	CAM SOP-00427	SM 22 4500 O G m
Hardness (calculated as CaCO3)	1	N/A	2017/09/27	CAM SOP 00102/00408/00447	SM 2340 B
Mercury	1	2017/09/26	2017/09/27	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	1	N/A	2017/09/28	CAM SOP-00447	EPA 6020B m
Total Ammonia-N	1	N/A	2017/09/28	CAM SOP-00441	EPA GS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (1)	1	N/A	2017/09/26	CAM SOP-00440	SM 22 4500-NO3I/NO2B
pH	1	N/A	2017/09/26	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2017/09/27	CAM SOP-00444	OMOE E3179 m
Field pH (2)	1	N/A	2017/09/28		Field pH Meter
Sulphide	1	N/A	2017/09/25	CAM SOP-00455	SM 22 4500-S G m
Field Temperature (2)	1	N/A	2017/09/28		Field Thermometer
Total Phosphorus (Colourimetric)	1	2017/09/27	2017/09/27	CAM SOP-00407	SM 22 4500 P B H m
Turbidity	1	N/A	2017/09/24	CAM SOP-00417	SM 22 2130 B m
Un-ionized Ammonia	1	2017/09/23	2017/09/29		

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported: unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise

Your Project #: 2017-0293
Site#: BOLTON
Site Location: SOLMAR
Your C.O.C. #: 629279-01-01

Attention:Alireza Hejazi

Cole Engineering Group Ltd
70 Valleywood Dr
Markham, ON
CANADA L3R 4T5

Report Date: 2017/09/29
Report #: R4745503
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

(2) This is a field test, therefore, the results relate to items that were not analysed at Maxxam Analytics Inc.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Jolanta Goralczyk, Project Manager

Email: JGoralczyk@maxxam.ca

Phone# (905)817-5751

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK659		
Sampling Date			2017/09/22 10:50		
COC Number			629279-01-01		
	UNITS	Criteria	MW4-17D	RDL	QC Batch
Calculated Parameters					
Hardness (CaCO3)	mg/L	-	310	1.0	5179429
Total Un-ionized Ammonia	mg/L	-	0.067	0.005	5179420
Field Measurements					
Field Temperature	Celcius	-	13.15	N/A	ONSITE
Field pH	pH	6.5:8.5	8.58		ONSITE
Inorganics					
Total Ammonia-N	mg/L	-	0.67	0.050	5182709
Dissolved Oxygen	mg/L	-	2.84		5179915
pH	pH	6.5:8.5	8.36		5179875
Phenols-4AAP	mg/L	0.001	ND	0.0010	5185031
Total Phosphorus	mg/L	0.01	3.3	0.2	5184483
Sulphide	mg/L	0.02	ND	0.020	5181239
Turbidity	NTU	-	3000	0.5	5179395
WAD Cyanide (Free)	ug/L	5	ND	1	5182547
Alkalinity (Total as CaCO3)	mg/L	-	340	1.0	5179872
Metals					
Dissolved (0.2u) Aluminum (Al)	ug/L	15	ND	5	5179909
Chromium (VI)	ug/L	1	ND	0.50	5184085
Mercury (Hg)	ug/L	0.2	ND	0.1	5183039
Total Antimony (Sb)	ug/L	20	0.94	0.50	5186729
Total Arsenic (As)	ug/L	100	2.8	1.0	5186729
Total Beryllium (Be)	ug/L	11	ND	0.50	5186729
Total Boron (B)	ug/L	200	110	10	5186729
Total Cadmium (Cd)	ug/L	0.2	ND	0.10	5186729
Total Chromium (Cr)	ug/L	-	ND	5.0	5186729
Total Cobalt (Co)	ug/L	0.9	2.5	0.50	5186729
Total Copper (Cu)	ug/L	5	5.5	1.0	5186729
No Fill	No Exceedance				
Grey	Exceeds 1 criteria policy/level				
Black	Exceeds both criteria/levels				
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Criteria: Ontario Provincial Water Quality Objectives					
Ref. to MOEE Water Management document dated Feb.1999					
ND = Not detected					
N/A = Not Applicable					

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK659		
Sampling Date			2017/09/22 10:50		
COC Number			629279-01-01		
	UNITS	Criteria	MW4-17D	RDL	QC Batch
Total Iron (Fe)	ug/L	300	5400	100	5186729
Total Lead (Pb)	ug/L	5	2.5	0.50	5186729
Total Molybdenum (Mo)	ug/L	40	8.4	0.50	5186729
Total Nickel (Ni)	ug/L	25	5.2	1.0	5186729
Total Selenium (Se)	ug/L	100	ND	2.0	5186729
Total Silver (Ag)	ug/L	0.1	ND	0.10	5186729
Total Thallium (Tl)	ug/L	0.3	ND	0.050	5186729
Total Tungsten (W)	ug/L	30	ND	1.0	5186729
Total Uranium (U)	ug/L	5	1.2	0.10	5186729
Total Vanadium (V)	ug/L	6	7.4	0.50	5186729
Total Zinc (Zn)	ug/L	30	21	5.0	5186729
Total Zirconium (Zr)	ug/L	4	1.1	1.0	5186729

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels

RDL = Reportable Detection Limit
 QC Batch = Quality Control Batch
 Criteria: Ontario Provincial Water Quality Objectives
 Ref. to MOEE Water Management document dated Feb.1999
 ND = Not detected

RESULTS OF ANALYSES OF WATER

Maxxam ID		FEK659		
Sampling Date		2017/09/22 10:50		
COC Number		629279-01-01		
	UNITS	MW4-17D	RDL	QC Batch
Inorganics				
Nitrite (N)	mg/L	ND	0.010	5181316
Nitrate (N)	mg/L	ND	0.10	5181316
Nitrate + Nitrite (N)	mg/L	ND	0.10	5181316
RDL = Reportable Detection Limit QC Batch = Quality Control Batch ND = Not detected				

Draft

TEST SUMMARY

Maxxam ID: FEK656
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK656 Dup
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/25	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith

TEST SUMMARY

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK657 Dup
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
pH	AT	5179875	N/A	2017/09/25	Surinder Rai

Maxxam ID: FEK658
Sample ID: MW3-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/26	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5185563	N/A	2017/09/28	Chandra Nandlal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5183116	N/A	2017/09/26	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai

TEST SUMMARY

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181239	N/A	2017/09/25	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	13.3°C
-----------	--------

Results relate only to the items tested.

Draft

QUALITY ASSURANCE REPORT

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5179395	Turbidity	2017/09/24			101	85 - 115	ND, RDL=0.1	NTU	2.8	20		
5179872	Alkalinity (Total as CaCO3)	2017/09/25			97	85 - 115	ND, RDL=1.0	mg/L	0.70	20		
5179875	pH	2017/09/25			101	98 - 103			0.63	N/A		
5179909	Dissolved (0.2u) Aluminum (Al)	2017/09/25	110	80 - 120	102	80 - 120	ND, RDL=5	ug/L	NC	20		
5181226	Sulphide	2017/09/26	109	80 - 120	98	80 - 120	ND, RDL=0.020	mg/L	NC	20		
5181239	Sulphide	2017/09/25	96	80 - 120	105	80 - 120	ND, RDL=0.020	mg/L	3.8	20		
5181316	Nitrate (N)	2017/09/26	100	80 - 120	101	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5181316	Nitrite (N)	2017/09/26	101	80 - 120	100	80 - 120	ND, RDL=0.010	mg/L				
5182547	WAD Cyanide (Free)	2017/09/27	103	80 - 120	101	80 - 120	ND, RDL=1	ug/L	NC	20		
5182709	Total Ammonia-N	2017/09/28	99	80 - 120	99	85 - 115	ND, RDL=0.050	mg/L	6.1	20		
5183039	Mercury (Hg)	2017/09/27	100	75 - 125	102	80 - 120	ND, RDL=0.1	ug/L	NC	20		
5183116	Phenols-4AAP	2017/09/26	94	80 - 120	96	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5184085	Chromium (VI)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5184483	Total Phosphorus	2017/09/27	96	80 - 120	92	80 - 120	ND, RDL=0.004	mg/L	NC	20	93	80 - 120
5185031	Phenols-4AAP	2017/09/27	97	80 - 120	99	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5185563	Nitrate (N)	2017/09/28	84	80 - 120	98	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5185563	Nitrite (N)	2017/09/28	103	80 - 120	103	80 - 120	ND, RDL=0.010	mg/L				
5186729	Total Antimony (Sb)	2017/09/28	110	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Arsenic (As)	2017/09/28	104	80 - 120	99	80 - 120	ND, RDL=1.0	ug/L	10	20		
5186729	Total Beryllium (Be)	2017/09/28	106	80 - 120	101	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Boron (B)	2017/09/28	102	80 - 120	98	80 - 120	ND, RDL=10	ug/L	5.1	20		
5186729	Total Cadmium (Cd)	2017/09/28	105	80 - 120	99	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Chromium (Cr)	2017/09/28	104	80 - 120	100	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Cobalt (Co)	2017/09/28	107	80 - 120	103	80 - 120	ND, RDL=0.50	ug/L	5.4	20		
5186729	Total Copper (Cu)	2017/09/28	108	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	9.7	20		

QUALITY ASSURANCE REPORT(CONT'D)

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5186729	Total Iron (Fe)	2017/09/28	105	80 - 120	101	80 - 120	ND, RDL=100	ug/L	2.3	20		
5186729	Total Lead (Pb)	2017/09/28	102	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.80	20		
5186729	Total Molybdenum (Mo)	2017/09/28	108	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.14	20		
5186729	Total Nickel (Ni)	2017/09/28	100	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	8.1	20		
5186729	Total Selenium (Se)	2017/09/28	103	80 - 120	101	80 - 120	ND, RDL=2.0	ug/L	NC	20		
5186729	Total Silver (Ag)	2017/09/28	101	80 - 120	96	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Thallium (Tl)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.050	ug/L	NC	20		
5186729	Total Tungsten (W)	2017/09/28	112	80 - 120	108	80 - 120	ND, RDL=1.0	ug/L	NC	20		
5186729	Total Uranium (U)	2017/09/28	106	80 - 120	102	80 - 120	ND, RDL=0.10	ug/L	7.8	20		
5186729	Total Vanadium (V)	2017/09/28	101	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L	0.15	20		
5186729	Total Zinc (Zn)	2017/09/28	105	80 - 120	102	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Zirconium (Zr)	2017/09/28	106	80 - 120	95	80 - 120	ND, RDL=1.0	ug/L	NC	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Brad Newman, Scientific Service Specialist



Cristina Carriere, Scientific Service Specialist

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Draft

Your Project #: 2017-0293
 Site#: BOLTON
 Site Location: SOLMAR
 Your C.O.C. #: 629279-01-01

Attention:Alireza Hejazi

Cole Engineering Group Ltd
 70 Valleywood Dr
 Markham, ON
 CANADA L3R 4T5

Report Date: 2017/09/29
 Report #: R4745503
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

Sample Matrix: Water
 # Samples Received: 4

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Dissolved Aluminum (0.2 u, clay free)	4	N/A	2017/09/25	CAM SOP-00447	EPA 6020B m
Alkalinity	1	N/A	2017/09/25	CAM SOP-00448	SM 22 2320 B m
Alkalinity	3	N/A	2017/09/26	CAM SOP-00448	SM 22 2320 B m
Chromium (VI) in Water	4	N/A	2017/09/28	CAM SOP-00436	EPA 7199 m
Free (WAD) Cyanide	4	N/A	2017/09/27	CAM SOP-00457	OMOE E3015 m
Dissolved Oxygen	4	2017/09/23	2017/09/23	CAM SOP-00427	SM 22 4500 O G m
Hardness (calculated as CaCO3)	1	N/A	2017/09/26	CAM SOP 00102/00408/00447	SM 2340 B
Hardness (calculated as CaCO3)	3	N/A	2017/09/27	CAM SOP 00102/00408/00447	SM 2340 B
Mercury	4	2017/09/26	2017/09/27	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	4	N/A	2017/09/28	CAM SOP-00447	EPA 6020B m
Total Ammonia-N	4	N/A	2017/09/28	CAM SOP-00441	EPA GS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (1)	3	N/A	2017/09/26	CAM SOP-00440	SM 22 4500-NO3I/NO2B
Nitrate (NO3) and Nitrite (NO2) in Water (1)	1	N/A	2017/09/28	CAM SOP-00440	SM 22 4500-NO3I/NO2B
pH	1	N/A	2017/09/25	CAM SOP-00413	SM 4500H+ B m
pH	3	N/A	2017/09/26	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2017/09/26	CAM SOP-00444	OMOE E3179 m
Phenols (4AAP)	3	N/A	2017/09/27	CAM SOP-00444	OMOE E3179 m
Field pH (2)	4	N/A	2017/09/28		Field pH Meter
Sulphide	1	N/A	2017/09/25	CAM SOP-00455	SM 22 4500-S G m
Sulphide	3	N/A	2017/09/26	CAM SOP-00455	SM 22 4500-S G m
Field Temperature (2)	4	N/A	2017/09/28		Field Thermometer
Total Phosphorus (Colourimetric)	4	2017/09/27	2017/09/27	CAM SOP-00407	SM 22 4500 P B H m
Turbidity	4	N/A	2017/09/24	CAM SOP-00417	SM 22 2130 B m
Un-ionized Ammonia	4	2017/09/23	2017/09/29		

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

Your Project #: 2017-0293
Site#: BOLTON
Site Location: SOLMAR
Your C.O.C. #: 629279-01-01

Attention:Alireza Hejazi

Cole Engineering Group Ltd
70 Valleywood Dr
Markham, ON
CANADA L3R 4T5

Report Date: 2017/09/29
Report #: R4745503
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported: unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

(2) This is a field test, therefore, the results relate to items that were not analysed at Maxxam Analytics Inc.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Jolanta Goralczyk, Project Manager

Email: JGoralczyk@maxxam.ca

Phone# (905)817-5751

=====
Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK656	FEK656		FEK657	FEK657		
Sampling Date			2017/09/22 12:45	2017/09/22 12:45		2017/09/22 11:50	2017/09/22 11:50		
COC Number			629279-01-01	629279-01-01		629279-01-01	629279-01-01		
	UNITS	Criteria	MW1-17	MW1-17 Lab-Dup	RDL	MW5-17S	MW5-17S Lab-Dup	RDL	QC Batch
Calculated Parameters									
Hardness (CaCO3)	mg/L	-	590		1.0	230		1.0	5179429
Total Un-ionized Ammonia	mg/L	-	0.0037		0.0016	0.11		0.0054	5179420
Field Measurements									
Field Temperature	Celcius	-	15.7		N/A	14.7		N/A	ONSITE
Field pH	pH	6.5:8.5	7.98			8.56			ONSITE
Inorganics									
Total Ammonia-N	mg/L	-	0.11		0.050	1.0		0.050	5182709
Dissolved Oxygen	mg/L	-	5.77	5.82		3.94			5179915
pH	pH	6.5:8.5	8.02			8.06	8.12		5179875
Phenols-4AAP	mg/L	0.001	ND		0.0010	ND		0.0010	5185031
Total Phosphorus	mg/L	0.01	0.36		0.02	0.8		0.1	5184483
Sulphide	mg/L	0.02	ND		0.020	ND		0.020	5181226
Turbidity	NTU	-	6.1		0.1	28		0.1	5179395
WAD Cyanide (Free)	ug/L	5	ND		1	ND		1	5182547
Alkalinity (Total as CaCO3)	mg/L	-	520		1.0	110	110	1.0	5179872
Metals									
Dissolved (0.2u) Aluminum (Al)	ug/L	15	ND		5	6		5	5179909
Chromium (VI)	ug/L	1	ND	ND	0.50	ND		0.50	5184085
Mercury (Hg)	ug/L	0.2	ND		0.1	ND		0.1	5183039
Total Antimony (Sb)	ug/L	20	ND		0.50	0.58		0.50	5186729
Total Arsenic (As)	ug/L	100	ND		1.0	ND		1.0	5186729
Total Beryllium (Be)	ug/L	11	ND		0.50	ND		0.50	5186729
Total Boron (B)	ug/L	200	110		10	420		10	5186729
Total Cadmium (Cd)	ug/L	0.2	ND		0.10	ND		0.10	5186729
Total Chromium (Cr)	ug/L	-	ND		5.0	ND		5.0	5186729
Total Cobalt (Co)	ug/L	0.9	ND		0.50	ND		0.50	5186729
Total Copper (Cu)	ug/L	5	1.6		1.0	1.3		1.0	5186729
Total Iron (Fe)	ug/L	300	ND		100	ND		100	5186729
No Fill	No Exceedance								
Grey	Exceeds 1 criteria policy/level								
Black	Exceeds both criteria/levels								
RDL = Reportable Detection Limit									
QC Batch = Quality Control Batch									
Lab-Dup = Laboratory Initiated Duplicate									
Criteria: Ontario Provincial Water Quality Objectives									
Ref. to MOEE Water Management document dated Feb.1999									
ND = Not detected									

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK656	FEK656		FEK657	FEK657		
Sampling Date			2017/09/22 12:45	2017/09/22 12:45		2017/09/22 11:50	2017/09/22 11:50		
COC Number			629279-01-01	629279-01-01		629279-01-01	629279-01-01		
	UNITS	Criteria	MW1-17	MW1-17 Lab-Dup	RDL	MW5-17S	MW5-17S Lab-Dup	RDL	QC Batch
Total Lead (Pb)	ug/L	5	ND		0.50	ND		0.50	5186729
Total Molybdenum (Mo)	ug/L	40	6.9		0.50	5.9		0.50	5186729
Total Nickel (Ni)	ug/L	25	2.6		1.0	ND		1.0	5186729
Total Selenium (Se)	ug/L	100	ND		2.0	ND		2.0	5186729
Total Silver (Ag)	ug/L	0.1	ND		0.10	ND		0.10	5186729
Total Thallium (Tl)	ug/L	0.3	ND		0.050	ND		0.050	5186729
Total Tungsten (W)	ug/L	30	ND		1.0	ND		1.0	5186729
Total Uranium (U)	ug/L	5	9.2		0.10	1.2		0.10	5186729
Total Vanadium (V)	ug/L	6	ND		0.50	0.74		0.50	5186729
Total Zinc (Zn)	ug/L	30	ND		5.0	ND		5.0	5186729
Total Zirconium (Zr)	ug/L	4	ND		1.0	ND		1.0	5186729

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels

RDL = Reportable Detection Limit
 QC Batch = Quality Control Batch
 Lab-Dup = Laboratory Initiated Duplicate
 Criteria: Ontario Provincial Water Quality Objectives
 Ref. to MOEE Water Management document dated Feb.1999
 ND = Not detected

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK658			FEK659		
Sampling Date			2017/09/22 10:15			2017/09/22 10:50		
COC Number			629279-01-01			629279-01-01		
	UNITS	Criteria	MW3-17	RDL	QC Batch	MW4-17D	RDL	QC Batch
Calculated Parameters								
Hardness (CaCO ₃)	mg/L	-	560	1.0	5179429	310	1.0	5179429
Total Un-ionized Ammonia	mg/L	-	0.019	0.0022	5179420	0.067	0.005	5179420
Field Measurements								
Field Temperature	Celcius	-	13.79	N/A	ONSITE	13.15	N/A	ONSITE
Field pH	pH	6.5:8.5	8.17		ONSITE	8.58		ONSITE
Inorganics								
Total Ammonia-N	mg/L	-	0.44	0.050	5182709	0.67	0.050	5182709
Dissolved Oxygen	mg/L	-	4.47		5179915	2.84		5179915
pH	pH	6.5:8.5	8.05		5179875	8.36		5179875
Phenols-4AAP	mg/L	0.001	ND	0.0010	5183116	ND	0.0010	5185031
Total Phosphorus	mg/L	0.01	1.4	0.2	5184483	3.3	0.2	5184483
Sulphide	mg/L	0.02	ND	0.020	5181226	ND	0.020	5181239
Turbidity	NTU	-	12	0.1	5179395	3000	0.5	5179395
WAD Cyanide (Free)	ug/L	5	ND	1	5182547	ND	1	5182547
Alkalinity (Total as CaCO ₃)	mg/L	-	250	1.0	5179872	340	1.0	5179872
Metals								
Dissolved (0.2u) Aluminum (Al)	ug/L	15	7	5	5179909	ND	5	5179909
Chromium (VI)	ug/L	1	ND	0.50	5184085	ND	0.50	5184085
Mercury (Hg)	ug/L	0.2	ND	0.1	5183039	ND	0.1	5183039
Total Antimony (Sb)	ug/L	20	ND	0.50	5186729	0.94	0.50	5186729
Total Arsenic (As)	ug/L	100	2.2	1.0	5186729	2.8	1.0	5186729
Total Beryllium (Be)	ug/L	11	ND	0.50	5186729	ND	0.50	5186729
Total Boron (B)	ug/L	200	260	10	5186729	110	10	5186729
Total Cadmium (Cd)	ug/L	0.2	ND	0.10	5186729	ND	0.10	5186729
Total Chromium (Cr)	ug/L	-	ND	5.0	5186729	ND	5.0	5186729
Total Cobalt (Co)	ug/L	0.9	ND	0.50	5186729	2.5	0.50	5186729
Total Copper (Cu)	ug/L	5	ND	1.0	5186729	5.5	1.0	5186729
Total Iron (Fe)	ug/L	300	ND	100	5186729	5400	100	5186729
No Fill	No Exceedance							
Grey	Exceeds 1 criteria policy/level							
Black	Exceeds both criteria/levels							
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
Criteria: Ontario Provincial Water Quality Objectives								
Ref. to MOEE Water Management document dated Feb.1999								
N/A = Not Applicable								
ND = Not detected								

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK658			FEK659		
Sampling Date			2017/09/22 10:15			2017/09/22 10:50		
COC Number			629279-01-01			629279-01-01		
	UNITS	Criteria	MW3-17	RDL	QC Batch	MW4-17D	RDL	QC Batch
Total Lead (Pb)	ug/L	5	ND	0.50	5186729	2.5	0.50	5186729
Total Molybdenum (Mo)	ug/L	40	11	0.50	5186729	8.4	0.50	5186729
Total Nickel (Ni)	ug/L	25	1.9	1.0	5186729	5.2	1.0	5186729
Total Selenium (Se)	ug/L	100	ND	2.0	5186729	ND	2.0	5186729
Total Silver (Ag)	ug/L	0.1	ND	0.10	5186729	ND	0.10	5186729
Total Thallium (Tl)	ug/L	0.3	ND	0.050	5186729	ND	0.050	5186729
Total Tungsten (W)	ug/L	30	ND	1.0	5186729	ND	1.0	5186729
Total Uranium (U)	ug/L	5	3.4	0.10	5186729	1.2	0.10	5186729
Total Vanadium (V)	ug/L	6	2.1	0.50	5186729	7.4	0.50	5186729
Total Zinc (Zn)	ug/L	30	ND	5.0	5186729	21	5.0	5186729
Total Zirconium (Zr)	ug/L	4	ND	1.0	5186729	1.1	1.0	5186729

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels

RDL = Reportable Detection Limit
QC Batch = Quality Control Batch
Criteria: Ontario Provincial Water Quality Objectives
Ref. to MOEE Water Management document dated Feb.1999
ND = Not detected

RESULTS OF ANALYSES OF WATER

Maxxam ID		FEK656	FEK657		FEK658		FEK659		
Sampling Date		2017/09/22 12:45	2017/09/22 11:50		2017/09/22 10:15		2017/09/22 10:50		
COC Number		629279-01-01	629279-01-01		629279-01-01		629279-01-01		
	UNITS	MW1-17	MW5-17S	QC Batch	MW3-17	QC Batch	MW4-17D	RDL	QC Batch
Inorganics									
Nitrite (N)	mg/L	ND	0.013	5181316	ND	5185563	ND	0.010	5181316
Nitrate (N)	mg/L	ND	ND	5181316	ND	5185563	ND	0.10	5181316
Nitrate + Nitrite (N)	mg/L	ND	ND	5181316	ND	5185563	ND	0.10	5181316
RDL = Reportable Detection Limit QC Batch = Quality Control Batch ND = Not detected									

Draft

TEST SUMMARY

Maxxam ID: FEK656
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK656 Dup
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/25	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith

TEST SUMMARY

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK657 Dup
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
pH	AT	5179875	N/A	2017/09/25	Surinder Rai

Maxxam ID: FEK658
Sample ID: MW3-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/26	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5185563	N/A	2017/09/28	Chandra Nandlal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5183116	N/A	2017/09/26	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai

TEST SUMMARY

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181239	N/A	2017/09/25	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	13.3°C
-----------	--------

Results relate only to the items tested.

Draft

QUALITY ASSURANCE REPORT

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5179395	Turbidity	2017/09/24			101	85 - 115	ND, RDL=0.1	NTU	2.8	20		
5179872	Alkalinity (Total as CaCO3)	2017/09/25			97	85 - 115	ND, RDL=1.0	mg/L	0.70	20		
5179875	pH	2017/09/25			101	98 - 103			0.63	N/A		
5179909	Dissolved (0.2u) Aluminum (Al)	2017/09/25	110	80 - 120	102	80 - 120	ND, RDL=5	ug/L	NC	20		
5181226	Sulphide	2017/09/26	109	80 - 120	98	80 - 120	ND, RDL=0.020	mg/L	NC	20		
5181239	Sulphide	2017/09/25	96	80 - 120	105	80 - 120	ND, RDL=0.020	mg/L	3.8	20		
5181316	Nitrate (N)	2017/09/26	100	80 - 120	101	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5181316	Nitrite (N)	2017/09/26	101	80 - 120	100	80 - 120	ND, RDL=0.010	mg/L				
5182547	WAD Cyanide (Free)	2017/09/27	103	80 - 120	101	80 - 120	ND, RDL=1	ug/L	NC	20		
5182709	Total Ammonia-N	2017/09/28	99	80 - 120	99	85 - 115	ND, RDL=0.050	mg/L	6.1	20		
5183039	Mercury (Hg)	2017/09/27	100	75 - 125	102	80 - 120	ND, RDL=0.1	ug/L	NC	20		
5183116	Phenols-4AAP	2017/09/26	94	80 - 120	96	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5184085	Chromium (VI)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5184483	Total Phosphorus	2017/09/27	96	80 - 120	92	80 - 120	ND, RDL=0.004	mg/L	NC	20	93	80 - 120
5185031	Phenols-4AAP	2017/09/27	97	80 - 120	99	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5185563	Nitrate (N)	2017/09/28	84	80 - 120	98	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5185563	Nitrite (N)	2017/09/28	103	80 - 120	103	80 - 120	ND, RDL=0.010	mg/L				
5186729	Total Antimony (Sb)	2017/09/28	110	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Arsenic (As)	2017/09/28	104	80 - 120	99	80 - 120	ND, RDL=1.0	ug/L	10	20		
5186729	Total Beryllium (Be)	2017/09/28	106	80 - 120	101	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Boron (B)	2017/09/28	102	80 - 120	98	80 - 120	ND, RDL=10	ug/L	5.1	20		
5186729	Total Cadmium (Cd)	2017/09/28	105	80 - 120	99	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Chromium (Cr)	2017/09/28	104	80 - 120	100	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Cobalt (Co)	2017/09/28	107	80 - 120	103	80 - 120	ND, RDL=0.50	ug/L	5.4	20		
5186729	Total Copper (Cu)	2017/09/28	108	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	9.7	20		

QUALITY ASSURANCE REPORT(CONT'D)

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5186729	Total Iron (Fe)	2017/09/28	105	80 - 120	101	80 - 120	ND, RDL=100	ug/L	2.3	20		
5186729	Total Lead (Pb)	2017/09/28	102	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.80	20		
5186729	Total Molybdenum (Mo)	2017/09/28	108	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.14	20		
5186729	Total Nickel (Ni)	2017/09/28	100	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	8.1	20		
5186729	Total Selenium (Se)	2017/09/28	103	80 - 120	101	80 - 120	ND, RDL=2.0	ug/L	NC	20		
5186729	Total Silver (Ag)	2017/09/28	101	80 - 120	96	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Thallium (Tl)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.050	ug/L	NC	20		
5186729	Total Tungsten (W)	2017/09/28	112	80 - 120	108	80 - 120	ND, RDL=1.0	ug/L	NC	20		
5186729	Total Uranium (U)	2017/09/28	106	80 - 120	102	80 - 120	ND, RDL=0.10	ug/L	7.8	20		
5186729	Total Vanadium (V)	2017/09/28	101	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L	0.15	20		
5186729	Total Zinc (Zn)	2017/09/28	105	80 - 120	102	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Zirconium (Zr)	2017/09/28	106	80 - 120	95	80 - 120	ND, RDL=1.0	ug/L	NC	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Brad Newman, Scientific Service Specialist



Cristina Carriere, Scientific Service Specialist

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Draft

Your Project #: 2017-0293
 Site#: BOLTON
 Site Location: SOLMAR
 Your C.O.C. #: 629279-01-01

Attention: Alireza Hejazi

Cole Engineering Group Ltd
 70 Valleywood Dr
 Markham, ON
 CANADA L3R 4T5

Report Date: 2017/09/29

Report #: R4745503

Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

Sample Matrix: Water
 # Samples Received: 1

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Dissolved Aluminum (0.2 u, clay free)	1	N/A	2017/09/25	CAM SOP-00447	EPA 6020B m
Alkalinity	1	N/A	2017/09/26	CAM SOP-00448	SM 22 2320 B m
Chromium (VI) in Water	1	N/A	2017/09/28	CAM SOP-00436	EPA 7199 m
Free (WAD) Cyanide	1	N/A	2017/09/27	CAM SOP-00457	OMOE E3015 m
Dissolved Oxygen	1	2017/09/23	2017/09/23	CAM SOP-00427	SM 22 4500 O G m
Hardness (calculated as CaCO3)	1	N/A	2017/09/27	CAM SOP 00102/00408/00447	SM 2340 B
Mercury	1	2017/09/26	2017/09/27	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	1	N/A	2017/09/28	CAM SOP-00447	EPA 6020B m
Total Ammonia-N	1	N/A	2017/09/28	CAM SOP-00441	EPA GS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (1)	1	N/A	2017/09/26	CAM SOP-00440	SM 22 4500-NO3I/NO2B
pH	1	N/A	2017/09/26	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2017/09/27	CAM SOP-00444	OMOE E3179 m
Field pH (2)	1	N/A	2017/09/28		Field pH Meter
Sulphide	1	N/A	2017/09/26	CAM SOP-00455	SM 22 4500-S G m
Field Temperature (2)	1	N/A	2017/09/28		Field Thermometer
Total Phosphorus (Colourimetric)	1	2017/09/27	2017/09/27	CAM SOP-00407	SM 22 4500 P B H m
Turbidity	1	N/A	2017/09/24	CAM SOP-00417	SM 22 2130 B m
Un-ionized Ammonia	1	2017/09/23	2017/09/29		

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported: unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise

Your Project #: 2017-0293
Site#: BOLTON
Site Location: SOLMAR
Your C.O.C. #: 629279-01-01

Attention:Alireza Hejazi

Cole Engineering Group Ltd
70 Valleywood Dr
Markham, ON
CANADA L3R 4T5

Report Date: 2017/09/29
Report #: R4745503
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B7K8760

Received: 2017/09/22, 14:25

agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

(2) This is a field test, therefore, the results relate to items that were not analysed at Maxxam Analytics Inc.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Jolanta Goralczyk, Project Manager

Email: JGoralczyk@maxxam.ca

Phone# (905)817-5751

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK656		
Sampling Date			2017/09/22 12:45		
COC Number			629279-01-01		
	UNITS	Criteria	MW1-17	RDL	QC Batch
Calculated Parameters					
Hardness (CaCO3)	mg/L	-	590	1.0	5179429
Total Un-ionized Ammonia	mg/L	-	0.0037	0.0016	5179420
Field Measurements					
Field Temperature	Celcius	-	15.7	N/A	ONSITE
Field pH	pH	6.5:8.5	7.98		ONSITE
Inorganics					
Total Ammonia-N	mg/L	-	0.11	0.050	5182709
Dissolved Oxygen	mg/L	-	5.77		5179915
pH	pH	6.5:8.5	8.02		5179875
Phenols-4AAP	mg/L	0.001	ND	0.0010	5185031
Total Phosphorus	mg/L	0.01	0.36	0.02	5184483
Sulphide	mg/L	0.02	ND	0.020	5181226
Turbidity	NTU	-	6.1	0.1	5179395
WAD Cyanide (Free)	ug/L	5	ND	1	5182547
Alkalinity (Total as CaCO3)	mg/L	-	520	1.0	5179872
Metals					
Dissolved (0.2u) Aluminum (Al)	ug/L	15	ND	5	5179909
Chromium (VI)	ug/L	1	ND	0.50	5184085
Mercury (Hg)	ug/L	0.2	ND	0.1	5183039
Total Antimony (Sb)	ug/L	20	ND	0.50	5186729
Total Arsenic (As)	ug/L	100	ND	1.0	5186729
Total Beryllium (Be)	ug/L	11	ND	0.50	5186729
Total Boron (B)	ug/L	200	110	10	5186729
Total Cadmium (Cd)	ug/L	0.2	ND	0.10	5186729
Total Chromium (Cr)	ug/L	-	ND	5.0	5186729
Total Cobalt (Co)	ug/L	0.9	ND	0.50	5186729
Total Copper (Cu)	ug/L	5	1.6	1.0	5186729
No Fill	No Exceedance				
Grey	Exceeds 1 criteria policy/level				
Black	Exceeds both criteria/levels				
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Criteria: Ontario Provincial Water Quality Objectives					
Ref. to MOEE Water Management document dated Feb.1999					
ND = Not detected					
N/A = Not Applicable					

PWQO METALS AND INORGANICS (WATER)

Maxxam ID			FEK656		
Sampling Date			2017/09/22 12:45		
COC Number			629279-01-01		
	UNITS	Criteria	MW1-17	RDL	QC Batch
Total Iron (Fe)	ug/L	300	ND	100	5186729
Total Lead (Pb)	ug/L	5	ND	0.50	5186729
Total Molybdenum (Mo)	ug/L	40	6.9	0.50	5186729
Total Nickel (Ni)	ug/L	25	2.6	1.0	5186729
Total Selenium (Se)	ug/L	100	ND	2.0	5186729
Total Silver (Ag)	ug/L	0.1	ND	0.10	5186729
Total Thallium (Tl)	ug/L	0.3	ND	0.050	5186729
Total Tungsten (W)	ug/L	30	ND	1.0	5186729
Total Uranium (U)	ug/L	5	9.2	0.10	5186729
Total Vanadium (V)	ug/L	6	ND	0.50	5186729
Total Zinc (Zn)	ug/L	30	ND	5.0	5186729
Total Zirconium (Zr)	ug/L	4	ND	1.0	5186729
No Fill	No Exceedance				
Grey	Exceeds 1 criteria policy/level				
Black	Exceeds both criteria/levels				
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Criteria: Ontario Provincial Water Quality Objectives					
Ref. to MOEE Water Management document dated Feb.1999					
ND = Not detected					

RESULTS OF ANALYSES OF WATER

Maxxam ID		FEK656		
Sampling Date		2017/09/22 12:45		
COC Number		629279-01-01		
	UNITS	MW1-17	RDL	QC Batch
Inorganics				
Nitrite (N)	mg/L	ND	0.010	5181316
Nitrate (N)	mg/L	ND	0.10	5181316
Nitrate + Nitrite (N)	mg/L	ND	0.10	5181316
RDL = Reportable Detection Limit QC Batch = Quality Control Batch ND = Not detected				

Draft

TEST SUMMARY

Maxxam ID: FEK656
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK656 Dup
Sample ID: MW1-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/25	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith

TEST SUMMARY

Maxxam ID: FEK657
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK657 Dup
Sample ID: MW5-17S
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	5179872	N/A	2017/09/25	Surinder Rai
pH	AT	5179875	N/A	2017/09/25	Surinder Rai

Maxxam ID: FEK658
Sample ID: MW3-17
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/26	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5185563	N/A	2017/09/28	Chandra Nandlal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5183116	N/A	2017/09/26	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181226	N/A	2017/09/26	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Aluminum (0.2 u, clay free)	ICP/MS	5179909	N/A	2017/09/25	Prempal Bhatti
Alkalinity	AT	5179872	N/A	2017/09/26	Surinder Rai

TEST SUMMARY

Maxxam ID: FEK659
Sample ID: MW4-17D
Matrix: Water

Collected: 2017/09/22
Shipped:
Received: 2017/09/22

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	5184085	N/A	2017/09/28	Lang Le
Free (WAD) Cyanide	SKAL/CN	5182547	N/A	2017/09/27	Louise Harding
Dissolved Oxygen	DO	5179915	2017/09/23	2017/09/23	Prakash Piya
Hardness (calculated as CaCO3)		5179429	N/A	2017/09/27	Automated Statchk
Mercury	CV/AA	5183039	2017/09/26	2017/09/27	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	5186729	N/A	2017/09/28	Arefa Dabhad
Total Ammonia-N	LACH/NH4	5182709	N/A	2017/09/28	Sarabjit Raina
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	5181316	N/A	2017/09/26	Amanpreet Sappal
pH	AT	5179875	N/A	2017/09/26	Surinder Rai
Phenols (4AAP)	TECH/PHEN	5185031	N/A	2017/09/27	Zahid Soikot
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Sulphide	ISE/S	5181239	N/A	2017/09/25	Tahir Anwar
Field pH	PH	ONSITE	N/A	2017/09/23	Adriana Smith
Total Phosphorus (Colourimetric)	LACH/P	5184483	2017/09/27	2017/09/27	Amanpreet Sappal
Turbidity	AT	5179395	N/A	2017/09/24	Neil Dassanayake
Un-ionized Ammonia	CALC/NH3	5179420	2017/09/29	2017/09/29	Automated Statchk

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	13.3°C
-----------	--------

Results relate only to the items tested.

Draft

QUALITY ASSURANCE REPORT

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5179395	Turbidity	2017/09/24			101	85 - 115	ND, RDL=0.1	NTU	2.8	20		
5179872	Alkalinity (Total as CaCO3)	2017/09/25			97	85 - 115	ND, RDL=1.0	mg/L	0.70	20		
5179875	pH	2017/09/25			101	98 - 103			0.63	N/A		
5179909	Dissolved (0.2u) Aluminum (Al)	2017/09/25	110	80 - 120	102	80 - 120	ND, RDL=5	ug/L	NC	20		
5181226	Sulphide	2017/09/26	109	80 - 120	98	80 - 120	ND, RDL=0.020	mg/L	NC	20		
5181239	Sulphide	2017/09/25	96	80 - 120	105	80 - 120	ND, RDL=0.020	mg/L	3.8	20		
5181316	Nitrate (N)	2017/09/26	100	80 - 120	101	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5181316	Nitrite (N)	2017/09/26	101	80 - 120	100	80 - 120	ND, RDL=0.010	mg/L				
5182547	WAD Cyanide (Free)	2017/09/27	103	80 - 120	101	80 - 120	ND, RDL=1	ug/L	NC	20		
5182709	Total Ammonia-N	2017/09/28	99	80 - 120	99	85 - 115	ND, RDL=0.050	mg/L	6.1	20		
5183039	Mercury (Hg)	2017/09/27	100	75 - 125	102	80 - 120	ND, RDL=0.1	ug/L	NC	20		
5183116	Phenols-4AAP	2017/09/26	94	80 - 120	96	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5184085	Chromium (VI)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5184483	Total Phosphorus	2017/09/27	96	80 - 120	92	80 - 120	ND, RDL=0.004	mg/L	NC	20	93	80 - 120
5185031	Phenols-4AAP	2017/09/27	97	80 - 120	99	85 - 115	ND, RDL=0.0010	mg/L	NC	20		
5185563	Nitrate (N)	2017/09/28	84	80 - 120	98	80 - 120	ND, RDL=0.10	mg/L	NC	20		
5185563	Nitrite (N)	2017/09/28	103	80 - 120	103	80 - 120	ND, RDL=0.010	mg/L				
5186729	Total Antimony (Sb)	2017/09/28	110	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Arsenic (As)	2017/09/28	104	80 - 120	99	80 - 120	ND, RDL=1.0	ug/L	10	20		
5186729	Total Beryllium (Be)	2017/09/28	106	80 - 120	101	80 - 120	ND, RDL=0.50	ug/L	NC	20		
5186729	Total Boron (B)	2017/09/28	102	80 - 120	98	80 - 120	ND, RDL=10	ug/L	5.1	20		
5186729	Total Cadmium (Cd)	2017/09/28	105	80 - 120	99	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Chromium (Cr)	2017/09/28	104	80 - 120	100	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Cobalt (Co)	2017/09/28	107	80 - 120	103	80 - 120	ND, RDL=0.50	ug/L	5.4	20		
5186729	Total Copper (Cu)	2017/09/28	108	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	9.7	20		

QUALITY ASSURANCE REPORT(CONT'D)

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5186729	Total Iron (Fe)	2017/09/28	105	80 - 120	101	80 - 120	ND, RDL=100	ug/L	2.3	20		
5186729	Total Lead (Pb)	2017/09/28	102	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.80	20		
5186729	Total Molybdenum (Mo)	2017/09/28	108	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	0.14	20		
5186729	Total Nickel (Ni)	2017/09/28	100	80 - 120	97	80 - 120	ND, RDL=1.0	ug/L	8.1	20		
5186729	Total Selenium (Se)	2017/09/28	103	80 - 120	101	80 - 120	ND, RDL=2.0	ug/L	NC	20		
5186729	Total Silver (Ag)	2017/09/28	101	80 - 120	96	80 - 120	ND, RDL=0.10	ug/L	NC	20		
5186729	Total Thallium (Tl)	2017/09/28	101	80 - 120	102	80 - 120	ND, RDL=0.050	ug/L	NC	20		
5186729	Total Tungsten (W)	2017/09/28	112	80 - 120	108	80 - 120	ND, RDL=1.0	ug/L	NC	20		
5186729	Total Uranium (U)	2017/09/28	106	80 - 120	102	80 - 120	ND, RDL=0.10	ug/L	7.8	20		
5186729	Total Vanadium (V)	2017/09/28	101	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L	0.15	20		
5186729	Total Zinc (Zn)	2017/09/28	105	80 - 120	102	80 - 120	ND, RDL=5.0	ug/L	NC	20		
5186729	Total Zirconium (Zr)	2017/09/28	106	80 - 120	95	80 - 120	ND, RDL=1.0	ug/L	NC	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Brad Newman, Scientific Service Specialist



Cristina Carriere, Scientific Service Specialist

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Draft



Maxxam Analytics International Corporation o/a Maxxam Analytics
 6740 Campbell Road, Mississauga, Ontario Canada L5N 2L8 Tel: (905) 817-5700 Toll-free 800-563-6266 Fax (905) 817-5777 www.maxxam.ca

CHAIN OF CUSTODY RECORD

INVOICE TO: Company Name: #24008 Cole Engineering Group Ltd Attention: Accounts Payable Address: 70 Valleywood Dr Markham ON L3R 4T5 Tel: (416) 987-6161 x Fax: (905) 940-2064 x Email: accountspayable@coleengineering.ca		REPORT TO: Company Name: Attention: Alireza Hejazi Address: Tel: (416) 987-6161 x243 Fax: Email: AHejazi@coleengineering.ca		PROJECT INFORMATION: Quotation #: B02064 P.O. #: Project: 2017-0293 Project Name: _____ Solmar/ Bolton Site #: Sampled By: AH, AG		Laboratory Use Only: Maxxam Job #: Bottle Order #: 529279 COC #: Project Manager: Jolanta Goralczyk Barcode: C#629279-01-01	
---	--	---	--	--	--	---	--

MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE MAXXAM DRINKING WATER CHAIN OF CUSTODY

Regulation 153 (2011) <input type="checkbox"/> Table 1 <input type="checkbox"/> Resi/Park <input type="checkbox"/> Medium/Fine <input type="checkbox"/> Table 2 <input type="checkbox"/> Ind/Comm <input type="checkbox"/> Coarse <input type="checkbox"/> Table 3 <input type="checkbox"/> Agri/Other <input type="checkbox"/> For RSC <input type="checkbox"/> Table _____		Other Regulations <input type="checkbox"/> CCME <input type="checkbox"/> Sanitary Sewer Bylaw <input type="checkbox"/> Reg 598 <input type="checkbox"/> Storm Sewer Bylaw <input type="checkbox"/> MISA Municipality _____ <input checked="" type="checkbox"/> PWQO <input type="checkbox"/> Other _____		Special Instructions	
---	--	--	--	-----------------------------	--

Include Criteria on Certificate of Analysis (Y/N)?

Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix	Field Filtered (please circle)	Metals (Up/Down)	PWQO Metals and Inorganics	Nitrate	Nitrite
1	MW1-17	22/09/17	12:45	GW	X	X	X	X	X
2	MW5-17s	↓	11:50	GW	X	X	X	X	X
3	MW3-17	↓	10:15	GW	X	X	X	X	X
4	MW4-17d	↓	10:50	GW	X	X	X	X	X
5									
6									
7									
8									
9									
10									

Turnaround Time (TAT) Required
 Please provide advance notice for rush projects

Regular (Standard) TAT:
 (will be applied if Rush TAT is not specified).
 Standard TAT = 5-7 Working days for most tests.
 Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details.

Job Specific Rush TAT (if applies to entire submission)
 Date Required: _____ Time Required: _____
 Rush Confirmation Number: _____ (call lab for #)

# of Bottles	Comments
	Temp 15.7°C, pH 7.98, Filtered
	Temp 14.7°C, pH 8.56, Filtered
	Temp 13.79°C, pH 8.17, Filtered
	Temp 13.15°C, pH 8.58, Filtered

22-Sep-17 14:25
 Jolanta Goralczyk
 B7K8760
 GKI ENV-1359

RELINQUISHED BY: (Signature/Print) Andrew O'Rourke Andrew O'Rourke		Date: (YY/MM/DD) Time 22/09/17 14:20		RECEIVED BY: (Signature/Print) Tanvika Tanvika		Date: (YY/MM/DD) Time 20/09/22 14:25		# jars used and not submitted		Laboratory Use Only	
								Time Sensitive		Temperature (°C) on Receipt 13/22/15	
								Custody Seal Present: Intact		Yes No <input checked="" type="checkbox"/> <input type="checkbox"/>	

* UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO MAXXAM'S STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.MAXXAM.CA/TERMS.

** IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.

*** SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT HTTP://MAXXAM.CA/WP-CONTENT/UPLOADS/ONTARIO-COC.PDF.

SAMPLES MUST BE KEPT COOL (< 10° C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM

White: Maxxa Yellow: Client

Appendix F

Well Records (WWIS)

WELL_ID	COMPLETED	DEPTH TO BEDROCK	DEPTH	STATIC_LEV	WELL_USE	FORMATION
4900205	1958-10-28	0.00	7.6	3.7	DO	BRWN LOAM 0012 GREY CLAY STNS 0023 GREY MSND 0025
4900209	1967-01-24	0.00	10.4	4.9	DO	BRWN LOAM 0012 GREY CLAY MSND STNS 0032 MSND GRVL 0034
4900211	1961-08-05	0.00	16.8	4.6	DO	BRWN LOAM 0016 GREY CLAY STNS 0054 GRVL 0055
4900249	1961-10-02	Bedrock	36.6	0.0		PRDG 0030 BLDR CLAY 0035 BLUE CLAY 0055 BLUE CLAY MSND GRVL 0080 BLUE CLAY 0087 SHLE 0120
4900250	1961-10-17	Bedrock	23.2	3.4	DO	BRWN CLAY 0025 MSND CLAY 0032 BLUE CLAY 0052 HPAN 0075 GRVL 0076
4900258	1963-05-08	Bedrock	35.1	0.0		LOAM 0001 BRWN CLAY 0018 BLUE CLAY 0079 BLUE SHLE 0115
4900259	1963-05-31	Bedrock	24.4	13.7	DO	BRWN LOAM 0015 GREY CLAY 0066 GREY SHLE 0080
4900260	1965-05-15	0.00	15.8	9.8	DO	BRWN LOAM 0018 GREY CLAY 0049 CSND GRVL 0052
4903285	1969-07-07	Bedrock	27.4	3.7	ST DO	LOAM 0001 CLAY MSND STNS 0025 BLUE CLAY 0055 BLUE CLAY STNS 0058 BLUE SHLE 0090
4903556	1970-09-18	Bedrock	30.5	0.0		FILL 0001 BRWN CLAY 0015 BLUE CLAY GRVL 0060 BLUE SHLE 0100
4903572	1970-09-28	Bedrock	45.7	0.0		PRDG 0055 BLUE SHLE 0150
4903573	1970-10-08	Bedrock	38.1	0.0		BRWN CLAY 0010 BLUE CLAY STNS 0055 BLUE GRVL MSND 0070 BLUE CLAY GRVL 0077 BLUE SHLE 0125
4903622	1971-03-15	Bedrock	27.7	0.0		BRWN LOAM 0001 BRWN STNS CLAY 0022 GREY CLAY MSND GRVL 0065 BLUE CLAY SHLE 0070 BLUE SHLE 0091
4903719	1971-11-05	0.00	17.7	7.6	DO	BRWN CLAY 0014 GREY CLAY 0057 GRVL 0058
4904113	1973-06-21	0.00	18.6	3.4	ST DO	BRWN CLAY STNS 0015 SAND CLAY 0017 BRWN CLAY 0050 SAND GRVL CLAY 0061


4904241	1973-09-25		0.00	66.1	0.0		BRWN CLAY 0016 BLUE CLAY 0112 GREY GRVL CLAY 0114 BLUE CLAY 0170 BLUE CLAY GRVL SILT 0205 BLUE SILT SAND 0217
4904566	1973-06-15	Bedrock		39.6	0.0		LOAM 0002 BLUE CLAY 0090 BLUE SHLE 0130
4905460	1978-09-15		0.00	9.8	7.6	DO	UNKN 0032
4905997	1982-09-01		0.00	15.8	3.0	DO	BLCK LOAM 0002 BRWN CLAY STNS 0017 BLUE CLAY STNS 0025 BLUE CLAY STNS SAND 0036 BLUE CLAY STNS 0045 BLUE CLAY CGVL 0048 BLUE CLAY STNS 0052
4906200	1984-05-11	Bedrock		16.5	3.7	DO ST	BLCK LOAM 0002 BRWN CLAY STNS 0015 GREY CLAY 0048 BRWN SAND GRVL 0053 BLUE SHLE 0054
4906309	1985-06-03		0.00	29.0	2.7	DO	BRWN SAND CLAY 0013 GREY SAND CLAY LYRD 0089 GREY SAND FSND SLTY 0094 GREY CLAY 0095
4906980	1988-11-20		0.00	18.9	6.1	DO	BRWN LOAM HARD 0001 BRWN CLAY HARD 0040 GREY CLAY LYRD PCKD 0062
4907464	1991-01-04	Bedrock		121.9	0.0	DO	BRWN CLAY 0040 GREY CGVL CMTD 0079 GREY FSND 0080 GREY CGVL CMTD 0092 GREY LMSN 0400
4907506	1991-02-01		0.00	0.0	2.4	DO	
4907515	1991-03-02		0.00	19.8	6.1	DO	BRWN LOAM HARD 0001 BRWN CLAY HARD 0030 GREY CLAY GRVL LYRD 0065
4907815	1993-09-03		0.00	18.3	3.0	DO	BRWN LOAM HARD 0001 BRWN CLAY HARD 0040 BRWN SAND LOOS 0060
4907950	1994-12-21	Bedrock		51.8	4.0	DO	BRWN CLAY STNS DNSE 0006 GREY CLAY STNS DNSE 0015 BLUE CLAY STNS DNSE 0059 BLUE SHLE HARD 0120 BLUE SHLE HARD 0170

4910381	2006-10-31	0.00	11.9	0.0		BRWN LOAM 0001 BRWN SILT TILL 0015 GREY SILT TILL 0020 GREY SILT TILL 0035 GREY SILT 0039
4910384	2006-11-06	0.00	53.3	0.0		BRWN LOAM 0001 BRWN SILT TILL 0010 GREY SILT TILL 0175
7210516	2013-10-11	0.00	6.1	0.0	MO	BRWN CLAY SAND PCKD 0005 GREY CLAY SAND SILT 0020
7224983	2014-06-09	0.00	7.6	0.0	MO	BRWN CLAY SILT LOOS 0015 GREY SILT CLAY PCKD 0025
7224993	2014-06-09	0.00	6.1	0.0	MO	BRWN CLAY SILT LOOS 0015 GREY SILT CLAY PCKD 0020
7224994	2014-06-09	0.00	7.6	0.0	MO	BRWN CLAY SILT LOOS 0015 GREY SILT CLAY PCKD 0025
7224997	2014-06-09	0.00	7.6	0.0	MO	BRWN CLAY SILT LOOS 0015 GREY SILT CLAY PCKD 0025
7224999	2014-06-09	0.00	6.1	0.0	MO	BRWN CLAY SILT LOOS 0015 GREY SILT CLAY PCKD 0020
7243117	2015-05-29	0.00	0.0	0.0		
7245005	2015-07-16	0.00	0.0	0.0		
7245006	2015-07-06	0.00	0.0	0.0		
7280866	2016-12-13	0.00	0.0	3.7		
7303451	2017-08-17	0.00	6.1	0.0	MO TH	BRWN SILT CLAY 0011 GREY SILT CLAY 0020
7306838	2017-08-16	0.00	0.0	0.0		
7306839	2017-08-16	0.00	0.0	0.0		
7306854	2017-08-18	0.00	0.0	0.0		
7326539	2018-12-07	0.00	0.0	0.0		
7328991	2018-04-05	0.00	0.0	0.0		
7355972	2019-04-02	0.00	6.1	0.0	TH	BRWN SILT CLAY 0012 GREY SILT CLAY 0020

Appendix G

Natural Heritage Features

(GEI 2022)



ELC Legend

CUM1-1	Dry Moist Old Field Meadow
CUP	Coniferous Plantation
CUT	Cultural Thicket
CUT1-1	Sumac Cultural Thicket
CUT1-7*	Buckthorn Cultural Thicket
FOD	Deciduous Forest
FOD8-3*	Fresh-Moist Basswood Deciduous Forest
MAM2	Mineral Meadow Marsh
MAM2-2	Reed-canary Grass Mineral Meadow Marsh
MAM2-10	Forb Mineral Meadow Marsh
MAM2-11*	Mixed Mineral Meadow Marsh
MAS2	Mineral Shallow Marsh
MAS (Phragmites)	Common Reed Mineral Shallow Marsh
MAS2-1	Cattail Mineral Shallow Marsh
SAS1-1	Pondweed Submerged Shallow Aquatic
SWD3-4	Manitoba Maple Mineral Deciduous

AG	Agricultural
DIST	Disturbed
Lawn	Lawn
Pond	Pond
RES	Residential

*Not included in Southern Ontario ELC Field Guide.

- Study Area
- Watercourse (Suitable for Realignment)
- Watercourse (Suitable for Realignment Non-participating Owner)
- Ecological Land Classification
- Creek Bank (Staked on October 19, 2021 by TRCA and GEI)
- Dripline (Staked on October 19, 2021 by TRCA and GEI)
- Hydrologic Edge of Wetland (Staked on October 19, 2021 by TRCA and GEI)
- Top of Bank (Staked on October 19, 2021 by TRCA and GEI)
- Wetland (Staked on October 19, 2021 by TRCA and GEI)
- Proposed Watercourse Realignment Route
- Estimated Top of Bank (GEI, 2022)
- Natural Heritage Features Limit
- Wetland Not Evaluated Per OWES
- Proposed Route for Highway 413

**PRELIMINARY DRAFT
FOR INTERNAL
DISCUSSION**

Humber Station Village, Town of Caledon ON

Figure 6
Natural Heritage Features

0 100 Meters




Appendix H

TRSPA Water Balance Results

A WATER BALANCE TOOL

Water Balance Tool [Guidance Document](#)



Precipitation (mm/yr)

863

Evapotranspiration

575

Runoff (mm/yr)

234

Recharge (mm/yr)

53.92