



TOWN OF CALEDON
PLANNING
RECEIVED

Feb.26, 2021

Proposed Warehouse Development

FINAL

Preliminary Hydrogeological Assessment

Project Location:

12892 Dixie Road, Caledon, Ontario

Prepared for:


Tribal Partners (Canada) Inc.
201-2700 Steeles Avenue West
Vaughan, ON

Prepared by:

MTE Consultants
123 St. George St.,
London, ON

February 23, 2021

MTE File No.: 48043-300





Contents

1.0	Introduction	1
1.1	Study Objectives	1
2.0	Background Review.....	1
2.1	Previous Investigations	1
2.2	Terrain	2
2.2.1	Topography and Drainage	2
2.2.2	Physiography	2
2.3	Regional Geology	2
2.3.1	Overburden.....	2
2.3.2	Bedrock	3
2.4	Regional Hydrogeology.....	3
2.4.1	Water Well Information System.....	3
2.4.2	Permit to Take Water Database	3
2.4.3	Source Protection	3
2.5	Natural Heritage Features	4
3.0	Field Investigation	4
3.1	Drilling Program	4
3.2	Monitoring Wells	5
3.3	Staff Gauges.....	5
3.4	Elevation Survey	5
3.5	Hydraulic Conductivity Testing	6
3.6	Monitoring Program	6
4.0	Hydrostratigraphy	6
4.1	Stratigraphy	6
4.2	Groundwater Elevations.....	7
4.3	Groundwater and Surface Water Quality.....	8
5.0	Water Balance.....	8
5.1	Methodology	9
5.1.1	Catchment Areas	9
5.1.2	Precipitation.....	9
5.1.3	Evapotranspiration	9
5.2	Results.....	10
5.3	Next Steps	10
6.0	Dewatering Review.....	10

6.1	Temporary Construction Dewatering.....	11
6.1.1	Services.....	11
6.1.2	Foundations.....	11
6.1.3	Stormwater Management Areas.....	11
6.2	Dewatering Permitting Requirements.....	11
7.0	Preliminary Impact Assessment.....	12
7.1	Inventory of Groundwater Receptors.....	12
7.1.1	Water Supply Wells.....	12
7.1.2	Watercourses.....	12
7.1.3	Wetlands.....	12
7.2	Potential Groundwater Impacts during Construction	13
7.2.1	Temporary Construction Dewatering.....	13
7.2.2	Spills.....	13
7.2.3	Water Supply Wells.....	13
7.2.4	Soil Compaction.....	14
7.3	Potential Post-Development Groundwater Impacts	14
7.3.1	Infiltration and Runoff.....	14
7.3.2	Groundwater Recharge.....	15
7.3.3	Water Supply Wells.....	15
7.3.4	Watercourses and Wetlands	15
8.0	Conclusions.....	15
9.0	Recommendations.....	16
10.0	Limitations	17
11.0	References.....	19

Figures

Figure 1 – Site Location

Figure 2 – Quaternary Geology

Figure 3 – Water Wells

Figure 4 – Location Plan

Figure 5 – Cross Section A-A'

Figure 6 – Cross Section B-B'

Figure 7 – Cross Section C-C'

Figure 8 – Groundwater Flow in Confined Sands

Figure 9 – Pre-Development Catchments

Figure 10 – Post-Development Catchments

Tables

Within the Text of the Report

Table 4.1 – Particle Size Distribution Results for Glacial Till

Table 4.2 – Particle Size Distribution Results for Granular Deposits

Table 5.1 – Water Balance Summary

Following the Text of the Report

Table 1 – Summary of MECP Water Well Records

Table 2 – Summary of Single Well Response Tests

Table 3 – Summary of Manually Measured Groundwater Levels

Table 4 – Analytical Results for RCAP Comprehensive in Groundwater and Surface Water

Appendices

Appendix A – Concept Plan

Appendix B – Borehole Logs

Appendix C – Particle Size Distributions

Appendix D – Single Well Response Tests

Appendix E – Hydrographs

Appendix F – Certificate of Analysis

Appendix G – Water Balance

Appendix H – Natural Environment Plans

1.0 Introduction

MTE Consultants Inc. (MTE) was retained by Tribal Partners (Canada) Inc. (Tribal) to carry out a preliminary hydrogeological assessment to support the proposed development of 12892 Dixie Road in Caledon, Ontario (hereinafter referred to as the “Site”). The approximate location of the Site is shown on **Figure 1**.

The Site is approximately 78.9 hectares (~195 acres) in area and is located on the west side of Dixie Road and the south side of Old School Road in an agricultural area of Caledon, Ontario. The Site is currently agricultural cropland with rural residences and associated outbuildings.

Based on the Concept Plan prepared by Baldassarra Architects Inc., the Site will be developed as an industrial warehousing complex consisting of four slab on-grade buildings with associated at-grade parking and stormwater management facilities. A copy of the Concept Plan is provided in **Appendix A**.

1.1 Study Objectives

The objectives of the preliminary hydrogeological assessment were to:

- Summarize the local hydrogeological conditions;
- Provide hydrogeological input to the Site design;
- Provide a qualitative assessment of the dewatering and permitting requirements;
- Identify groundwater receptors and assess the potential for hydrogeological impacts on these receptors as a result of the proposed development; and
- Provide recommendations for additional work, groundwater monitoring and/or mitigation, as required.

2.0 Background Review

The following sections present the results of the background information review and describe the Site setting in a regional context.

2.1 Previous Investigations

A Phase I environmental investigation was completed by MTE (report dated September 30, 2020). The Phase I recommended that a Phase II ESA be completed, which was undertaken concurrently with this investigation. The results of the Phase II ESA were provided under separate cover.

No other previous hydrogeological, geotechnical, environmental or natural heritage reports are known to have been previously completed for the Site.

To support the design of the proposed development, a concurrent geotechnical investigation was also completed by MTE.

Although the results of the concurrent geotechnical and Phase II ESA investigations are provided under separate cover, relevant subsurface information has been reviewed and incorporated into the hydrogeological assessment, where appropriate.

In addition, the following additional studies have been undertaken concurrently by WSP to support the proposed development and may be relevant to the hydrogeological assessment:

- Comprehensive Environmental Impact Study and Management Plan (CEISMP);
- Stormwater Management Report; and
- Functional Servicing Report.

2.2 Terrain

2.2.1 Topography and Drainage

Based on a Plan of Survey prepared by R. Avis Surveying Inc., the Site topography slopes gently downwards to the east and north, with ground surface elevations ranging from a topographic high elevation of approximately 272.2 m above mean sea level (AMSL) in the west near Old School Road to a topographic low of approximately 259.8 m AMSL within the meander belt of Kilamanagh Creek in the southern portion of the Site.

Kilamanagh Creek is a tributary of the West Humber River. The tributary enters the Site from the south before turning east and flowing off-Site. The approximate length (ignoring sinuosity) of the on-Site reach of the tributary is 220 m.

In the northwest of the Site, another tributary of the West Humber River (Tributary 5) enters the Site through a culvert beneath Old School Road, flows southeast for approximately 410 m before turning east and leaving the Site through a culvert beneath Dixie Road.

There are three other tributaries of the West Humber, designated Tributaries 2, 3 and 4, that originate on the Site: two within the woodland and one south of the farm buildings.

2.2.2 Physiography

The landforms within the region are primarily the result of the movement and deposition of sediments as a result of glacial advancement and recession during the most recent periods of glaciation. The Site is located within the broad physiographic region known as the South Slope (Chapman & Putnam, 1984). This region is a sloping till plain that extends from the Oak Ridges Moraine located approximately 8 kilometers (km) northwest of the Site to the Peel Plain, located approximately 4 km to the east.

2.3 Regional Geology

2.3.1 Overburden

The Quaternary deposits in the region of the Site are mapped as a predominantly clay to silt textured till derived from glaciolacustrine deposits (Ontario Geological Survey, 2003). Along the northeastern boundary of the Site, modern alluvial deposits consisting of clay, silt, sand and gravel can also be found (Ontario Geological Survey, 2003). The Quaternary geology in the vicinity of the Site is shown on **Figure 2**.

2.3.2 Bedrock

Bedrock topography mapping suggests the elevation of the bedrock surface in the vicinity of the Site ranges from approximately 236 m AMSL in the north to 244 m AMSL in the south (Ontario Department of Mines, 1968). The bedrock consists of Upper Ordovician shales and siltstones of the Queenston Formation (Fm) (Armstrong & Dodge, 2007). The Queenston Formation is characterized by red shale; however, it also contains red siltstone, minor green shale and siltstone, with variable calcareous siltstone to sandstone and limestone interbeds (Johnson, Armstrong, Sanford, Telford, & Rutka, 1992). The Queenston Formation gradationally overlies the Georgian Bay Formation and the Carlsbad Formation in eastern Ontario (Armstrong & Dodge, 2007).

2.4 Regional Hydrogeology

2.4.1 Water Well Information System

The MECP Water Well Information System (WWIS) was queried for data pertaining to all wells located within an approximate 500 m radius of the Site and resulted in data for 39 wells. The well records corresponded to the following:

- Seventeen records were for wells reportedly used as a water supply;
 - a. These wells were primarily completed within deep confined overburden or bedrock aquifers;
 - b. These records included six large diameter bored or dug wells completed at intermediate depths within the glacial till that are anticipated to have low yields and rely on interbedded granular deposits as their source;
- Eleven records were reported to be used as monitoring, test hole or observation wells;
- Six records were for wells reported to have been abandoned; and
- Five records did not include information on well status or use.

The approximate locations of these wells, as indicated in the MECP well records, are shown on **Figure 3**. Pertinent information from these well records is summarized in **Table 1**.

2.4.2 Permit to Take Water Database

The MECP Permit to Take Water (PTTW) database contained only one inactive permit that was issued for a surface water taking approximately 200 m South of the Site. The record was active from 1973 to 1978 for a daily water taking of 412, 413 litres per day (L/day) from the West Humber River for agricultural purposes (Ministry of the Environment, Conservation and Parks, 2021).

2.4.3 Source Protection

The Source Protection Information Atlas (Ministry of Environment, Conservation and Parks, 2021) was used to confirm that the Site is not within:

- an Intake Protection Zone (IPZ);
- a Wellhead Protection Area (WHPA);

- a Highly Vulnerable Aquifer (HVA); or
- a Significant Groundwater Recharge Area (SGRA).

2.5 Natural Heritage Features

No Environmentally Significant Areas (ESAs) (Region of Peel, 2008) or Areas of Natural and Science Interest (ANSIs) were identified within 500 m of the Site (Land Information Ontario, 2020). A Provincially Significant Wetland (PSW), associated with the Heart Lake Wetland Complex swamp, is located approximately 495 m southeast of the Site (Land Information Ontario, 2020).

The CEISMP identified the following local natural heritage features in the vicinity of the Site:

- A woodland located in the central portion of the Site;
- Kilamanagh Creek (designated as coldwater) and associated riparian area in the southwest portion of the Site;
- Four other tributaries of the West Branch of the Humber River;
 - a. Tributaries 2 and 3 are intermittent/ephemeral in nature and convey flows through the woodland to an online pond, prior to being conveyed off-property under Dixie Road;
 - b. Tributary 4 and associated riparian wetland, originating south of the farm buildings, conveying flows through an adjacent residential property before being conveyed under Dixie Road to the east; and
 - c. Tributary 5 and associated riparian wetland, originating north of Old School Road, flowing southeast through the Site before being conveyed under Dixie Road to the east.

The approximate locations of the above natural heritage features are shown on Figures 1 and 2 in **Appendix G**. For detailed information on these features, reference should be made to the CEISMP (WSP, 2021).

No groundwater dependent plant species were identified on-Site during the fieldwork completed for the CEISMP (WSP, 2021).

3.0 Field Investigation

3.1 Drilling Program

The drilling program for the concurrent geotechnical investigation was carried out between October 12 and October 30, 2020. Forty-one boreholes, designated BH101-20 to BH141-20, were drilled at the approximate locations shown on **Figure 4**. The boreholes were advanced with a CME 75 track-mounted drill rig equipped with continuous flight hollow stem augers. The drill rig was supplied and operated by Tri-Phase Group under the supervision of MTE. The stratigraphy encountered in the boreholes is shown on the borehole logs provided in **Appendix B**. Particle size distribution curves for representative soil samples are provided in **Appendix C**.

3.2 Monitoring Wells

Upon completion of drilling, monitoring wells were installed in seven boreholes and designated MW101-20 to MW107-20. The remaining boreholes were backfilled in general accordance with Ontario Regulation (O.Reg.) 903, as amended, under the Ontario Water Resources Act.

Monitoring wells MW102-20 to MW104-20, MW106-20 and MW107-20 were screened within the saturated granular deposits interbedded within the glacial till. MW101-20 and 105-20 were screened within the glacial till deposits. Each of the monitoring wells were constructed with 0.9 to 1.5-metre long, nominal 50 mm inside diameter (ID), slot 10, Schedule 40 polyvinyl chloride (PVC) well screens threaded to PVC riser pipes. A sand pack consisting of commercially available silica sand was used to backfill the borehole annulus surrounding the well screen. The annulus above the sand pack was backfilled with bentonite to near ground surface and hydrated in place. The monitoring wells were secured with monument-style protective casings cemented in place.

Following their construction, the monitoring wells were mechanically developed using a hydrolift pump and dedicated low density polyethylene (LDPE) tubing equipped with an inertial foot valve and surge block. The monitoring wells were purged of a minimum of three standing well volumes or until dry three times.

Details of the monitoring well construction and encountered groundwater levels are provided on the borehole logs in **Appendix B**. The approximate locations of the monitoring wells are shown on **Figure 4**.

The monitoring wells were installed in general accordance with O.Reg. 903, as amended. The construction, maintenance and abandonment of the wells are regulated under the Ontario Water Resources Act (OWRA).

3.3 Staff Gauges

On November 19, 2020 two staff gauges, designated SG1 and SG2, were installed within the on-Site watercourses in order to monitor stage and assess groundwater and surface water interactions. The staff gauge locations are shown in **Figure 4**.

A third staff gauge was proposed to be installed within a watercourse reportedly flowing through the wooded area and discharging into a dugout pond. A dry swale was observed during the site visit. Three corrugated steel pipes were observed to outlet from the agricultural field at the “headwaters” of the swale, but were not discharging at that time. The outlet of these steel pipes leading from the farm field suggests some form of field drainage system is present and that the watercourse within the wooded area is ephemeral.

3.4 Elevation Survey

The ground surface elevations at the borehole locations, top of pipe elevations for the monitoring wells, and top of steel elevations for the staff gauges were surveyed by MTE and referenced to geodetic datum.

3.5 Hydraulic Conductivity Testing

Single well response tests were conducted in monitoring wells MW101-20, MW103-20, MW106-20 and MW107-20 to estimate the hydraulic conductivity of the saturated granular deposits confined beneath the glacial till deposits at the Site and to confirm the hydraulic conductivity of the glacial till. Prior to initiating the tests, each monitoring well was instrumented with a pressure transducer equipped with a datalogger to measure water levels at a suitable frequency during the tests.

The water level dataset collected during the single well response tests was analyzed using the AquiferTest Pro software package. Hydraulic conductivity (K) values for each test were estimated using the Hvorslev analytical solution (Hvorslev, 1951). The results of the single well response tests are provided in **Appendix D** and summarized in **Table 2**.

The results of the hydraulic testing analyses indicate that the estimated K values for the confined granular deposits range between approximately 2×10^{-5} and 7×10^{-7} m per second (m/s), with a geometric mean of approximately 3×10^{-6} m/s ($n = 7$). The K values estimated from the single well response tests are consistent with the range of hydraulic conductivity values reported by Freeze and Cherry (1979) for silt, silty sand, and sand deposits.

In comparison, the results of the single well response testing on MW101-20 estimate a hydraulic conductivity of 8×10^{-8} m/s ($n = 2$) for the glacial till deposits.

3.6 Monitoring Program

Pressure transducers equipped with dataloggers were installed in six monitoring wells (MW101-20 to MW103-20 and MW105-20 to MW107-20). The dataloggers were configured to record water levels at one hour intervals and the data downloaded on a quarterly basis. The transducer readings were compensated for changes in atmospheric pressure using data collected by a barometric pressure transducer installed at the Site for the duration of the monitoring period. During the compensation process, level offsets using corresponding manual water level measurements collected at the time of download were applied to the data to convert the water levels to geodetic elevations. Hydrographs of the compensated groundwater elevations are provided in **Appendix E**.

Groundwater and surface water levels were manually measured in all seven monitoring wells and at the two staff gauge locations during each quarterly monitoring event. The results obtained over the period of record (November to December 2020) are summarized in **Table 3**.

Quarterly download of the dataloggers and manual measurement of groundwater and surface water levels will continue until September 2021, at which time the continuation of the groundwater monitoring will be reassessed.

4.0 Hydrostratigraphy

4.1 Stratigraphy

In general, the stratigraphic conditions encountered in the boreholes typically consisted of topsoil and/or surficial fill materials overlying glacial till deposits. The till ranged in composition from sandy silt to clayey silt. Cobbles and/or boulders should be anticipated in glacial till deposits. **Table 4.1** summarizes the variability in the particle size composition within the glacial tills.

Table 4.1 – Particle Size Distribution Results for Glacial Till

Borehole ID	Sample Depth (m)	Gravel (%)	Sand (%)	Silt (%)	Clay (%)
MW101-20	9.1 – 9.8	6	40	41	13
MW103-20	6.1 – 6.7	1	26	66	7
MW105-20	4.6 – 5.0	1	28	43	28
BH116-20	3.0 – 3.7	7	25	40	28

Granular deposits were interbedded within the glacial till and ranged in composition from silt to silty sand to gravelly sand to sand and gravel. **Table 4.2** summarizes the variability in the particle size composition within the granular deposits.

Table 4.2 – Particle Size Distribution Results for Granular Deposits

Borehole ID	Sample Depth (m)	Gravel (%)	Sand (%)	Silt (%)	Clay (%)
MW104-20	9.9 – 10.5	1	70	22	7
MW106-20	10.7– 11.3	1	9	78	12
MW107-20	9.9 – 10.5	8	44	35	15

The till deposits are considered an aquitard ($K \sim 8 \times 10^{-8}$ m/s) and act as a confining layer for the saturated granular deposits ($K \sim 3 \times 10^{-6}$ m/s). These granular deposits were encountered at elevations ranging from approximately 264.5 to 255.1 m AMSL, corresponding to depths ranging from 3.0 to 11.1 m BGS and, where fully penetrated, were approximately 0.3 to 2.0 m in thickness.

The simplified stratigraphy inferred from the boreholes is shown on the cross-sections provided on **Figure 5**, **Figure 6** and **Figure 7**.

4.2 Groundwater Elevations

The encountered groundwater levels are shown on the borehole logs in **Appendix B** and manually measured groundwater levels are summarized in **Table 3**. Hydrographs of the compensated groundwater elevations are provided in **Appendix E**.

The measured groundwater elevations within the confined granular deposits have ranged from a maximum of 262.56 m AMSL to a minimum of 257.30 m AMSL over the monitoring period to date (November to December 2020). The hydrographs show a muted response following significant precipitation events, remaining relatively consistent over the period of record.

The groundwater elevations at MW106-20 and MW107-20 are noted to be above the top of the aquifer indicating artesian conditions.

It is noted that the monitoring period to date has coincided with a period when regional groundwater levels in southern Ontario are typically increasing as they rise towards their seasonally high levels in the late winter or early spring and then begin to decline towards their

seasonally low levels, which generally occur in late summer or early fall. For the purposes of design, groundwater elevations potentially one metre higher should be anticipated during the period of seasonally high groundwater levels following the spring freshet. Groundwater monitoring at the Site is currently scheduled to continue until September 2021. The amplitude of the seasonal variation will be further assessed following completion of the proposed monitoring period.

Because MW101-20 and MW105-20 were constructed with their well screens within the low permeability glacial till deposits, caution should be used when interpreting their groundwater level measurements. In general, groundwater level measurements within an aquitard should be limited to assessing vertical gradients within or between strata.

Figure 8 shows the inferred potentiometric surface and flow direction across the Site for December 2020. The results indicate that the groundwater flow direction is generally towards the east, with observed gradients (i.e., slope) of 0.004 to 0.006 m/m over the Site.

Groundwater conditions may subsequently differ from those described herein due to seasonal and inter-annual variations in groundwater levels and in response to significant precipitation events. The groundwater conditions at the time of construction should be confirmed by the contractor and their work plan modified as appropriate.

4.3 Groundwater and Surface Water Quality

Groundwater was sampled from two representative monitoring wells (MW106-20 and MW107-20) on November 23, 2020. The samples were collected using dedicated inertial pumps and low-density polyethylene tubing. Prior to sampling, the wells were purged of a minimum of three equivalent well volumes of groundwater or purged dry three consecutive times.

A surface water sample was also collected from each of the two tributaries in the vicinity of their corresponding staff gauge (SG1 and SG2).

The samples were collected into the appropriate bottles supplied by the analytical laboratory with the applicable preservatives added by the laboratory. Upon collection, the water samples were placed on ice in coolers and submitted under chain of custody to the Bureau Veritas Laboratories (BV Labs) depot in London, Ontario for analysis at their Mississauga laboratory.

No sheen, odours, free product or other evidence of potential environmental contamination were observed in the samples collected at these locations.

The samples were analyzed for a suite of general water quality parameters to establish a water quality baseline prior to development and assess groundwater-surface water interactions. The analytical results were compared to the Provincial Water Quality Objectives (PWQO) and there were no reported exceedances. The results are summarized in **Table 4** and a copy of the laboratory Certificate of Analysis is provided in **Appendix F**.

5.0 Water Balance

Water balances for the pre- and post-development conditions were completed for the Site to assess potential impacts of the proposed development on infiltration.

5.1 Methodology

Following the Thornthwaite and Mather (1957) approach, the annualized water balance for the Site may be expressed as:

$$P = RO + ET + I + \Delta S$$

Where:

P	= precipitation
RO	= runoff
ET	= evapotranspiration
I	= infiltration
ΔS	= change in groundwater storage (assumed to be negligible over long term)

The difference between precipitation and evapotranspiration is the water surplus (WS) available for infiltration (I) and runoff (RO).

$$WS = P - ET$$

The water surplus is used to estimate infiltration by applying an infiltration factor (IF).

$$I = WS \times IF$$

This infiltration factor (IF) is estimated based on topography, soil type and ground cover, as described in the MECP Stormwater Management Planning and Design Manual (Ministry of the Environment, 2003).

And finally, runoff (RO) is estimated from:

$$RO = WS - I$$

The following sections provide a summary of the on-Site catchments and input parameters for the water balance equation.

5.1.1 Catchment Areas

Details of the catchments for the pre- and post-development conditions are described in the *Stormwater Management Report* (WSP, 2021b).

The pre- and post-development catchments are shown on **Figure 9** and **Figure 10**, respectively, which include details on the total area of each catchment and the percentage of impervious area within the catchment.

5.1.2 Precipitation

The average annual precipitation measured at the Toronto Lester B. Pearson International Airport Climate Station (Climate ID 6158733) for the period from 1981 to 2010 was 786 millimetres per year (mm/yr) (Environment Canada, 2021).

5.1.3 Evapotranspiration

The average annual evapotranspiration rates were determined using the MECP Stormwater Management Planning and Design Manual (Ministry of the Environment, 2003), which provides

a range of evapotranspiration values depending on ground and vegetative cover and the hydrologic soil group.

5.2 Results

The results of the water balance for the Site are summarized below in **Table 5.1** and a copy of the water balance worksheet is provided in **Appendix G**.

Table 5.1 – Water Balance Summary

Parameter	Pre-Development [m ³ /year]	Post-Development (Unmitigated) [m ³ /year]	Difference [m ³ /year]	% Change [%]
Precipitation (P)	619,800	619,800	0	0
Evapotranspiration (ET)	352,300	136,500	-215,800	-61
Infiltration (I)	137,200	36,500	-100,700	-73
Runoff (RO)	130,400	446,800	316,400	243

NOTES:

1. Negative value indicates a decrease following development.

The proposed development is anticipated to increase the impervious surface area of the Site from effectively nil under the existing conditions to approximately 76% following development. This is anticipated to result in an estimated decrease in infiltration of approximately 73% and increase in runoff of approximately 243%. Mitigation strategies are discussed in Section 7.3.1.

5.3 Next Steps

As part of the detailed design and in consultation with the Toronto Region Conservation Authority (TRCA), feature-based water balances will be completed for sensitive ecological features identified as runoff dependent. Where feasible, the feature-based water balances should use site-specific data and include scenarios for pre-development, unmitigated post-development and mitigated post-development.

6.0 Dewatering Review

The following sections provide a qualitative discussion of the potential dewatering and permitting requirements for the project.

Design details for site servicing, foundations and stormwater management facilities were not available at the time of this review. Once available, MTE should be requested to review the design and complete a quantitative dewatering assessment to confirm the findings described herein.

6.1 Temporary Construction Dewatering

6.1.1 Services

The proposed development will be municipally serviced with piped water supply, storm and sanitary sewers. Inverts for the watermain and sewers are assumed to be at conventional depths of up to approximately 3 m BGS.

Although proactive construction dewatering is not anticipated to be required, saturated granular deposits were encountered as interbeds within the glacial till at variable depths and locations. Should excavations encounter these saturated granular deposits, temporary construction dewatering may be required to control groundwater inflow from these deposits.

Nuisance dewatering of groundwater seepage will be required where trench excavations for the services encounter sand/silt seams within the glacial till. Groundwater seepage from these sand/silt seams should be adequately handled by pumping from properly constructed sumps.

6.1.2 Foundations

It is understood that the floor slab for the four proposed warehouse buildings (Buildings A, B, C and D) will be constructed using conventional concrete slab-on-grade techniques with footing depths of approximately 1.4 m BGS. The approximate locations of the buildings are shown on **Figure 10**.

Given the shallow foundations used for slab-on-grade buildings, construction dewatering is not anticipated to be required for their excavation.

6.1.3 Stormwater Management Areas

The proposed development plan includes four Stormwater Management (SWM) facilities (SWM Areas A, B, C and D). The approximate locations of these areas are shown on **Figure 10**.

Although proactive construction dewatering is not anticipated to be required, saturated granular deposits were encountered as interbeds within the glacial till at variable depths and locations. Should excavations encounter these saturated granular deposits, temporary construction dewatering may be required to control groundwater inflow from these deposits.

Nuisance dewatering of groundwater seepage will be required where excavations for the stormwater management facilities encounter sand/silt seams within the glacial till. Groundwater seepage from these sand/silt seams should be adequately handled by pumping from properly constructed sumps.

6.2 Dewatering Permitting Requirements

Based on the encountered subsurface conditions, it is our opinion that with appropriate staging and scheduling considerations, the daily water taking volumes for nuisance dewatering within open excavations should be less than the threshold of 50,000 litres per day (L/day) above which a water taking permit is required. However, should excavations encounter the saturated granular deposits interbedded within the glacial till, the daily water taking volumes may exceed 50,000 L/day and an Environmental Activity Sector Registration (EASR) would be required.

An EASR is required for temporary construction dewatering with daily pumping volumes greater than 50,000 L/day, but less than 400,000 L/day. This is an online registration supported by Water Taking and Discharge Plans prepared by a Qualified Professional (QP). At least two weeks should be allowed in the project schedule to prepare the supporting documents and complete the online registration.

As a precaution, it is recommended that an EASR be obtained to avoid potential delays should these interbedded saturated granular deposits be encountered during excavation. Obtaining an EASR also has the benefit of maintaining staging and scheduling flexibility should large areas or multiple excavations require concurrent nuisance dewatering.

7.0 Preliminary Impact Assessment

7.1 Inventory of Groundwater Receptors

7.1.1 Water Supply Wells

Based on the MECF WWRs, water supply wells within 500 metres of the Site are primarily completed within deep confined overburden or bedrock aquifers. However, six large diameter bored or dug wells completed at intermediate depths within the glacial till were identified. These wells are anticipated to have low yields and rely on sand/silt seams and/or interbedded granular deposits as their source. The approximate locations of the water supply wells, as provided in the WWRs, are shown on **Figure 4**.

7.1.2 Watercourses

Five watercourses were identified on-Site:

- Two permanent tributaries of the West Humber River;
- One intermittent/ephemeral watercourse originating south of the farm buildings; and
- Two intermittent/ephemeral watercourses located within the central woodland and discharging to an on-line pond.

The approximate locations of these watercourses are shown on Figure 1 (WSP, 2021) in **Appendix G**.

Given the low permeability of the shallow sediments, as well as the observed separation between the channel beds and groundwater levels at the Site, groundwater is not anticipated to contribute to flow within these watercourses in the vicinity of the Site.

7.1.3 Wetlands

As discussed in Section 0, the CEISMP identified wetland communities (Reed Canary Grass Mineral Meadow Marsh) along the riparian zones of Tributaries 4 and 5 of the West Humber River and Kilamanagh Creek. The approximate locations of these wetland communities are shown on Figure 2 (WSP, 2021) in **Appendix G**.

Based on the low permeability of the encountered glacial till and apparent separation from groundwater, the hydraulic functions of the identified wetland communities are not considered to

be dependent on groundwater. It is anticipated that the hydrologic function of these wetlands is primarily supported by runoff.

7.2 Potential Groundwater Impacts during Construction

7.2.1 Temporary Construction Dewatering

It is anticipated that only nuisance dewatering of groundwater seepage from sand/silt seams within the glacial till will be required during construction. The nuisance dewatering would be completed using sumps and pumps is not anticipated to have a significant impact on nearby groundwater receptors.

In the event that construction dewatering is required to control groundwater inflow into excavations from saturated granular deposits, the low yield large diameter water supply wells located within approximately 250 metres of the Site may be susceptible to well interference during temporary construction dewatering. The potential impact on these water supply wells would be further assessed during preparation of the supporting documentation for an EASR.

Given that the identified watercourses and wetland community are not considered to be dependent on groundwater, no impacts to these natural heritage features are anticipated as a result of temporary construction dewatering.

No other groundwater related impacts are anticipated should construction dewatering be required.

7.2.2 Spills

The proposed construction will require the use of heavy machinery and equipment and, as such, there is some potential for associated petroleum hydrocarbons, such as fuel or lubricants, to impact the shallow groundwater.

These risks are readily minimized by:

- implementing Best Management Practices (BMPs) for all refueling, fuel and lubricant storage and equipment maintenance activities;
- prohibiting refueling and maintenance activities within 30 m of any waterbody, if any; and
- implementing a spill contingency plan during construction.

With the above control measures in place, the residual risk of spills potentially impacting shallow groundwater is considered to be very low.

7.2.3 Water Supply Wells

Since proactive construction dewatering is not anticipated to be required, potential impacts to water supply wells in the vicinity of the Site are anticipated to be limited to spills and vibrations from heavy construction equipment. As discussed in Section 7.2.2, the risks from spills is minimized by implementing BMPs for refueling and maintenance activities. Vibrations from heavy construction equipment may disturb existing accumulated sediment in the bottom of the well casing and/or scale from the walls of the casing temporarily resulting in an increase in Total Suspended Solids (TSS). Poorly maintained water supply wells are generally more susceptible.

A door to door well inventory should be completed to confirm the locations and installation depths of water supply wells in the immediate vicinity of the Site. A request should also be submitted to the Municipality to confirm properties that are on a piped municipal water supply.

Following completion of the door to door well inventory, a monitoring and contingency plan would be recommended for wells susceptible to interference during construction.

7.2.4 Soil Compaction

Compaction of soils by heavy machinery traffic during construction may reduce the infiltration capacity of surficial soils. These impacts may be mitigated, at least partially, by implementing a best practices Soil Management Plan (SMP) during clearing, grading and construction with the goal to preserve or restore the pre-development infiltration capacity of the native soils and subsoils in areas that will remain pervious following development. The SMP may include:

- Allowing the proposed pervious areas to remain undisturbed, to the extent possible, and protecting them from compaction during construction; and/or
- Restoration of compacted subsoils following construction using a combination of de-compaction treatments (e.g. ripping, scarification, tilling) and application of organic soil amendments to increase the organic matter content.

7.3 Potential Post-Development Groundwater Impacts

7.3.1 Infiltration and Runoff

Following development, the increase in the impervious surface area at the Site is anticipated to decrease infiltration and increase runoff relative to the existing conditions.

Appropriate low impact development (LID) measures may mitigate the anticipated decrease in post-development infiltration. Subject to site limitations, specific mitigation measures may include:

- Reduction of the amount of impervious surface area, where feasible;
- Storage of precipitation for subsequent use to satisfy landscape irrigation requirements;
- Topsoil thickening to provide additional storage;
- Promote diffused infiltration of stormwater so that, where feasible, runoff from impervious surfaces sheet flows over adjacent pervious surfaces that are managed to optimize infiltration capacity;
- Construction of bioretention cells and/or bioswales within proposed greenspaces, boulevards or landscaped areas to allow for the diversion of overland flow and subsequent infiltration, where feasible; and
- Use of permeable pavements, where feasible (i.e., driveways, parking lots, sidewalks, patios, etc.).

It is recommended that suitable LID mitigation measures be implemented to maintain approximately 90% of the pre-development infiltration following development. Due to the low permeability of the surficial glacial till, the proposed LID mitigation measures must be suitably designed for use in fine-textured soils with percolation rates of less than 15 millimeters per hour (mm/hr).

Design considerations for infiltration in low permeability soils include, but are not limited to:

- Use of underdrains with storage reservoirs below the underdrain;
- Longer drawdown periods and overflows;
- Vertical orientation of storage to increase hydraulic head;
- Matric potential and groundwater mounding;
- Compaction of soils within footprint of facility by heavy machinery during construction; and
- Decrease in infiltration performance over time and system maintenance requirements.

In-situ infiltration testing in areas considered for infiltration is highly recommended to assess feasibility and provide a site-specific infiltration rate of the soils in those areas to inform the design. The testing program should include profiling of infiltration rates with depth.

7.3.2 Groundwater Recharge

Though the Site is not considered to be an area of significant groundwater recharge, by implementing appropriate LID mitigation measures to maintain approximately 90% of the pre-development infiltration and implementing a SMP to mitigate the reduction in infiltration due to soil and subsoil compaction, no significant change in groundwater recharge is anticipated following development.

Furthermore, the agricultural drainage tile system discussed in Section 3.3 would intercept some component of the infiltrating rainwater pulse, effectively decreasing the realized groundwater recharge. Removal of the drainage tile system will further improve groundwater recharge.

7.3.3 Water Supply Wells

As discussed in Section 7.3.1, mitigation measures will be implemented to maintain approximately 90% of the pre-development infiltration at the Site. As a result, no significant change in the available drawdown of existing water supply wells is expected as a result of the proposed development.

7.3.4 Watercourses and Wetlands

As discussed in Sections 7.1.2 and 7.1.3, the watercourses and wetlands identified on-Site are not considered to be dependent on groundwater. No groundwater related impacts to these features are anticipated as a result of the proposed development.

8.0 Conclusions

Based on the foregoing discussion, it is concluded that:

- i. Stratigraphic conditions consist of low permeability glacial till deposits ranging in composition from sandy silt to clayey silt interbedded with saturated granular deposits consisting of silt to silty sand to gravelly sand to sand and gravel.

- ii. Groundwater elevations within the confined granular deposits ranged from a maximum of 262.56 m AMSL to a minimum of 257.30 m AMSL over the period of record.
- iii. Artesian conditions may be encountered in the saturated granular deposits.
- iv. Proactive construction dewatering or depressurization is not anticipated to be required to facilitate excavations for site services, foundations and/or stormwater management facilities, though there is the risk of encountering saturated granular deposits interbedded within the glacial till that may require dewatering. Nuisance dewatering may be required to control groundwater seepage from sand/silt seams within the glacial till.
- v. The identified watercourses and associated wetland communities are not considered to be groundwater dependent.
- vi. If unmitigated, the increase in the impervious surface area at the Site following development is anticipated to decrease infiltration and increase runoff relative to the existing conditions.
- vii. The surficial soils may be susceptible to compaction by heavy machinery traffic during construction, which may further reduce their infiltration capacity.
- viii. Nearby water supply wells may be susceptible to well interference due to heavy construction equipment vibrations, spills and/or temporary construction dewatering, if any.
- ix. No other significant impacts on groundwater receptors are anticipated as a result of the proposed development or related construction activities.

9.0 Recommendations

It is recommended that:

- i. The groundwater level monitoring program described above should be continued to provide up to date groundwater levels for final design, approvals, permitting, tendering and construction;
- ii. As a precaution, it is recommended that an EASR be obtained to avoid potential delays if interbedded saturated granular layers are encountered during excavation within the glacial tills and to maintain staging and scheduling flexibility should large areas or multiple excavations require concurrent nuisance dewatering.
- iii. To identify nearby water supply wells that may be susceptible to well interference from equipment vibrations, spills and/or temporary construction dewatering, a door to door well survey should be undertaken for properties that are not connected to a piped municipal water supply and are located within 250 metres of the Site.
- iv. Based on the results of the door to door well inventory, a monitoring and contingency plan should be developed for wells that are considered susceptible to interference during construction.
- x. A best practices SMP should be developed and implemented during clearing, grading and construction with the goal to preserve or restore the pre-development infiltration capacity of the native soils and subsoils in areas that will remain pervious following development.

- xi. Suitable LID strategies should be implemented, where feasible, to mitigate the potential decrease in infiltration following development and maintain at least 90% of the pre-development infiltration.
- xii. A location-specific investigation of subsurface conditions and in-situ infiltration testing should be carried out to support LID design.
- xiii. Post-development runoff contributions to sensitive natural heritage areas should be similar to pre-development conditions. Mitigation of thermal impacts of the post-development runoff contributed to Kilamanagh Creek should be included in the stormwater management design.
- xiv. In consultation with the TRCA, a feature-based water balance be completed for each sensitive ecological feature identified as runoff dependent.
- xv. Following completion of groundwater monitoring, the monitoring wells should be properly abandoned in accordance with O.Reg. 903, as amended.

10.0 Limitations

Services performed by MTE Consultants Inc. (MTE) were conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the Geoscience Consulting profession practicing under similar conditions in the same geographic area where the services are provided. No other warranty or representation expressed or implied as to the accuracy of the information, conclusions or recommendations is included or intended in this report.

This report was completed for the sole use of the Tribal Partners (Canada) Inc. This report is not intended to be exhaustive in scope or to imply a risk-free site. As such, this report may not deal with all issues potentially applicable to the site and may omit aspects which are or may be of interest to the reader.

In addition, it should be recognized that a discrete soil sample represents one distinct portion of a site at the time it is collected, and that the findings of this report are based on conditions as they existed during the time period of the investigation. The material in the report reflects our opinions using the information available at the time the report was written. The soil and groundwater conditions between and beyond the test holes may differ from those encountered in the test holes. Should subsurface conditions arise that are different from those noted herein, MTE should be notified to determine whether or not changes should be made as a result of these conditions.

It should be recognized that the passage of time may affect the views, conclusions and recommendations (if any) provided in this report because groundwater and soil conditions of a property can change, along with regulatory requirements. All design details were not known at the time of submission of this report and it is recommended that MTE be retained to review the final design documents prior to construction to confirm they are consistent with our report recommendations. Should additional or new information become available, MTE recommends that it be brought to our attention in order that we may determine whether it affects the contents of this report.


Any use which another party makes of this report, or any reliance on, or decisions to be made based upon it, are the responsibility of such parties. MTE accepts no responsibility for liabilities incurred by or damages, if any, suffered by another party as a result of decisions made or actions taken, based upon this report. Others with interest in the site should undertake their

own investigations and studies to determine how or if the condition affects them or their plans. The contractors bidding on this project or undertaking the construction should make their own interpretation of the factual information and draw their own conclusions as to how subsurface conditions may affect their work.

The benchmark and elevations provided in this report are primarily established to identify differences between the test hole locations and should not be used for other purposes such as, planning, development, grading, and excavation.

All of which is respectfully submitted,

MTE Consultants Inc.



Mackenzie Costello

Environmental Scientist
+1 (519) 204-6510 ext. 2212
mcostello@mte85.com



John McNeil, M.Sc., P.Geol.

Manager, Environmental Division
Senior Hydrogeologist
+1 (519) 204-6510 ext. 2228
jmcneil@mte85.com

MBC/JDM:vlf


M:\48043\300\8 - Deliverables\3 - Reports\R01\48043-300 20210223 FINAL Prelim HydroG - North Site.docx

11.0 References

- Armstrong, D., & Dodge, J. (2007). Paleozoic Geology of Southern Ontario. *Miscellaneous Release - Data 219*. Ontario Geological Survey.
- Chapman, L. J., & Putnam, D. F. (1984). The Physiography of Southern Ontario - Second Addition. In L. J. Chapman, & D. F. Putnam, *The Physiography of Southern Ontario - Second Addition*. University of Toronto Press.
- Environment Canada. (2021). *Canadian Climate Normals*. Retrieved from https://climate.weather.gc.ca/climate_normals/index_e.html
- Freeze, R., & Cherry, J. (1979). *Groundwater*. Englewood Cliffs, New Jersey: Prentice-Hall.
- Hvorslev, M. (1951). *Time Lag and Soil Permeability in Ground-Water Observation* (Vols. Bulletin No. 36, Waterways Experiment Station). Vicksburg, Mississippi: U.S. Army Corps of Engineers.
- Johnson, M. D., Armstrong, D. K., Sanford, B. V., Telford, P. G., & Rutka, M. A. (1992). Paleozoic and Mesozoic Geology of Ontario. In *Geology of Ontario* (pp. 907-1008). Ontario Geological Survey.
- Land Information Ontario. (2020). *Areas of Natural and Scientific Interest (ANSI)*. Retrieved from Ontario GeoHub: <https://geohub.lio.gov.on.ca/datasets/areas-of-natural-and-scientific-interest-ansi>
- Land Information Ontario. (2020). *Wetlands*. Retrieved from Ontario GeoHyb: <https://geohub.lio.gov.on.ca/datasets/mnrf::wetlands>
- Ministry of Environment, Conservation and Parks. (2021). Retrieved from Source Protection Information Atlas: <https://www.gisapplication.lrc.gov.on.ca/SourceWaterProtection/Index.html?viewer=SourceWaterProtection.SWPViewer&locale=en-US>
- Ministry of the Environment. (2003). *Stormwater Management Planning and Design Manual*.
- Ministry of the Environment, Conservation and Parks. (2021). Retrieved from PTTW Database: <https://www.ontario.ca/environment-and-energy/map-permits-take-water>
- Ontario Department of Mines. (1968). Preliminary Map P.470. *Bolton Sheet, Bedrock Topography Series, Southern Ontario, Scale 1:50,000*. Ontario Department of Mines.
- Ontario Geological Survey. (2003). *Surficial Geology of Ontario* (Vols. Miscellaneous Release Data 128 - Revised). Ontario Geological Survey, .
- Region of Peel. (2008, October). *Natural Heritage Policy Review*. Retrieved from Peel Region: w.peelregion.ca/planning/officialplan/pdfs/Natural-Heritage-Policy-Review-Discussion-Paper.pdf
- WSP Canada Inc. (2021a). *Comprehensive Environmental Impact Study and Management Plan*, 12892 Dixie Road, Caledon, Ontario. Project No. 201-11545-00.
- WSP Canada Inc. (2021b). *Stormwater Management Report*, 12892 Dixie Road, Caledon, Ontario. Project No. 201-11545-00.
- WSP Canada Inc. (2021c). *Functional Servicing Report*, 12892 Dixie Road, Caledon, Ontario. Project No. 201-11545-00.


Figures

February 23, 2021 — 2:05 PM — Plotted By: Slemieux
 Project: 48043-300 CAD: P:\48043\300\48043-300-MS1.DWG
 1 SITE LOCATION MAP




Engineers, Scientists, Surveyors
 Ph. (905) 639-2552


0 2 4 6 8 10km
 Scale(8.5x11): 1:200 000

CLIENT	Tribal Partners Canada Inc.		TITLE	Site Location Map	
PROJECT	Preliminary Hydrogeological Assessment		Reviewed By	JDM	
SITE	12892 Dixie Road Caledon, ON		Prepared By	MBC	
			Drawn By	SLG	
			Date	February 2021	
			Project No.	48043-300	
			Figure No.	1	







NORTH



PROJECT
NORTH


Legend

 Site Boundary


 500m Study Area

Quaternary Geology

Quaternary

 19. Modern alluvial deposits: clay, silt, sand, gravel, may contain organic remains

5. Till:

 5d. Clay to silt-textured till (derived from glaciolacustrine deposits or shale)


Data Sources:

Ontario Geological Survey 2010. Surficial geology of southern Ontario; Ontario Geological Survey Miscellaneous Release-128 - Revised.

South Central Ontario Orthophotography Project (2018). Source: Data provided by Ontario Ministry of Natural Resources and Forestry.


© Copyright: 2018 Queen's Printer of Ontario. All Rights Reserved.

0 60 120 180 240 300 m



Scale (11x17): 1:7000

Project CRS: NAD83 / UTM zone 17N



MTE

Engineers, Scientists, Surveyors

Ph. (519) 204-6510

Client

Canaola Inc.

Project

Preliminary Hydrogeological Assessment

Site


12892 Dixie Road, Caledon, ON

Title

Quaternary Geology

Reviewed By	JDM
Prepared By	MBC
Drawn By	SAR
Date	February 2021

Project No	48043-300
Figure No	2





NORTH



PROJECT NORTH

LEGEND

 Property Line

 Study Area

Ontario Water Well Records:

-  Observation Well
-  Water Supply
-  Test Hole
-  Abandoned Well
-  Unknown Well

Notes:
All Locations are Approximate





0 70 140 210 280 350m

Scale(11x17): 1:7000




MTE
Engineers, Scientists, Surveyors
Ph. (905) 639-2552

CLIENT	Tribal Partners Canada Inc.	
PROJECT	Preliminary Hydrogeological Assessment	
SITE	12892 Dixie Road Caledon, ON	
TITLE	Water Wells	
Reviewed By	JDM	
Prepared By	MBC	Project No. 48043-300
Drawn By	SGL	Figure No.
Date	February 2021	3




- LEGEND**
- Property Line
 - Existing Building
 - Permanent Watercourse
 - Intermittent/Ephemeral Watercourse
 - Abandoned Drinking Water Well
 - Borehole
 - Monitoring Well (Phase II ESA)
 - Monitoring Well (Hydrogeological Assessment)
 - Datalogger Installed
 - Staff Gauge
 - Cross-Section Line

Notes:
All Locations are Approximate



CLIENT	Tribal Partners Canada Inc.	
PROJECT	Preliminary Hydrogeological Assessment	
SITE	12892 Dixie Road Caledon, ON	
TITLE	Location Plan	
Reviewed By	JDM	
Prepared By	MBC	Project No. 48043-300
Drawn By	SGL	Figure No.
Date	February 2021	4



Scale(11x17): N.T.S.

MTE
Engineers, Scientists, Surveyors
Ph. (905) 639-2552


CLIENT
Tribal Partners Canada Inc.

PROJECT
Preliminary
Hydrogeological Assessment

SITE
12892 Dixie Road
Caledon, ON

TITLE
Cross-Section A-A'

Reviewed By	JDM		
Prepared By	MBC	Project No.	48043-300
Drawn By	SGL	Figure No.	5
Date	February 2021		



Scale(11x17): N.T.S.

MTE
Engineers, Scientists, Surveyors
Ph. (905) 639-2552


CLIENT
Tribal Partners Canada Inc.

PROJECT
Preliminary
Hydrogeological Assessment

SITE
12892 Dixie Road
Caledon, ON


TITLE
Cross-Section B-B'

Reviewed By	JDM		
Prepared By	MBC	Project No.	48043-300
Drawn By	SGL	Figure No.	6
Date	February 2021		



LEGEND

- Property Line
- Fill
- Sand/ Silty Sand/ Sand and Gravel
- Clayey Silt Till/ Sandy Silt Till



NOTES:

1. Cross-Section locations are shown in Figure 4
2. Simplified stratigraphy shown above is based on the observed subsurface conditions at the borehole locations
3. Subsurface conditions may vary between and beyond each borehole locations
4. m AMSL - metres above mean sea level
5. Water levels measured on 2020/12/14

Scale(11x17): N.T.S.



CLIENT

Tribal Partners Canada Inc.

PROJECT

Preliminary
Hydrogeological Assessment

SITE

12892 Dixie Road
Caledon, ON

TITLE



Cross-Section C-C'

Reviewed By JDM

Prepared By MBC Project No. 48043-300


Drawn By SGL Figure No. 7

Date February 2021





- LEGEND**
- Property Line
 - Existing Building
 - Permanent Watercourse
 - Intermittent/Ephemeral Watercourse
 - Monitoring Well (Phase II ESA)
 - Monitoring Well (Hydrogeological Assessment)
 - Staff Gauge
 - Groundwater Elevation (m AMSL)
 - Groundwater Contour (m AMSL)
 - Inferred Direction of Groundwater Flow

NOTES:
Water Levels Measured on 2020/12/14
m AMSL - Metres Above Mean Sea Level
All Locations are Approximate




CLIENT		Tribal Partners Canada Inc.	
PROJECT		Preliminary Hydrogeological Assessment	
SITE		12892 Dixie Road Caledon, ON	
TITLE		Groundwater Flow in Confined Sands	
Reviewed By		JDM	
Prepared By	MBC	Project No.	48043-300
Drawn By	SGL	Figure No.	8
Date	February 2021		







NORTH




PROJECT
NORTH


LEGEND

 Property Line


 Catchment



Catchment ID




Area (ha.)



% IMP


Notes:

- All Locations are Approximate
- Pre-Development Catchments Provided by WSP (2021)



0 40 80 120 160 200m

Scale(11x17): 1:4000



MTE
Engineers, Scientists, Surveyors
Ph. (905) 639-2552

CLIENT

Tribal Partners Canada Inc.

PROJECT

Preliminary
Hydrogeological Assessment

SITE

12892 Dixie Road
Caledon, ON

TITLE



**Pre-Development
Catchments**

Reviewed By JDM

Prepared By MBC Project No. 48043-300

Drawn By SGL Figure No. **9**

Date February 2021




LEGEND

- Property Line
- Catchment

Notes:

- All Locations are Approximate
- Post-Development Catchments Provided by WSP (2021)



MTE
Engineers, Scientists, Surveyors
Ph. (905) 639-2552

CLIENT
Tribal Partners Canada Inc.

PROJECT
Preliminary Hydrogeological Assessment

SITE
12892 Dixie Road
Caledon, ON

TITLE
Post-Development Catchments

Reviewed By JDM
Prepared By MBC
Drawn By SGL
Date February 2021

Project No. 48043-300
Figure No. 10

Tables

Table 1: Summary of MECP Water Well Records

MECP Well No.	UTM Coordinates (NAD83 Zone 17)		Year Drilled	Nominal Casing Diameter (millimetres)	Drilling Method	Well Status	Well Use	Water Quality	Water Found (m BGS)	Total Depth (metres)	Interval Top (m BGS)	Screened Bottom (m BGS)	Static Level (m BGS)	Pumping Test			Depth to Unit Base (m BGS)	Stratigraphy			
	Eastings	Northing												Level	Rate	Duration		Colour	Material 1	Material 2	Material 3
7238069	596033	4847347	2015	52	Boring	Observation Well	Monitoring	-	-	7.6	4.6	7.6	-	-	-	-	2.1 7.6	brown grey	fill clay	loose packed	- -
7238068	596233	4847168	2015	52	Boring	Observation Well	Monitoring	-	-	7.6	4.6	7.6	-	-	-	-	2.1 7.6	brown grey	fill clay	sand silt	loose packed
4904249	595715	4847564	1973	127	Rotary	Water Supply	Domestic		34.7	39.0	34.7	39.0	15.2	19.8	15	6.0	8.2 10.4 19.8 29.9 39.0	brown grey grey brown	clay clay clay clay gravel	stones gravel - - shale	- - - - -
7255231	596200	4847193	2015	52	Rotary	Observation Well	Monitoring	-	-	6.1	4.5	6.1	-	-	-	-	1.8 3.7 6.1	brown brown grey	sand sand silt	gravel silt sand	hard hard hard
4901348	596039	4847019	1959	762	-	Water Supply	Domestic	Fresh	18.3	18.9	-	-	-	12.2	18.9	-	4.5 17.7 18.2	brown grey grey	loam clay sand	clay stones -	- - -
7238063	595696	4847696	2015	52	-	Observation Well	Monitoring	-	-	-	4.6	7.6	-	-	-	-	1.5 3.1 7.6	brown brown grey	fill sand clay	silt silt	loose loose packed
7266225	595968	4846774	2016	52	Rotary	Monitoring Well / Test hole	Monitoring / Test Hole	-	-	7.6	6.1	7.6	-	-	-	-	7.6	brown to grey	sandy silt	some clay and gravel	hard -
7294665	596257	4847157	2017	52	Auger	Observation Well	Monitoring	-	9.1	13.7	9.1	13.7	-	-	-	-	9.1	grey	silt	clay	soft
4903372	-	-	1969	178	Cable Tool	Water Supply	Domestic	Fresh	36.6	37.2	-	-	17.1	18.3	18.9	12.0	0.3 3.4 8.8 36.0 37.2	brown	loam sand sand sand sand	- sandy clay hard pan quick sand -	- - - - -
7246998	595955	4846732	2015	52	Direct Push	Abandoned Monitoring and Test Hole	Monitoring and Test Hole	-	-	6.1	3.0	6.1	-	-	-	-	-	-	-	-	-
7302032	596184	4847281	2017	900	-	Abandoned Monitoring	-	-	4.9	11.9	-	-	-	-	-	-	-	-	-	-	-
7326241	595968	4846774	2018	-	-	-	-	-	-	8.5	-	-	-	-	-	-	-	-	-	-	-
7326239	596032	4846900	2018	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7326240	595915	4846755	2018	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4906148	594651	4847825	1983	762	Boring	Water Supply	Domestic	Cloudy	12.2	22.9	-	-	12.2	22.0	7.6	0.5	0.3 6.1 15.0 22.9	brown brown grey grey	loam clay clay clay	hard hard hard sand	- - - hard
4901351	594945	4846557	1967	762	Boring	Water Supply	Domestic / Livestock	Fresh	8.5	12.2	-	-	8.5	11.3	5.7	0.5	0.3 3.0 5.8 8.5 8.8 12.2	- brown - blue - blue	loam clay hard pan clay sand clay	- - - - - -	- - - - - -
4903799	595245	487973	1971	762	Boring	Water Supply	Domestic / Livestock	Fresh	17.7	20.7	-	-	1.5	-	11.4	-	0.3 2.4 3.0 3.6 6.7 7.6 15.2 20.7	brown brown brown brown grey grey grey grey	loam clay sand clay clay sand clay clay	stones gravel - - - clay silt sand	- - - - - - stones stones
7238064	594910	4848237	2015	52	Boring	Observation Well	Monitoring	-	-	7.6	4.6	7.6	-	-	-	-	1.5 3.1 7.6	brown brown grey	fill sand clay	- silt silt	loose loose packed
4903980	594865	4848123	1972	152	Cable Tool	Water Supply	Domestic	Clear	19.8	30.5	-	-	19.8	27.4	3.8	1.0	0.6 17.7 19.8	brown brown red	loam clay shale	- sand -	- - -
7238065	594661	4847912	2015	52	Boring	Observation Well	Monitoring	-	-	7.6	4.6	7.6	-	-	-	-	1.5 3.1 7.6	brown brown grey	fill sand clay	- silt silt	loose loose packed
7202814	595440	4848240	2013	150	-	Abandoned	-	Fresh	2.4	-	-	-	-	-	-	-	-	-	-	-	-
7240978	595303	4848080	2015	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7238070	595355	4848018	2015	52	Boring	-	Monitoring	-	-	7.6	4.3	7.6	-	-	-	-	2.1 7.6	brown grey	fill clay	sand silt	loose packed
7238058	595356	4848017	2015	52	Boring	Observation Well	Monitoring	-	-	18.3	15.3	18.3	-	-	-	-	3.1 9.2 18.3	brown brown grey	fill sand sand	gravel silt silt	loose packed packed
4901350	595201	4847250	1952	102	Cable Tool	Water Supply	Domestic / Livestock	Fresh	41.1	41.1	-	-	12.2	12.2	37.9	-	9.1 25.9 38.1 39.6 41.1	- blue - - -	hard pan clay sand sand gravel	gravel - - stones -	- - - - -
7238066	595305	4848080	2015	52	Boring	Observation Well	Monitoring	-	-	18.3	15.3	18.3	-	-	-	-	3.1 9.2 18.3	brown brown grey	fill sand sand	gravel silt silt	sand packed packed

Table 2: Summary of Single Well Response Tests

Monitoring Well	Screened Interval (m BGS)	Hydrostratigraphy	Stratigraphic Description	Test	K (m/s)	Geometric Mean, K (m/s)
MW101-20	8.8 - 10.4	Aquitard	compact to very dense grey SILT AND SAND, some clay, trace gravel	Rising Head 1	9.0E-08	8.E-08
				Rising Head 2	7.9E-08	
MW103-20	5.2 - 6.7	Confined Aquifer	very dense brown SILTY SAND, trace clay to dense grey/brown SAND, some silt, some gravel	Falling Head 1	3.3E-06	2.E-05
				Rising Head 1	5.4E-05	
				Rising Head 2	7.4E-05	
MW106-20	10.7 - 11.6	Confined Aquifer	compact grey SILT to SILTY SAND, trace clay	Falling Head 1	1.5E-06	1.E-06
				Rising Head 1	1.4E-06	
MW107-20	10.5 - 11.4	Confined Aquifer	compact grey SILTY SAND, some clay, trace gravel to very dense grey GRAVELLY SAND	Falling Head 1	4.3E-07	7.E-07
				Rising Head 1	9.9E-07	

- Notes:
- 1. Table to be read in conjunction with accompanying report.
 - 2. K values provided in metres per second (m/s).
 - 3. Screened intervals provided in metres (m) below ground surface (bgs).
 - 4. Refer to Figure 4 for well locations.
 - 5. Refer to Borehole Logs for installation details.

Table 3: Summary of Manually Measured Groundwater Elevations

Well ID	Ground Surface Elevation (m AMSL)	Top of Pipe Elevation (m AMSL)	2020-11-04		2020-11-09		2020-11-19		2020-11-23		2020-11-30		2020-12-14	
			Water Level (m BTOP)	Elevation (m AMSL)	Water Level (m BTOP)	Elevation (m AMSL)	Water Level (m BTOP)	Elevation (m AMSL)	Water Level (m BTOP)	Elevation (m AMSL)	Water Level (m BTOP)	Elevation (m AMSL)	Water Level (m BTOP)	Elevation (m AMSL)
MW101-20	266.97	267.89	8.46	259.43	8.48	259.42	8.43	259.46	8.47	259.43	-	-	8.45	259.44
MW102-20	267.55	268.49	8.18	260.31	8.18	260.31	-	-	8.20	260.29	-	-	8.21	260.28
MW103-20	268.03	269.03	6.53	262.50	6.53	262.51	-	-	6.57	262.47	6.59	262.44	6.59	262.45
MW104-20	272.09	273.13	Dry	-	Dry	-	-	-	Dry	-	Dry	-	Dry	-
MW105-20	264.65	265.66	Dry	-	6.82	258.84	-	-	6.54	259.12	6.63	259.03	6.62	259.04
MW106-20	266.25	267.20	9.65	257.55	9.70	257.49	-	-	9.74	257.46	9.49	257.71	9.54	257.66
MW107-20	268.42	269.37	8.98	260.39	9.07	260.31	-	-	9.11	260.26	9.04	260.33	9.18	260.20
SG1	263.03	264.52	-	-	-	-	1.20	263.32	1.18	263.35	-	-	1.13	263.40
SG2	259.77	261.49	-	-	-	-	1.45	260.04	1.45	260.04	-	-	1.25	260.24

- Notes:
- 1. Table to be read in conjunction with accompanying report.
 - 2. See Borehole Log for installation details.
 - 3. Dates are provided in Standard International (SI) format (i.e., yyyy-mm-dd).
 - 4. Water Levels provided in metres (m) below top of pipe (BTOP).
 - 5. Elevations are provided in metres (m) above mean sea level (AMSL).
 - 6. Reference elevations surveyed by MTE November 25, 2020 relative to geodetic datum.


Table 4: Analytical Results for RCAP Comprehensive in Groundwater and Surface Water

Parameters	Unit	RDL	PWQO Criteria	Sample Location		MW106-20	MW107-20	SG1	SG2
				Sample Name		MW106-20	MW107-20	SG1	SG2
				Lab Job #		C0V1801	C0V1801	C0V1801	C0V1801
				Laboratory ID		OFX270	OFX271	OFX272	OFX273
				Sampling Date		23-Nov-2020	23-Nov-2020	23-Nov-2020	23-Nov-2020
				Well Screen Interval (m bgs)		10.7 - 11.6	10.5 - 11.4	NA	NA
Maximum Concentration									
Calculated Parameters									
Anion Sum	me/L	NA	NV		14.1	8.11	7.09	14.1	8.49
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	1.0	NV		330	330	300	280	270
Calculated TDS	mg/L	1.0	NV		790	420	350	790	460
Carb. Alkalinity (calc. as CaCO3)	mg/L	1.0	NV		5.2	5.2	4.2	3.8	4
Cation Sum	me/L	NA	NV		14.3	8.1	7.12	14.3	8.45
Hardness (CaCO3)	mg/L	1.0	NV		390	340	320	390	350
Ion Balance (% Difference)	%	NA	NV		0.81	0.09	0.22	0.81	0.22
Langelier Index (@ 20C)	NA	NA	NV		1.19	1.07	0.765	1.17	1.19
Langelier Index (@ 4C)	NA	NA	NV		0.943	0.824	0.516	0.924	0.943
Saturation pH (@ 20C)	NA	NA	NV		7.41	7.16	7.41	6.99	7.01
Saturation pH (@ 4C)	NA	NA	NV		7.65	7.41	7.65	7.24	7.25
Inorganics									
Alkalinity (Total as CaCO3)	mg/L	1.0	NV		330	330	300	280	270
Conductivity	umho/cm	1.0	NV		1500	720	630	1500	820
Dissolved Chloride (Cl-)	µg/L	1000 - 3000	NV		260000	11000	15000	260000	75000
Dissolved Organic Carbon	mg/L	0.40	NV		8.6	1.9	1.1	8.6	4.9
Dissolved Sulphate (SO4)	mg/L	1.0	NV		55	55	27	49	41
Nitrate (N)	mg/L	0.10	NV		0.41	0.41	<0.10	<0.10	0.37
Nitrate + Nitrite (N)	mg/L	0.10	NV		0.53	0.53	<0.10	<0.10	0.37
Nitrite (N)	mg/L	0.010	NV		0.115	0.115	<0.010	<0.010	<0.010
Orthophosphate (P)	mg/L	0.010	NV		0.11	<0.010	0.011	0.11	0.035
pH	pH	NA	6.5:8.5		8.23	8.23	8.17	8.16	8.2
Total Ammonia-N	mg/L	0.050	NV		0.32	0.32	0.2	<0.050	<0.050
Metals									
Dissolved Aluminum (Al)	µg/L	4.9	NV		80	80	<4.9	<4.9	7.1
Dissolved Antimony (Sb)	µg/L	0.50	20		0.62	0.62	<0.50	<0.50	<0.50
Dissolved Arsenic (As)	µg/L	1.0	100		5	4.4	5	<1.0	<1.0
Dissolved Barium (Ba)	µg/L	2.0	NV		220	220	120	53	53
Dissolved Beryllium (Be)	µg/L	0.40	11	<	0.40	<0.40	<0.40	<0.40	<0.40
Dissolved Boron (B)	µg/L	10	200		79	63	79	28	17
Dissolved Cadmium (Cd)	µg/L	0.090	0.2	<	0.090	<0.090	<0.090	<0.090	<0.090
Dissolved Calcium (Ca)	µg/L	200	NV		120000	59000	35000	120000	100000
Dissolved Chromium (Cr)	µg/L	5.0	NV	<	5.0	<5.0	<5.0	<5.0	<5.0
Dissolved Cobalt (Co)	µg/L	0.50	0.9	<	0.50	<0.50	<0.50	<0.50	<0.50
Dissolved Copper (Cu)	µg/L	0.90	5		2.4	1.7	<0.90	2.4	<0.90
Dissolved Iron (Fe)	µg/L	100	300		200	200	<100	<100	<100
Dissolved Lead (Pb)	µg/L	0.50	5	<	0.50	<0.50	<0.50	<0.50	<0.50
Dissolved Magnesium (Mg)	µg/L	50	NV		56000	47000	56000	23000	21000
Dissolved Manganese (Mn)	µg/L	2.0	NV		62	62	20	33	51
Dissolved Molybdenum (Mo)	µg/L	0.50	40		9	9	3.9	<0.50	<0.50
Dissolved Nickel (Ni)	µg/L	1.0	25	<	1.0	<1.0	<1.0	<1.0	<1.0
Dissolved Phosphorus (P)	µg/L	100	NV		180	<100	<100	180	<100
Dissolved Potassium (K)	µg/L	200	NV		9900	4400	4700	9900	3300
Dissolved Selenium (Se)	µg/L	2.0	100	<	2.0	<2.0	<2.0	<2.0	<2.0
Dissolved Silicon (Si)	µg/L	50	NV		7600	7500	7600	4900	5300
Dissolved Silver (Ag)	µg/L	0.090	0.1	<	0.090	<0.090	<0.090	<0.090	<0.090
Dissolved Sodium (Na)	µg/L	100	NV		140000	26000	15000	140000	33000
Dissolved Strontium (Sr)	µg/L	1.0	NV		530	510	530	310	250
Dissolved Thallium (Tl)	µg/L	0.050	0.3	<	0.05	<0.050	<0.050	<0.050	<0.050
Dissolved Titanium (Ti)	µg/L	5.0	NV	<	5.0	<5.0	<5.0	<5.0	<5.0
Dissolved Uranium (U)	µg/L	0.10	5		1.6	1.5	0.55	1.6	0.6
Dissolved Vanadium (V)	µg/L	0.50	6		1.7	1.7	0.64	<0.50	<0.50
Dissolved Zinc (Zn)	µg/L	5.0	30	<	5.0	<5.0	<5.0	<5.0	<5.0

- Notes:
1. Criteria for Provincial Water Quality Objectives "PWQO" (Feb. 1999)
 2. **Exceeds Criteria** - Exceeds Criteria
 3. "-" - parameter not analyzed
 4. m bgs - Metres below ground surface
 5. RDL - Reported detection limit
 6. NV- No Value
 7. NA - Not Applicable
 8. < - Less than the Reporting Detection Limit
 9. µg/L- Micro-grams per Litre
 10. mg/L - Milligrams per Litre
 11. umho/cm - Micromhos per Centimeter
 12. me/L - Milliequivalent per Litre

Appendix A

Concept Plan



KEY PLAN

NTS

LEGAL DESCRIPTION

PLAN OF SURVEY OF
PART OF LOTS 21 AND 22
CONCESSION 2,
CITY OF CALEDON
(FORMERLY THE TOWNSHIP OF
CHINGUACOUSY, COUNTY OF PEEL)
REGIONAL MUNICIPALITY OF PEEL

TRUE NORTH

PROJECT NORTH

SCALE 1 : 1000

0 20 40 60 80 100 METERS

PLAN: A.VIS SURVEYING INC.

© COPYRIGHT 2021

SITE AREA SUMMARY

TOTAL SITE AREA	790,553.67 m ²	or	195.35 acres
SITE AREA "A-B" (including buffer)	398,261.32 m ²	or	98.41 acres
BUFFER "A-B-C1"	24,392.41 m ²	or	6.03 acres
SITE AREA "C-D" (including buffer)	256,385.34 m ²	or	63.35 acres
BUFFER "C2-D"	31,665.35 m ²	or	9.88 acres
ENVIRONMENTALLY PROTECTED AREAS (excluding buffers)	135,907.01 m ²	or	33.59 acres
ENVIRONMENTAL AREA "A"	26,709.02 m ²	or	6.60 acres
ENVIRONMENTAL AREA "C" (Wood Lot)	100,877.00 m ²	or	24.93 acres
ENVIRONMENTAL AREA "D"	8,320.99 m ²	or	2.06 acres

OVERALL SITE STATISTICS

ZONING DESIGNATION		MS-XX
	REQUIRED	PROVIDED
PLANTING STRIP WIDTH		
FRONT YARD (OLD SCHOOL RD)	9.0 m	3.54 m
EXTERIOR LOT LINE (DIXIE RD.)	7.0 m	8.62 m
INTERIOR LOT LINE (WEST)	1.5 m	0.0 m
REAR LOT LINE (SOUTH)	0.0 m	0.0 m
SETBACKS		
LOT FRONTAGE	30.0 m	456.33 m
FRONT YARD (OLD SCHOOL RD)	20.0 m	57.52 m
EXTERIOR SIDE YARD (DIXIE RD.)	7.5 m	20.12 m
INTERIOR SIDE YARD (WEST)	6.0 m	14.63 m
REAR YARD (SOUTH)	15.0 m	52.47 m
SITE COVERAGE (Based on Total Site Area, less ENV. "A", "D" & Wood Lot)	247,242.98 m ²	or 37.76 %
LANDSCAPE AREA (Based on Total Site Area, less ENV. "A", "D" & Wood Lot)	178,816.74 m ²	or 27.32 %
PAVED AREA (Based on Total Site Area, less ENV. "A", "D" & Wood Lot)	228,586.94 m ²	or 34.92 %
TOTAL PARKING	1,656 spaces	1,857 spaces
TOTAL ACCESSIBLE PARKING	39 spaces	42 spaces
SNOW STORAGE AREA (MIN. 2%)	11,972.89 m ²	11,972.89 m ²

SITE "A-B" (NORTH) STATISTICS

DEVELOPMENT SITE AREA	373,711.65 m ²	or 92.35 acres
-----------------------	---------------------------	----------------

CONTEXT MAP

FIRE ROUTE SIGN STANDARDS

FIGURE A
FIRE ROUTE

FIGURE B
FIRE ROUTE

1. All signs required to be 1000 mm x 1000 mm and shall be placed on a 200 mm x 400 mm sign post and shall display a format as illustrated in Figure A and Figure B.

2. The sign shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel.

3. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel.

4. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel.

5. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel. Signs shall be placed on the right side of the road, facing the direction of travel.

ACCESSIBLE PARKING SPACE


SYMBOL LEGEND

MAN DOOR LOCATIONS	LOADING DOCK LOCATIONS	DRIVE-IN OVERHEAD DOORS	HYDRANT & VALVE	CATCH BASIN	DOUBLE CATCH BASIN	STORM SEWER MANHOLE	SANITARY SEWER MANHOLE	TOP OF CURB	TOP OF WALL	DIRECTION OF TRAFFIC FLOW	EXISTING ELEVATION	PROPOSED ELEVATION	DIRECTION OF DRAINAGE FLOW	ELECTRIC VEHICLE PARKING	CARPOOL PARKING SIGN	FIRE DEPARTMENT CONNECTION / SIAMSE CONNECTION
--------------------	------------------------	-------------------------	-----------------	-------------	--------------------	---------------------	------------------------	-------------	-------------	---------------------------	--------------------	--------------------	----------------------------	--------------------------	----------------------	--


CURB RAMP DETAIL

Appendix B


Borehole Logs

ID Number: MW101-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/29/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Water level measured at 7.5 mbgs on Dec 14, 2020

ID Number: MW101-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/29/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Water level measured at 7.5 mbgs on Dec 14, 2020

ID Number: MW102-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** N/A**Field Technician:** SKC**Drafted by:** SKC**Reviewed by:** B. ThornerWater level measured at 7.3mbgs
on Dec 14, 2020


ID Number: MW102-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** N/A


Subsurface Profile				Sample		Dynamic Cone x	Shear Strength (PP) kPa	Shear Strength (FV) kPa	Water Content %	Groundwater Observations and Standpipe Details
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type					
259.9			7.6							
26	8	SILT grey silt, some clay, wet	259.3	11	SS	59				
28		Drilling Terminated	8.2							
30										
32										
34										
36										
38										
40										
42										
44										
46	14									
48										


Field Technician: SKC**Drafted by:** SKC**Reviewed by:** B. ThornerWater level measured at 7.3mbgs
on Dec 14, 2020


ID Number: MW103-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/19/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Water level measured at 5.6mbgs on Dec 14, 2020


ID Number: MW103-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/19/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerWater level measured at 5.6mbgs
on Dec 14, 2020


ID Number: MW104-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/21/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerNo water level measured as
borehole was dry on Dec 14, 2020


ID Number: MW104-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/21/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerNo water level measured as
borehole was dry on Dec 14, 2020

ID Number: MW105-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Water level measured at 5.6 mbgs on Dec 14, 2020


ID Number: MW105-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerWater level measured at 5.6 mbgs
on Dec 14, 2020

ID Number: MW106-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerWater level measured at 8.6 mbgs
on Dec 14, 2020


ID Number: MW106-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Water level measured at 8.6 mbgs on Dec 14, 2020


ID Number: MW107-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. ThornerWater level measured at 8.2 mbgs
on Dec 14, 2020

ID Number: MW107-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:** Monument**Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Water level measured at 8.2 mbgs on Dec 14, 2020

ID Number: BH108-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH109-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/19/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH110-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/19/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH111-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1


ID Number: BH112-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1


ID Number: BH113-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1


ID Number: BH114-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/21/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

ID Number: BH115-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/21/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH116-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/21/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH117-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH118-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH119-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH120-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH121-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Hollow Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH122-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH123-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/22/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH124-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH125-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH126-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH127-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/20/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH128-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH129-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/26/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1


ID Number: BH130-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1


ID Number: BH131-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1


ID Number: BH132-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

ID Number: BH133-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH134-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH135-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH136-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH137-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH138-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner


Sheet: 1 of 1

ID Number: BH139-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/27/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1




ID Number: BH140-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1

ID Number: BH141-20**Project:** 12892 Dixie Road: Engineering Consulting Services**Project No:** 48043-100**Client:** Tribal Partners (Canada) Inc.**Site Location:** 12892 Dixie Road, Caledon, ON**Drill Date:** 10/28/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:****Field Technician:** MBC**Drafted by:** B. Gaul**Reviewed by:** B. Thorner

Sheet: 1 of 1





ID Number: BH201-20**Project Name:** 12892 Dixie Road: Engineering Consulting Services**MTE File No.:** 48043-100**Client:** Tribal Partners**Site Location:** 12824 & 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:** N/A

Subsurface Profile			Sample					Well Completion Details		
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type	Recovery (%)	Soil Sample Lab Analysis			PID (ppm)
ft m 0 2 4 6 2 8 10 12		Ground Surface								
		TOPSOIL Dark brown, clayey silt with rootlets, damp	0.0	1	SS	60	Metals, OCs, CPs, PHCs	0	0	
		FILL Brown, clayey silt with sand, some gravel, moist	0.2							
		CLAYEY SILT Brown, trace sand and gravel, moist	1.7	3	SS	100		0	0	
				4	SS	80		0	0	
		Drilling Terminated	2.9							

Field Technician: SKC**Drafted by:** SKC**Reviewed by:** TJJ

Sheet: 1 of 1




ID Number: BH202-20**Project Name:** 12892 Dixie Road: Engineering Consulting Services**MTE File No.:** 48043-100**Client:** Tribal Partners**Site Location:** 12824 & 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:** N/A

Subsurface Profile			Sample						Well Completion Details	
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type	Recovery (%)	Soil Sample Lab Analysis	PID (ppm)		
0		Ground Surface								
0		TOPSOIL Dark brown, clayey silt with rootlets, damp to moist	0.0							
		FILL Brown, clayey silt, some sand and gravel, moist		1	SS	70	Metals, OCs, CPs, PHCs	0	0	
2		Orange sand seam at 0.91m								
										
				2	SS	85		0	0	
		CLAYEY SILT Brown to grey, some sand and gravel, moist	1.5							
				3	SS	100		0	0	
				4	SS	100		0	0	
				5	SS	100		0	0	
12		Drilling Terminated	3.7							

Field Technician: SKC**Drafted by:** SKC**Reviewed by:** TJJ

Sheet: 1 of 1




ID Number: BH203-20**Project Name:** 12892 Dixie Road: Engineering Consulting Services**MTE File No.:** 48043-100**Client:** Tribal Partners**Site Location:** 12824 & 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:** N/A

Subsurface Profile			Sample					Well Completion Details		
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type	Recovery (%)	Soil Sample Lab Analysis			PID (ppm)
0 ft m		Ground Surface	0.0							
		TOPSOIL Dark brown, clayey silt with rootlets, damp								
		FILL Brown, clayey silt with sand, trace to some gravel, moist		1	SS	0	Metals	0	0	
2										
				2	SS	90		0	0	
4										
		CLAYEY SILT Light brown to grey, trace sand and gravel, moist	1.5	3	SS	90		0	0	
2										
8				4	SS	95		0	0	
10		Drilling Terminated	2.9							
12										

Field Technician: SKC**Drafted by:** SKC**Reviewed by:** TJJ

Sheet: 1 of 1




ID Number: BH204-20**Project Name:** 12892 Dixie Road: Engineering Consulting Services**MTE File No.:** 48043-100**Client:** Tribal Partners**Site Location:** 12824 & 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:** N/A

Subsurface Profile			Sample						Well Completion Details	
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type	Recovery (%)	Soil Sample Lab Analysis	PID (ppm)		
0 ft 0 m		Ground Surface	0.0							
		TOPSOIL Dark brown, clayey silt with rootlets, damp								
		FILL Brown, clayey silt, trace sand and gravel, trace rootlets Higher gravel content from 0.15m to 0.30m Grey mottling at 1.22m		1	SS	70	PHCs	0	0	
2										
				2	SS	80		0	0	
4										
6		CLAYEY SILT Light brown to grey, trace sand and gravel, moist	1.7	3	SS	75		0	0	
2										
8				4	SS	85		0	0	
10		Drilling Terminated	2.9							
12										

Field Technician: SKC**Drafted by:** SKC**Reviewed by:** TJJ

Sheet: 1 of 1

ID Number: BH205-20**Project Name:** 12892 Dixie Road: Engineering Consulting Services**MTE File No.:** 48043-100**Client:** Tribal Partners**Site Location:** 12824 & 12892 Dixie Road, Caledon, ON**Drill Date:** 10/23/2020**Drilling Contractor:** Tri-Phase Group**Drill Rig:** CME 75**Drill Method:** Solid Stem Auger**Protective Cover:** N/A

Subsurface Profile			Sample					Well Completion Details	
Depth	Symbol	Soil Description	Elevation (masl) Depth (m)	Number	Type	Recovery (%)	Soil Sample Lab Analysis		
<div><div>ft m</div><div>0 0</div><div></div><div>2</div><div></div><div>4</div><div></div><div>6 2</div><div></div><div>8</div><div></div><div>10</div><div></div><div>12</div></div>		Ground Surface							
		TOPSOIL Dark brown, clayey silt with rootlets, damp to moist	0.0	1	SS	90	Metals, OCs, CPs, PHCs	0	0
		FILL Brown, clayey silt, some sand and gravel, moist	0.2						
		Grey mottling at 1.22m							
				2	SS	100		0	0
		CLAYEY SILT Brown to grey, some sand, trace gravel, mosit	1.5	3	SS	80		0	0
				4	SS	85		0	0
		Drilling Terminated	2.9						

Field Technician: SKC**Drafted by:** SKC**Reviewed by:** TJJ

Sheet: 1 of 1

Appendix C

Particle Size Distributions



Particle Size Distribution Analysis Test Results

Project Name: 12982 Dixie Road Geotechnical Investigation

Client: Tribal Partners Inc.

Project Location: 12982 Dixie Road, Caledon, ON


Date Sampled: Oct. 19-29, 2020

Date Tested: Nov. 17-24, 2020

MTE File No.: 48043-200

Table No.: 101

Unified Soil Classification



Symbol	Borehole ID	Sample #	Sample Depth
▲	MW101-20	SS-11	9.1-9.8 mbgs
■	MW103-20	SS-8	6.1-6.7 mbgs
×	MW104-20	SS-11	9.9-10.5 mbgs
◆	MW105-20	SS-7	4.6-5.0 mbgs

Description
SILT and SAND, some Clay, trace Gravel
Sandy SILT, trace Clay and Gravel
Silty SAND, trace Clay and Gravel
Clayey Sandy SILT, trace Gravel



NOTES:



Particle Size Distribution Analysis Test Results

Project Name: 12982 Dixie Road Geotechnical Investigation

Client: Tribal Partners Inc.

Project Location: 12982 Dixie Road, Caledon, ON


Date Sampled: Oct. 19-29, 2020

Date Tested: Nov. 17-24, 2020

MTE File No.: 48043-200

Table No.: 102

Unified Soil Classification



Symbol	Borehole ID	Sample #	Sample Depth
▲	MW106-20	SS-11	10.7-11.3 mbgs
■	MW107-20	SS-12	9.9-10.5 mbgs
✕	BH116-20	SS-5	3.0-3.7 mbgs


Description
SILT, some Clay and Sand
Silty SAND, some Clay, trace Gravel
Clayey Sandy SILT, trace Gravel





NOTES:


Appendix D


Single Well Response Tests


			Slug Test Analysis Report	
			Project: Hydrogeological Assessment	
			Number: 48043-300	
			Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW101-20 - Rising Test 1		Test Well: MW101-20
Test Conducted by:			Test Date: 11/23/2020	
Analysis Performed by: MBC		MW101 - Rising Test 1		Analysis Date: 12/14/2020
Aquifer Thickness: 1.60 m				
<div><p>Time [s]</p></div>				
Calculation using Hvorslev				
Observation Well	Hydraulic Conductivity [m/s]			
MW101-20	8.95×10^{-8}			


		Slug Test Analysis Report	
		Project: Hydrogeological Assessment	
		Number: 48043-300	
		Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW101-20 - Rising Test 2	Test Well: MW101-20
Test Conducted by: MBC			Test Date: 11/23/2020
Analysis Performed by: MBC		MW101-20 - Rising Test 2	Analysis Date: 12/14/2020
Aquifer Thickness: 1.60 m			
			
Calculation using Hvorslev			
Observation Well	Hydraulic Conductivity [m/s]		
MW101-20	7.85×10^{-8}		


			Slug Test Analysis Report	
			Project: Hydrogeological Assessment	
			Number: 48043-300	
			Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW103-20 - Falling Test 1		Test Well: MW101-20
Test Conducted by: JAK				Test Date: 11/30/2020
Analysis Performed by: MBC		MW103-20 - Falling Test 1		Analysis Date: 12/1/2020
Aquifer Thickness: 1.60 m				
<div><p>Time [s]</p></div>				
Calculation using Hvorslev				
Observation Well		Hydraulic Conductivity [m/s]		
MW101-20		3.27 × 10 ⁻⁶		


			Slug Test Analysis Report	
			Project: Hydrogeological Assessment	
			Number: 48043-300	
			Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW103-20 - Rising Test 1		Test Well: MW103-20
Test Conducted by: JAK			Test Date: 11/30/2020	
Analysis Performed by: MBC		MW103-20 - Rising Test 1		Analysis Date: 12/1/2020
Aquifer Thickness: 1.60 m				
<div><p>Time [s]</p></div>				
Calculation using Hvorslev				
Observation Well		Hydraulic Conductivity [m/s]		
MW103-20		5.37×10^{-5}		





		Slug Test Analysis Report	
		Project: Hydrogeological Assessment	
		Number: 48043-300	
		Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW106-20 - Rising Test 1	Test Well: MW106-20
Test Conducted by: JAK			Test Date: 11/30/2020
Analysis Performed by: MBC		MW106-20 - Rising Test 1	Analysis Date: 12/1/2020
Aquifer Thickness: 0.50 m			
			
Calculation using Hvorslev			
Observation Well	Hydraulic Conductivity [m/s]		
MW106-20	1.37×10^{-6}		


		Slug Test Analysis Report	
		Project: Hydrogeological Assessment	
		Number: 48043-300	
		Client: Tribal Partners	
Location: 12892 Dixie Road, Caledon		Slug Test: MW107-20 - Falling Test 1	Test Well: MW107-20
Test Conducted by: JAK			Test Date: 11/30/2020
Analysis Performed by: MBC		MW107-20 - Falling Test 1	Analysis Date: 12/1/2020
Aquifer Thickness: 1.50 m			
			
Calculation using Hvorslev			
Observation Well	Hydraulic Conductivity [m/s]		
MW107-20	4.34×10^{-7}		

			Slug Test Analysis Report		
			Project: Hydrogeological Assessment		
			Number: 48043-300		
			Client: Tribal Partners		
Location: 12892 Dixie Road, Caledon		Slug Test: MW107-20 - Rising Test 1		Test Well: MW107-20	
Test Conducted by: MBC				Test Date: 11/30/2020	
Analysis Performed by: MBC		MW107-20 - Rising Test 1		Analysis Date: 12/1/2020	
Aquifer Thickness: 1.50 m					
<div><p>Time [s]</p></div>					
Calculation using Hvorslev					
Observation Well		Hydraulic Conductivity [m/s]			
MW107-20		9.94 × 10 ⁻⁷			


Appendix E

Hydrographs


Hydrograph 1: Groundwater Elevations




Hydrograph 2: Groundwater Elevations - MW101-20




Hydrograph 3: Groundwater Elevations - MW102-20




Hydrograph 4: Groundwater Elevations - MW103-20




Hydrograph 5: Groundwater Elevations - MW105-20



Hydrograph 6: Groundwater Elevations - MW106-20



Hydrograph 7: Groundwater Elevations - MW107-20



Appendix F

Certificate of Analysis



Your Project #: 48043-300
Your C.O.C. #: 794340-29-01

Attention: John McNeil

MTE Consultants Inc
520 Bingham Centre Dr
Kitchener, ON
CANADA N2B 3X9

Report Date: 2020/12/01

Report #: R6431488

Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0V1801

Received: 2020/11/23, 17:58

Sample Matrix: Water
Samples Received: 4

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Analytical Method
Alkalinity	4	N/A	2020/11/26	CAM SOP-00448	SM 23 2320 B m
Carbonate, Bicarbonate and Hydroxide	4	N/A	2020/11/27	CAM SOP-00102	APHA 4500-CO ₂ D
Chloride by Automated Colourimetry	4	N/A	2020/11/27	CAM SOP-00463	SM 23 4500-Cl E m
Conductivity	4	N/A	2020/11/26	CAM SOP-00414	SM 23 2510 m
Dissolved Organic Carbon (DOC) (1)	2	N/A	2020/11/25	CAM SOP-00446	SM 23 5310 B m
Dissolved Organic Carbon (DOC) (1)	2	N/A	2020/11/26	CAM SOP-00446	SM 23 5310 B m
Hardness (calculated as CaCO ₃)	3	N/A	2020/11/27	CAM SOP 00102/00408/00447	SM 2340 B
Hardness (calculated as CaCO ₃)	1	N/A	2020/11/30	CAM SOP 00102/00408/00447	SM 2340 B
Lab Filtered Metals by ICPMS	2	2020/11/25	2020/11/26	CAM SOP-00447	EPA 6020B m
Dissolved Metals by ICPMS	1	N/A	2020/11/25	CAM SOP-00447	EPA 6020B m
Dissolved Metals by ICPMS	1	N/A	2020/11/30	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	3	N/A	2020/11/27		
Ion Balance (% Difference)	1	N/A	2020/11/30		
Anion and Cation Sum	3	N/A	2020/11/27		
Anion and Cation Sum	1	N/A	2020/11/30		
Total Ammonia-N	4	N/A	2020/11/26	CAM SOP-00441	USGS I-2522-90 m
Nitrate (NO ₃) and Nitrite (NO ₂) in Water (2)	3	N/A	2020/11/25	CAM SOP-00440	SM 23 4500-NO ₃ /NO ₂ B
Nitrate (NO ₃) and Nitrite (NO ₂) in Water (2)	1	N/A	2020/11/26	CAM SOP-00440	SM 23 4500-NO ₃ /NO ₂ B
pH	3	2020/11/25	2020/11/26	CAM SOP-00413	SM 4500H+ B m
pH	1	2020/11/26	2020/11/26	CAM SOP-00413	SM 4500H+ B m
Orthophosphate	4	N/A	2020/11/26	CAM SOP-00461	EPA 365.1 m
Sat. pH and Langelier Index (@ 20C)	3	N/A	2020/11/27		Auto Calc
Sat. pH and Langelier Index (@ 20C)	1	N/A	2020/11/30		Auto Calc
Sat. pH and Langelier Index (@ 4C)	3	N/A	2020/11/27		Auto Calc
Sat. pH and Langelier Index (@ 4C)	1	N/A	2020/11/30		Auto Calc
Sulphate by Automated Colourimetry	4	N/A	2020/11/27	CAM SOP-00464	EPA 375.4 m
Total Dissolved Solids (TDS calc)	3	N/A	2020/11/27		Auto Calc
Total Dissolved Solids (TDS calc)	1	N/A	2020/11/30		Auto Calc



Your Project #: 48043-300
Your C.O.C. #: 794340-29-01

Attention: John McNeil

MTE Consultants Inc
520 Bingham Centre Dr
Kitchener, ON
CANADA N2B 3X9

Report Date: 2020/12/01

Report #: R6431488

Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0V1801

Received: 2020/11/23, 17:58

Remarks:

Bureau Veritas Laboratories are accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by BV Labs are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in BV Labs profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and BV Labs in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

BV Labs liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. BV Labs has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by BV Labs, unless otherwise agreed in writing. BV Labs is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by BV Labs, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.

(2) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Ronklin Gracian, Project Manager

Email: Ronklin.Gracian@bvlabs.com

Phone# (905)817-5752

=====

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Total Cover Pages : 2

Page 2 of 16

Bureau Veritas Laboratories 6740 Campobello Road, Mississauga, Ontario, L5N 2L8 Tel: (905) 817-5700 Toll-Free: 800-563-6266 Fax: (905) 817-5777 www.bvlabs.com

Microbiology testing is conducted at 6660 Campobello Rd. Chemistry testing is conducted at 6740 Campobello Rd.



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

RCAP - COMPREHENSIVE (WATER)

BV Labs ID			OFX270			OFX270			OFX271		
Sampling Date			2020/11/23 14:42			2020/11/23 14:42			2020/11/23 15:20		
COC Number			794340-29-01			794340-29-01			794340-29-01		
	UNITS	Criteria	MW106-20	RDL	QC Batch	MW106-20 Lab-Dup	RDL	QC Batch	MW107-20	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	-	8.11	N/A	7074369				7.09	N/A	7074369
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	-	330	1.0	7073132				300	1.0	7073132
Calculated TDS	mg/L	-	420	1.0	7074372				350	1.0	7074372
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	-	5.2	1.0	7073132				4.2	1.0	7073132
Cation Sum	me/L	-	8.10	N/A	7074369				7.12	N/A	7074369
Hardness (CaCO ₃)	mg/L	-	340	1.0	7073133				320	1.0	7073133
Ion Balance (% Difference)	%	-	0.0900	N/A	7073134				0.220	N/A	7073134
Langelier Index (@ 20C)	N/A	-	1.07		7074370				0.765		7074370
Langelier Index (@ 4C)	N/A	-	0.824		7074371				0.516		7074371
Saturation pH (@ 20C)	N/A	-	7.16		7074370				7.41		7074370
Saturation pH (@ 4C)	N/A	-	7.41		7074371				7.65		7074371

Inorganics

Total Ammonia-N	mg/L	-	0.32	0.050	7077399				0.20	0.050	7077399
Conductivity	umho/cm	-	720	1.0	7076464				630	1.0	7076464
Dissolved Organic Carbon	mg/L	-	1.9	0.40	7075788	1.9	0.40	7075788	1.1	0.40	7075788
Orthophosphate (P)	mg/L	-	<0.010	0.010	7075392				0.011	0.010	7075392
pH	pH	6.5:8.5	8.23		7076476				8.17		7076476
Dissolved Sulphate (SO ₄)	mg/L	-	55	1.0	7075391				27	1.0	7075391
Alkalinity (Total as CaCO ₃)	mg/L	-	330	1.0	7076462				300	1.0	7076462
Dissolved Chloride (Cl ⁻)	ug/L	-	11000	1000	7075384				15000	1000	7075384
Nitrite (N)	mg/L	-	0.115	0.010	7075569				<0.010	0.010	7075202
Nitrate (N)	mg/L	-	0.41	0.10	7075569				<0.10	0.10	7075202
Nitrate + Nitrite (N)	mg/L	-	0.53	0.10	7075569				<0.10	0.10	7075202

Metals

Dissolved Aluminum (Al)	ug/L	-	80	4.9	7075570				<4.9	4.9	7075570
Dissolved Antimony (Sb)	ug/L	20	0.62	0.50	7075570				<0.50	0.50	7075570
Dissolved Arsenic (As)	ug/L	100	4.4	1.0	7075570				5.0	1.0	7075570
Dissolved Barium (Ba)	ug/L	-	220	2.0	7075570				120	2.0	7075570

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Criteria: Ontario Provincial Water Quality Objectives

Ref. to MOEE Water Management document dated Feb.1999

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

RCAP - COMPREHENSIVE (WATER)

BV Labs ID			OFX270			OFX270			OFX271		
Sampling Date			2020/11/23 14:42			2020/11/23 14:42			2020/11/23 15:20		
COC Number			794340-29-01			794340-29-01			794340-29-01		
	UNITS	Criteria	MW106-20	RDL	QC Batch	MW106-20 Lab-Dup	RDL	QC Batch	MW107-20	RDL	QC Batch
Dissolved Beryllium (Be)	ug/L	11	<0.40	0.40	7075570				<0.40	0.40	7075570
Dissolved Boron (B)	ug/L	200	63	10	7075570				79	10	7075570
Dissolved Cadmium (Cd)	ug/L	0.2	<0.090	0.090	7075570				<0.090	0.090	7075570
Dissolved Calcium (Ca)	ug/L	-	59000	200	7075570				35000	200	7075570
Dissolved Chromium (Cr)	ug/L	-	<5.0	5.0	7075570				<5.0	5.0	7075570
Dissolved Cobalt (Co)	ug/L	0.9	<0.50	0.50	7075570				<0.50	0.50	7075570
Dissolved Copper (Cu)	ug/L	5	1.7	0.90	7075570				<0.90	0.90	7075570
Dissolved Iron (Fe)	ug/L	300	200	100	7075570				<100	100	7075570
Dissolved Lead (Pb)	ug/L	5	<0.50	0.50	7075570				<0.50	0.50	7075570
Dissolved Magnesium (Mg)	ug/L	-	47000	50	7075570				56000	50	7075570
Dissolved Manganese (Mn)	ug/L	-	62	2.0	7075570				20	2.0	7075570
Dissolved Molybdenum (Mo)	ug/L	40	9.0	0.50	7075570				3.9	0.50	7075570
Dissolved Nickel (Ni)	ug/L	25	<1.0	1.0	7075570				<1.0	1.0	7075570
Dissolved Phosphorus (P)	ug/L	-	<100	100	7075570				<100	100	7075570
Dissolved Potassium (K)	ug/L	-	4400	200	7075570				4700	200	7075570
Dissolved Selenium (Se)	ug/L	100	<2.0	2.0	7075570				<2.0	2.0	7075570
Dissolved Silicon (Si)	ug/L	-	7500	50	7075570				7600	50	7075570
Dissolved Silver (Ag)	ug/L	0.1	<0.090	0.090	7075570				<0.090	0.090	7075570
Dissolved Sodium (Na)	ug/L	-	26000	100	7075570				15000	100	7075570
Dissolved Strontium (Sr)	ug/L	-	510	1.0	7075570				530	1.0	7075570
Dissolved Thallium (Tl)	ug/L	0.3	<0.050	0.050	7075570				<0.050	0.050	7075570
Dissolved Titanium (Ti)	ug/L	-	<5.0	5.0	7075570				<5.0	5.0	7075570
Dissolved Uranium (U)	ug/L	5	1.5	0.10	7075570				0.55	0.10	7075570
Dissolved Vanadium (V)	ug/L	6	1.7	0.50	7075570				0.64	0.50	7075570
Dissolved Zinc (Zn)	ug/L	30	<5.0	5.0	7075570				<5.0	5.0	7075570

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Criteria: Ontario Provincial Water Quality Objectives

Ref. to MOEE Water Management document dated Feb.1999



RCAP - COMPREHENSIVE (LAB FILTERED)

BV Labs ID			OFX272			OFX273		
Sampling Date			2020/11/23 12:40			2020/11/23 13:52		
COC Number			794340-29-01			794340-29-01		
	UNITS	Criteria	SG1	RDL	QC Batch	SG2	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L	-	14.1	N/A	7074369	8.49	N/A	7074369
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	-	280	1.0	7073132	270	1.0	7073132
Calculated TDS	mg/L	-	790	1.0	7074372	460	1.0	7074372
Carb. Alkalinity (calc. as CaCO3)	mg/L	-	3.8	1.0	7073132	4.0	1.0	7073132
Cation Sum	me/L	-	14.3	N/A	7074369	8.45	N/A	7074369
Hardness (CaCO3)	mg/L	-	390	1.0	7073133	350	1.0	7073133
Ion Balance (% Difference)	%	-	0.810	N/A	7073134	0.220	N/A	7073134
Langelier Index (@ 20C)	N/A	-	1.17		7074370	1.19		7074370
Langelier Index (@ 4C)	N/A	-	0.924		7074371	0.943		7074371
Saturation pH (@ 20C)	N/A	-	6.99		7074370	7.01		7074370
Saturation pH (@ 4C)	N/A	-	7.24		7074371	7.25		7074371
Inorganics								
Total Ammonia-N	mg/L	-	<0.050	0.050	7077399	<0.050	0.050	7077399
Conductivity	umho/cm	-	1500	1.0	7076464	820	1.0	7077732
Dissolved Organic Carbon	mg/L	-	8.6	0.40	7075788	4.9	0.40	7075735
Orthophosphate (P)	mg/L	-	0.11	0.010	7075392	0.035	0.010	7075392
pH	pH	6.5:8.5	8.16		7076476	8.20		7077731
Dissolved Sulphate (SO4)	mg/L	-	49	1.0	7075391	41	1.0	7075391
Alkalinity (Total as CaCO3)	mg/L	-	280	1.0	7076462	270	1.0	7077724
Dissolved Chloride (Cl-)	ug/L	-	260000	3000	7075384	75000	1000	7075384
Nitrite (N)	mg/L	-	<0.010	0.010	7075202	<0.010	0.010	7075202
Nitrate (N)	mg/L	-	<0.10	0.10	7075202	0.37	0.10	7075202
Nitrate + Nitrite (N)	mg/L	-	<0.10	0.10	7075202	0.37	0.10	7075202
Metals								
Dissolved Aluminum (Al)	ug/L	-	<4.9	4.9	7076206	7.1	4.9	7076206
Dissolved Antimony (Sb)	ug/L	20	<0.50	0.50	7076206	<0.50	0.50	7076206
Dissolved Arsenic (As)	ug/L	100	<1.0	1.0	7076206	<1.0	1.0	7076206
Dissolved Barium (Ba)	ug/L	-	53	2.0	7076206	53	2.0	7076206
Dissolved Beryllium (Be)	ug/L	11	<0.40	0.40	7076206	<0.40	0.40	7076206
No Fill	No Exceedance							
Grey	Exceeds 1 criteria policy/level							
Black	Exceeds both criteria/levels							
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
Criteria: Ontario Provincial Water Quality Objectives								
Ref. to MOEE Water Management document dated Feb.1999								
N/A = Not Applicable								



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

RCAP - COMPREHENSIVE (LAB FILTERED)

BV Labs ID			OFX272			OFX273		
Sampling Date			2020/11/23 12:40			2020/11/23 13:52		
COC Number			794340-29-01			794340-29-01		
	UNITS	Criteria	SG1	RDL	QC Batch	SG2	RDL	QC Batch
Dissolved Boron (B)	ug/L	200	28	10	7076206	17	10	7076206
Dissolved Cadmium (Cd)	ug/L	0.2	<0.090	0.090	7076206	<0.090	0.090	7076206
Dissolved Calcium (Ca)	ug/L	-	120000	200	7076206	100000	200	7076206
Dissolved Chromium (Cr)	ug/L	-	<5.0	5.0	7076206	<5.0	5.0	7076206
Dissolved Cobalt (Co)	ug/L	0.9	<0.50	0.50	7076206	<0.50	0.50	7076206
Dissolved Copper (Cu)	ug/L	5	2.4	0.90	7076206	<0.90	0.90	7076206
Dissolved Iron (Fe)	ug/L	300	<100	100	7076206	<100	100	7076206
Dissolved Lead (Pb)	ug/L	5	<0.50	0.50	7076206	<0.50	0.50	7076206
Dissolved Magnesium (Mg)	ug/L	-	23000	50	7076206	21000	50	7076206
Dissolved Manganese (Mn)	ug/L	-	33	2.0	7076206	51	2.0	7076206
Dissolved Molybdenum (Mo)	ug/L	40	<0.50	0.50	7076206	<0.50	0.50	7076206
Dissolved Nickel (Ni)	ug/L	25	<1.0	1.0	7076206	<1.0	1.0	7076206
Dissolved Phosphorus (P)	ug/L	-	180	100	7076206	<100	100	7076206
Dissolved Potassium (K)	ug/L	-	9900	200	7076206	3300	200	7076206
Dissolved Selenium (Se)	ug/L	100	<2.0	2.0	7076206	<2.0	2.0	7076206
Dissolved Silicon (Si)	ug/L	-	4900	50	7076206	5300	50	7076206
Dissolved Silver (Ag)	ug/L	0.1	<0.090	0.090	7076206	<0.090	0.090	7076206
Dissolved Sodium (Na)	ug/L	-	140000	100	7076206	33000	100	7076206
Dissolved Strontium (Sr)	ug/L	-	310	1.0	7076206	250	1.0	7076206
Dissolved Thallium (Tl)	ug/L	0.3	<0.050	0.050	7076206	<0.050	0.050	7076206
Dissolved Titanium (Ti)	ug/L	-	<5.0	5.0	7076206	<5.0	5.0	7076206
Dissolved Uranium (U)	ug/L	5	1.6	0.10	7076206	0.60	0.10	7076206
Dissolved Vanadium (V)	ug/L	6	<0.50	0.50	7076206	<0.50	0.50	7076206
Dissolved Zinc (Zn)	ug/L	30	<5.0	5.0	7076206	<5.0	5.0	7076206
No Fill	No Exceedance							
Grey	Exceeds 1 criteria policy/level							
Black	Exceeds both criteria/levels							
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
Criteria: Ontario Provincial Water Quality Objectives								
Ref. to MOEE Water Management document dated Feb.1999								



BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

TEST SUMMARY

BV Labs ID: OFX270
Sample ID: MW106-20
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7076462	N/A	2020/11/26	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7073132	N/A	2020/11/27	Automated Statchk
Chloride by Automated Colourimetry	KONE	7075384	N/A	2020/11/27	Deonarine Ramnarine
Conductivity	AT	7076464	N/A	2020/11/26	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7075788	N/A	2020/11/25	Nimarta Singh
Hardness (calculated as CaCO ₃)		7073133	N/A	2020/11/30	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7075570	N/A	2020/11/30	Azita Fazaeli
Ion Balance (% Difference)	CALC	7073134	N/A	2020/11/30	Automated Statchk
Anion and Cation Sum	CALC	7074369	N/A	2020/11/30	Automated Statchk
Total Ammonia-N	LACH/NH ₄	7077399	N/A	2020/11/26	Amanpreet Sappal
Nitrate (NO ₃) and Nitrite (NO ₂) in Water	LACH	7075569	N/A	2020/11/26	Chandra Nandlal
pH	AT	7076476	2020/11/25	2020/11/26	Surinder Rai
Orthophosphate	KONE	7075392	N/A	2020/11/26	Alina Dobreanu
Sat. pH and Langelier Index (@ 20C)	CALC	7074370	N/A	2020/11/30	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7074371	N/A	2020/11/30	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7075391	N/A	2020/11/27	Deonarine Ramnarine
Total Dissolved Solids (TDS calc)	CALC	7074372	N/A	2020/11/30	Automated Statchk

BV Labs ID: OFX270 Dup
Sample ID: MW106-20
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7075788	N/A	2020/11/25	Nimarta Singh

BV Labs ID: OFX271
Sample ID: MW107-20
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7076462	N/A	2020/11/26	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7073132	N/A	2020/11/27	Automated Statchk
Chloride by Automated Colourimetry	KONE	7075384	N/A	2020/11/27	Deonarine Ramnarine
Conductivity	AT	7076464	N/A	2020/11/26	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7075788	N/A	2020/11/26	Nimarta Singh
Hardness (calculated as CaCO ₃)		7073133	N/A	2020/11/27	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7075570	N/A	2020/11/25	Azita Fazaeli
Ion Balance (% Difference)	CALC	7073134	N/A	2020/11/27	Automated Statchk
Anion and Cation Sum	CALC	7074369	N/A	2020/11/27	Automated Statchk
Total Ammonia-N	LACH/NH ₄	7077399	N/A	2020/11/26	Amanpreet Sappal
Nitrate (NO ₃) and Nitrite (NO ₂) in Water	LACH	7075202	N/A	2020/11/25	Chandra Nandlal
pH	AT	7076476	2020/11/25	2020/11/26	Surinder Rai
Orthophosphate	KONE	7075392	N/A	2020/11/26	Alina Dobreanu
Sat. pH and Langelier Index (@ 20C)	CALC	7074370	N/A	2020/11/27	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7074371	N/A	2020/11/27	Automated Statchk



BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

TEST SUMMARY

BV Labs ID: OFX271
Sample ID: MW107-20
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphate by Automated Colourimetry	KONE	7075391	N/A	2020/11/27	Deonarine Ramnarine
Total Dissolved Solids (TDS calc)	CALC	7074372	N/A	2020/11/27	Automated Statchk

BV Labs ID: OFX272
Sample ID: SG1
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7076462	N/A	2020/11/26	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7073132	N/A	2020/11/27	Automated Statchk
Chloride by Automated Colourimetry	KONE	7075384	N/A	2020/11/27	Deonarine Ramnarine
Conductivity	AT	7076464	N/A	2020/11/26	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7075788	N/A	2020/11/26	Nimarta Singh
Hardness (calculated as CaCO ₃)		7073133	N/A	2020/11/27	Automated Statchk
Lab Filtered Metals by ICPMS	ICP/MS	7076206	2020/11/25	2020/11/26	Arefa Dabhad
Ion Balance (% Difference)	CALC	7073134	N/A	2020/11/27	Automated Statchk
Anion and Cation Sum	CALC	7074369	N/A	2020/11/27	Automated Statchk
Total Ammonia-N	LACH/NH ₄	7077399	N/A	2020/11/26	Amanpreet Sappal
Nitrate (NO ₃) and Nitrite (NO ₂) in Water	LACH	7075202	N/A	2020/11/25	Chandra Nandlal
pH	AT	7076476	2020/11/25	2020/11/26	Surinder Rai
Orthophosphate	KONE	7075392	N/A	2020/11/26	Alina Dobreanu
Sat. pH and Langelier Index (@ 20C)	CALC	7074370	N/A	2020/11/27	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7074371	N/A	2020/11/27	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7075391	N/A	2020/11/27	Deonarine Ramnarine
Total Dissolved Solids (TDS calc)	CALC	7074372	N/A	2020/11/27	Automated Statchk

BV Labs ID: OFX273
Sample ID: SG2
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7077724	N/A	2020/11/26	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7073132	N/A	2020/11/27	Automated Statchk
Chloride by Automated Colourimetry	KONE	7075384	N/A	2020/11/27	Deonarine Ramnarine
Conductivity	AT	7077732	N/A	2020/11/26	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7075735	N/A	2020/11/25	Nimarta Singh
Hardness (calculated as CaCO ₃)		7073133	N/A	2020/11/27	Automated Statchk
Lab Filtered Metals by ICPMS	ICP/MS	7076206	2020/11/25	2020/11/26	Arefa Dabhad
Ion Balance (% Difference)	CALC	7073134	N/A	2020/11/27	Automated Statchk
Anion and Cation Sum	CALC	7074369	N/A	2020/11/27	Automated Statchk
Total Ammonia-N	LACH/NH ₄	7077399	N/A	2020/11/26	Amanpreet Sappal
Nitrate (NO ₃) and Nitrite (NO ₂) in Water	LACH	7075202	N/A	2020/11/25	Chandra Nandlal
pH	AT	7077731	2020/11/26	2020/11/26	Surinder Rai
Orthophosphate	KONE	7075392	N/A	2020/11/26	Alina Dobreanu
Sat. pH and Langelier Index (@ 20C)	CALC	7074370	N/A	2020/11/27	Automated Statchk



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

TEST SUMMARY

BV Labs ID: OFX273
Sample ID: SG2
Matrix: Water

Collected: 2020/11/23
Shipped:
Received: 2020/11/23

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 4C)	CALC	7074371	N/A	2020/11/27	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7075391	N/A	2020/11/27	Deonarine Ramnarine
Total Dissolved Solids (TDS calc)	CALC	7074372	N/A	2020/11/27	Automated Statchk



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	2.7°C
-----------	-------

Sample OFX271 [MW107-20] : ortho-Phosphate > Total Phosphorus: Both values fall within the method uncertainty for duplicates and are likely equivalent.

Sample OFX273 [SG2] : ortho-Phosphate > Total Phosphorus: Both values fall within the method uncertainty for duplicates and are likely equivalent.

Results relate only to the items tested.

BUREAU
VERITAS

BV Labs Job #: COV1801

Report Date: 2020/12/01

QUALITY ASSURANCE REPORT

MTE Consultants Inc

Client Project #: 48043-300

Sampler Initials: MC

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
7075202	Nitrate (N)	2020/11/25	90	80 - 120	92	80 - 120	<0.10	mg/L	2.9	20
7075202	Nitrite (N)	2020/11/25	102	80 - 120	105	80 - 120	<0.010	mg/L	NC	20
7075384	Dissolved Chloride (Cl-)	2020/11/27	NC	80 - 120	101	80 - 120	<1000	ug/L	1.3	20
7075391	Dissolved Sulphate (SO4)	2020/11/27	NC	75 - 125	104	80 - 120	<1.0	mg/L	1.2	20
7075392	Orthophosphate (P)	2020/11/26	102	75 - 125	100	80 - 120	<0.010	mg/L	NC	25
7075569	Nitrate (N)	2020/11/26	94	80 - 120	96	80 - 120	<0.10	mg/L	2.2	20
7075569	Nitrite (N)	2020/11/26	101	80 - 120	104	80 - 120	<0.010	mg/L		
7075570	Dissolved Aluminum (Al)	2020/11/25	102	80 - 120	103	80 - 120	<4.9	ug/L		
7075570	Dissolved Antimony (Sb)	2020/11/25	104	80 - 120	101	80 - 120	<0.50	ug/L	NC	20
7075570	Dissolved Arsenic (As)	2020/11/25	98	80 - 120	98	80 - 120	<1.0	ug/L	0.93	20
7075570	Dissolved Barium (Ba)	2020/11/25	99	80 - 120	96	80 - 120	<2.0	ug/L	4.3	20
7075570	Dissolved Beryllium (Be)	2020/11/25	96	80 - 120	99	80 - 120	<0.40	ug/L	NC	20
7075570	Dissolved Boron (B)	2020/11/25	102	80 - 120	99	80 - 120	<10	ug/L	2.7	20
7075570	Dissolved Cadmium (Cd)	2020/11/25	98	80 - 120	100	80 - 120	<0.090	ug/L	NC	20
7075570	Dissolved Calcium (Ca)	2020/11/25	NC	80 - 120	100	80 - 120	<200	ug/L		
7075570	Dissolved Chromium (Cr)	2020/11/25	95	80 - 120	99	80 - 120	<5.0	ug/L	NC	20
7075570	Dissolved Cobalt (Co)	2020/11/25	93	80 - 120	99	80 - 120	<0.50	ug/L	NC	20
7075570	Dissolved Copper (Cu)	2020/11/25	96	80 - 120	99	80 - 120	<0.90	ug/L	5.5	20
7075570	Dissolved Iron (Fe)	2020/11/25	96	80 - 120	98	80 - 120	<100	ug/L		
7075570	Dissolved Lead (Pb)	2020/11/25	91	80 - 120	96	80 - 120	<0.50	ug/L	NC	20
7075570	Dissolved Magnesium (Mg)	2020/11/25	NC	80 - 120	99	80 - 120	<50	ug/L		
7075570	Dissolved Manganese (Mn)	2020/11/25	96	80 - 120	99	80 - 120	<2.0	ug/L		
7075570	Dissolved Molybdenum (Mo)	2020/11/25	102	80 - 120	100	80 - 120	<0.50	ug/L	0.26	20
7075570	Dissolved Nickel (Ni)	2020/11/25	91	80 - 120	98	80 - 120	<1.0	ug/L	NC	20
7075570	Dissolved Phosphorus (P)	2020/11/25	106	80 - 120	110	80 - 120	<100	ug/L		
7075570	Dissolved Potassium (K)	2020/11/25	99	80 - 120	100	80 - 120	<200	ug/L		
7075570	Dissolved Selenium (Se)	2020/11/25	97	80 - 120	101	80 - 120	<2.0	ug/L	NC	20
7075570	Dissolved Silicon (Si)	2020/11/25	104	80 - 120	98	80 - 120	<50	ug/L		
7075570	Dissolved Silver (Ag)	2020/11/25	66 (1)	80 - 120	98	80 - 120	<0.090	ug/L	NC	20
7075570	Dissolved Sodium (Na)	2020/11/25	NC	80 - 120	100	80 - 120	<100	ug/L	0.51	20
7075570	Dissolved Strontium (Sr)	2020/11/25	97	80 - 120	98	80 - 120	<1.0	ug/L		



**BUREAU
VERITAS**

BV Labs Job #: COV1801

Report Date: 2020/12/01

QUALITY ASSURANCE REPORT(CONT'D)

MTE Consultants Inc

Client Project #: 48043-300

Sampler Initials: MC

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
7075570	Dissolved Thallium (Tl)	2020/11/25	92	80 - 120	97	80 - 120	<0.050	ug/L	NC	20
7075570	Dissolved Titanium (Ti)	2020/11/25	104	80 - 120	95	80 - 120	<5.0	ug/L		
7075570	Dissolved Uranium (U)	2020/11/25	100	80 - 120	100	80 - 120	<0.10	ug/L	NC	20
7075570	Dissolved Vanadium (V)	2020/11/25	98	80 - 120	99	80 - 120	<0.50	ug/L	NC	20
7075570	Dissolved Zinc (Zn)	2020/11/25	92	80 - 120	100	80 - 120	<5.0	ug/L	NC	20
7075735	Dissolved Organic Carbon	2020/11/25	99	80 - 120	98	80 - 120	<0.40	mg/L	1.2	20
7075788	Dissolved Organic Carbon	2020/11/25	99	80 - 120	98	80 - 120	<0.40	mg/L	0.89	20
7076206	Dissolved Aluminum (Al)	2020/11/26	96	80 - 120	99	80 - 120	<4.9	ug/L	NC	20
7076206	Dissolved Antimony (Sb)	2020/11/26	101	80 - 120	102	80 - 120	<0.50	ug/L	NC	20
7076206	Dissolved Arsenic (As)	2020/11/26	95	80 - 120	98	80 - 120	<1.0	ug/L	2.2	20
7076206	Dissolved Barium (Ba)	2020/11/26	96	80 - 120	100	80 - 120	<2.0	ug/L	2.5	20
7076206	Dissolved Beryllium (Be)	2020/11/26	93	80 - 120	95	80 - 120	<0.40	ug/L	NC	20
7076206	Dissolved Boron (B)	2020/11/26	89	80 - 120	92	80 - 120	<10	ug/L	1.6	20
7076206	Dissolved Cadmium (Cd)	2020/11/26	97	80 - 120	99	80 - 120	<0.090	ug/L	NC	20
7076206	Dissolved Calcium (Ca)	2020/11/26	NC	80 - 120	98	80 - 120	<200	ug/L	1.3	20
7076206	Dissolved Chromium (Cr)	2020/11/26	90	80 - 120	93	80 - 120	<5.0	ug/L	NC	20
7076206	Dissolved Cobalt (Co)	2020/11/26	91	80 - 120	96	80 - 120	<0.50	ug/L	NC	20
7076206	Dissolved Copper (Cu)	2020/11/26	91	80 - 120	94	80 - 120	<0.90	ug/L	NC	20
7076206	Dissolved Iron (Fe)	2020/11/26	94	80 - 120	96	80 - 120	<100	ug/L	NC	20
7076206	Dissolved Lead (Pb)	2020/11/26	94	80 - 120	97	80 - 120	<0.50	ug/L	NC	20
7076206	Dissolved Magnesium (Mg)	2020/11/26	92	80 - 120	100	80 - 120	<50	ug/L	1.6	20
7076206	Dissolved Manganese (Mn)	2020/11/26	93	80 - 120	95	80 - 120	<2.0	ug/L	NC	20
7076206	Dissolved Molybdenum (Mo)	2020/11/26	94	80 - 120	95	80 - 120	<0.50	ug/L	0.60	20
7076206	Dissolved Nickel (Ni)	2020/11/26	89	80 - 120	93	80 - 120	<1.0	ug/L	NC	20
7076206	Dissolved Phosphorus (P)	2020/11/26	97	80 - 120	107	80 - 120	<100	ug/L	NC	20
7076206	Dissolved Potassium (K)	2020/11/26	100	80 - 120	102	80 - 120	<200	ug/L	1.4	20
7076206	Dissolved Selenium (Se)	2020/11/26	94	80 - 120	96	80 - 120	<2.0	ug/L	NC	20
7076206	Dissolved Silicon (Si)	2020/11/26	98	80 - 120	98	80 - 120	<50	ug/L	0.49	20
7076206	Dissolved Silver (Ag)	2020/11/26	93	80 - 120	96	80 - 120	<0.090	ug/L	NC	20
7076206	Dissolved Sodium (Na)	2020/11/26	92	80 - 120	98	80 - 120	<100	ug/L	1.4	20
7076206	Dissolved Strontium (Sr)	2020/11/26	94	80 - 120	98	80 - 120	<1.0	ug/L	2.6	20



BUREAU
VERITAS

BV Labs Job #: COV1801

Report Date: 2020/12/01

QUALITY ASSURANCE REPORT(CONT'D)

MTE Consultants Inc

Client Project #: 48043-300

Sampler Initials: MC

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
7076206	Dissolved Thallium (Tl)	2020/11/26	92	80 - 120	98	80 - 120	<0.050	ug/L	NC	20
7076206	Dissolved Titanium (Ti)	2020/11/26	94	80 - 120	96	80 - 120	<5.0	ug/L	NC	20
7076206	Dissolved Uranium (U)	2020/11/26	93	80 - 120	97	80 - 120	<0.10	ug/L	2.0	20
7076206	Dissolved Vanadium (V)	2020/11/26	91	80 - 120	94	80 - 120	<0.50	ug/L	NC	20
7076206	Dissolved Zinc (Zn)	2020/11/26	93	80 - 120	95	80 - 120	<5.0	ug/L	NC	20
7076462	Alkalinity (Total as CaCO ₃)	2020/11/26			96	85 - 115	<1.0	mg/L	0.38	20
7076464	Conductivity	2020/11/26			101	85 - 115	<1.0	umho/cm	0.36	25
7076476	pH	2020/11/26			101	98 - 103			0.80	N/A
7077399	Total Ammonia-N	2020/11/26	99	75 - 125	98	80 - 120	<0.050	mg/L	3.7	20
7077724	Alkalinity (Total as CaCO ₃)	2020/11/26			96	85 - 115	<1.0	mg/L	1.6	20
7077731	pH	2020/11/26			101	98 - 103			0.36	N/A
7077732	Conductivity	2020/11/26			102	85 - 115	<1.0	umho/cm	0.58	25

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

(1) Recovery or RPD for this parameter is outside control limits. The overall quality control for this analysis meets acceptability criteria.



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

Brad Newman, B.Sc., C.Chem., Scientific Service Specialist

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



INVOICE TO:		REPORT TO:		PROJECT INFORMATION:		Laboratory Use Only:	
Company Name: #6868 MTE Consultants Inc		Company Name: MTE Consultants		Quotation #: B90004		BV Labs Job #:	
Attention: Accounts Payable		Attention: Gehin Charabegian John McNeil		P.O. #:		Bottle Order #:	
Address: 520 Bingham Centre Dr Kitchener ON N2B 3X9		Address: 123 St. George St, London, ON		Project: 48043-300		794340	
Tel: (519) 743-6500 Fax: (519) 743-6513		Tel: (905) 639-2552 Ext. 2430 Fax: mcastello@mte85.com		Project Name:		COC #:	
Email: accounting@mte85.com		Email: ocharabegian@mte85.com jmcneil@mte85.com		Requested By: Mackenzie Gestel		Project Manager:	
						Ronklin Gracian	
MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE BV LABS DRINKING WATER CHAIN OF CUSTODY				Turnaround Time (TAT) Required: Please provide advance notice for rush projects			
Regulation 153 (2011)		Other Regulations		Special Instructions		Regular (Standard) TAT: (will be applied if Rush TAT is not specified): Standard TAT = 5-7 Working days for most tests.	
<input type="checkbox"/> Table 1 <input type="checkbox"/> Res/Park <input type="checkbox"/> Medium/Fine <input type="checkbox"/> Table 2 <input type="checkbox"/> Ind/Comm <input type="checkbox"/> Coarse <input type="checkbox"/> Table 3 <input type="checkbox"/> Agri/Other <input type="checkbox"/> For RSC <input type="checkbox"/> Table _____		<input type="checkbox"/> CCME <input type="checkbox"/> Sanitary Sewer Bylaw <input type="checkbox"/> Reg 558 <input type="checkbox"/> Storm Sewer Bylaw <input type="checkbox"/> MISA Municipality _____ <input checked="" type="checkbox"/> PWQO <input type="checkbox"/> Reg 406 Table <input type="checkbox"/> Other *Lower DL				Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details. Job Specific Rush TAT (if applies to entire submission) Date Required: _____ Time Required: _____ Rush Confirmation Number: _____ (call lab for #)	
Include Criteria on Certificate of Analysis (Y/N)? <input checked="" type="checkbox"/>							
	Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix	Field Filtered (please circle): Metals: Hg / Cr / V	
1		MW106-20	20/11/23	14:42	GW	Yes	
2		MW107-20	↓	15:20	↓	Yes	
3		SG1	↓	12:40	↓	No	
4		SG2	↓	13:52	↓	No	
5							
6							
7							
8							
9							
10							
* RELINQUISHED BY: (Signature/Print) mf C/O Mackenzie Gestel				Date: (YY/MM/DD) 20/11/23		Time 16:15	
RECEIVED BY: (Signature/Print) [Signature]				Date: (YY/MM/DD) 20/11/23		Time 17:58	
				# jars used and not submitted		Laboratory Use Only	
						Time Sensitive	
						Temperature (°C) on Receipt 22.4	
						Custody Seal Present Intact	
						Yes No	
						White: BV Labs Yellow: Client	
* UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO BV LABS' STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.BVLABS.COM/TERMS-AND-CONDITIONS. * IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS. * SAMPLES RECEIVED FOR PRESERVATION: HOLD TIME AND BACKLOG INFORMATION CAN BE VIEWED AT WWW.BVLABS.COM/RESOURCES/CHAIN-OF-CUSTODY-FORMS.							



BUREAU
VERITAS

BV Labs Job #: COV1801
Report Date: 2020/12/01

MTE Consultants Inc
Client Project #: 48043-300
Sampler Initials: MC

Exceedance Summary Table – Prov. Water Quality Obj.
Result Exceedances

Sample ID	BV Labs ID	Parameter	Criteria	Result	DL	UNITS
No Exceedances						
The exceedance summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.						

Appendix G

Water Balance

Parameter		Units	Pre-Development								Post-Development (Unmitigated)															
Catchment	-		100		101			102			103		1000		1100		1200		1300	1400	1500	1600		1700		
Area	ha		16.25		18.62			36.65			7.33		20.28		16.7		14.36		8.21	3.0	0.7	13.8		1.8		
Average Annual Precipitation	mm		786		786			786			786		786		786		786		786	786	786	786		786		
% Impervious	%		0%		0%			0%			0%		98.4%		97.6%		97.6%		100%	0.0%	0.0%	0.0%		0.0%		
Surface/Ground Cover	-		Urban Lawn/Crop	Pasture and Shrubs	Urban Lawn/Crop	Wooded	Wetland	Crop	Wooded	Pond	Crop	Impervious	Lined SWM Ponds (2)	Impervious	Lined SWM Pond	Impervious	Lined SWM Pond	Impervious	Pasture and Shrubs	Wetland	Woodlot	Urban Lawn (Buffer)	Pond	Pasture and Shrubs		
Simplified Soil Description (Native)	-		Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	-	-	-	-	-	-	-	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till	Glacial Till		
Hydrologic Soil Group	-		CD	CD	CD	CD	CD	CD	CD	CD	CD	-	-	-	-	-	-	-	CD	CD	CD	CD	CD	CD		
Area	ha		13.25	3.00	15.21	2.71	0.70	30.08	6.18	0.39	7.33	19.00	1.28	15.13	1.57	13.16	1.20	8.21	3.00	0.70	8.89	4.52	0.39	1.80		
	m ²		132,500	30,000	152,100	27,100	7,000	300,800	61,800	3,900	73,300	190,000	12,800	151,300	15,700	131,600	12,000	82,100	30,000	7,000	88,900	45,200	3,900	18,000		
Precipitation, P	m/year		0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786	0.786		
Evapotranspiration, ET	m/year		0.444	0.457	0.444	0.460	0.460	0.444	0.460	0.510	0.444	0.050	0.510	0.050	0.510	0.050	0.510	0.050	0.457	0.460	0.460	0.444	0.510	0.457		
Water Surplus, WS	m/year		0.342	0.329	0.342	0.326	0.326	0.342	0.326	0.276	0.342	0.736	0.276	0.736	0.276	0.736	0.276	0.736	0.329	0.326	0.326	0.342	0.276	0.329		
Ground Cover Factor	-		0.10	0.15	0.10	0.20	0.15	0.10	0.20	0.00	0.10	-	-	-	-	-	-	-	0.15	0.15	0.20	0.10	0.00	0.15		
Soils Factor	-		0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	-	-	-	-	-	-	-	0.20	0.20	0.20	0.20	0.20	0.20		
Topography Factor	-		0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	-	-	-	-	-	-	-	0.20	0.20	0.20	0.30	0.20	0.10		
Infiltration Factor (sum)	-		0.50	0.55	0.50	0.60	0.55	0.50	0.60	0.40	0.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.55	0.55	0.60	0.60	0.40	0.45		
Infiltration, I	m/year		0.171	0.181	0.171	0.196	0.179	0.171	0.196	0.111	0.171	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.181	0.179	0.196	0.205	0.111	0.148		
Runoff, RO	m/year		0.171	0.148	0.171	0.130	0.147	0.171	0.130	0.166	0.171	0.736	0.276	0.736	0.276	0.736	0.276	0.736	0.148	0.147	0.130	0.137	0.166	0.181		
Annual Volumes																										
Precipitation, P	m ³ /year		104,145	23,580	119,551	21,301	5,502	236,429	48,575	3,065	57,614	149,340	10,061	118,922	12,340	103,438	9,432	64,531	23,580	5,502	69,875	35,527	3,065	14,148		
Evapotranspiration, ET	m ³ /year		58,831	13,696	67,533	12,463	3,219	133,557	28,421	1,987	32,546	9,500	6,522	7,565	7,999	6,580	6,114	4,105	13,696	3,219	40,885	20,069	1,987	8,218		
Infiltration, I	m ³ /year		22,657	5,436	26,009	5,302	1,256	51,436	12,092	431	12,534	0	0	0	0	0	0	0	5,436	1,256	17,395	9,275	431	2,669		
Runoff, RO	m ³ /year		22,657	4,448	26,009	3,535	1,027	51,436	8,061	647	12,534	139,840	3,539	111,357	4,341	96,858	3,318	60,426	4,448	1,027	11,596	6,183	647	3,262		
Catchment Totals																										
Precipitation, P	m ³ /year		127,725			146,353			288,069			57,614		159,401		131,262		112,870		64,531	23,580	5,502	108,468		14,148	
Evapotranspiration, ET	m ³ /year		72,527			83,216			163,966			32,546		16,022		15,564		12,694		4,105	13,696	3,219	62,941		8,218	
Infiltration, I	m ³ /year		28,093			32,567			63,959			12,534		0		0		0		0	5,436	1,256	27,101		2,669	
Runoff, RO	m ³ /year		27,105			30,571			60,144			12,534		143,379		115,698		100,176		60,426	4,448	1,027	18,427		3,262	
Site Totals																										
Precipitation, P	m ³ /year		619,761								619,761															
Evapotranspiration, ET	m ³ /year		352,254								136,459															
Infiltration, I	m ³ /year		137,153								36,461															
Runoff, RO	m ³ /year		130,354								446,841															

Appendix H

Natural Environment Plans

Excerpt from WSP (2021)



