TOWN OF CALEDON
PLANNING
RECEIVED
Nov.29, 2021



ASPHALT STEP JOINT DETAIL
SCALE: NTS

STORM SEWER

1. STORM SEWER PIPES 300mm DIA. SHALL BE PVC SDR 35 CONFORMING TO C.S.A. SPECIFICATION B182.2–M1990 AND B182.4–M–992 OR LATEST REVISION THEREOF. STORM SEWER PIPES 300mm DIA. TO 450mm DIA. SHALL BE C.S.A. B182.4 RIBBED PVC. STORM SEWER PIPES LARGER THAN 450mm DIA. SHALL BE REINFORCED CONCRETE CONFORMING TO C.S.A. SPECIFICATION A57.2–M1982 OR LATEST REVISION THEREOF. PIPE JOINTS SHALL BE BY MEANS OF APPROVED RUBBER GASKETS CONFORMING TO C.S.A. SPECIFICATION A257.3–M1982 OR LATEST.
2. SEWER BEDDING AND BACKFILL FOR STORM SEWER SHALL BE AS PER O.P.S.D. 802.030 CLASS "B" WITH GRANULAR "A" BEDDING FOR CONCRETE PIPE AND 802.010 FOR PVC PIPE.
3. STORM MANHOLES TO BE 1200ø AS PER O.P.S.D. 701.010, 701.012, 701.012, 701.013. UNLESS NOTED OTHERWISE. FRAME AND COVER AS PER O.P.S.D. 401.010 TYPE "B". SAFETY PLATFORMS AS PER O.P.S.D. 404.020 AND SHALL BE INSTALLED IN MANHOLES WHERE DEPTH EXCEEDS 5.0M. STORM MANHOLE BENCHING TO BE TO OBVERT OF PIPE AND AS PER O.P.S.D. 701.021, MINIMUM 230mm IN WIDTH AND TO CROWN OR AS SPECIFIED ON DRAWINGS.
4. STREET CATCHBASINS SHALL BE AS PER O.P.S.D. 705.020 (DOUBLE) AND 705.010 (SINGLE) WITH FRAME AND GRATES AS PER O.P.S.D. 400.11 CATCHBASIN CONNECTIONS SHALL BE AS PER O.P.S.D. 708.03 SINGLE CB LEAD 200mm DIA. DOUBLE CB LEAD 250mm DIA. CATCHBASIN LEADS SHALL BE PVC SDR–35, CONFORMING TO C.S.A. SPECIFICATION B182.2 AND B182.4 OR LATEST REVISION THEREOF.
5. REAR LOT CATCHBASIN FRAME AND GRATE SHALL BE AS TOWN STANDARDS, LEADS SHALL BE CONCRETE ENCASED TO MAIN SEWER.
6. ADJUSTMENTS UNITS FOR CATCHBASINS AND MANHOLES SHALL BE AS PER TOWN STANDARDS
7. CONCRETE HEADWALLS TO BE AS SPECIFIED ON DRAWINGS WHERE THE FINISHED GRADE DIFFERENCE BETWEEN THE TOP OF HEADWALL AND PIPE INVERT IS GREATER THAN OR EQUAL TO 1.2m, HANDRAILS CONFORMING TO O.P.S.D. 915.01 SHALL BE INSTALLED ON THE HEADWALL AND WINGWALLS OR AS DIRECTED BY THE ENGINEER.
8. ORIFICE CONTROL PLATES SHALL BE NON–REMOVABLE& BOLTED TO STRUCTURES; MIN. SIZE OF ORIFICE TO BE 75mm DIA.) PIPE REDUCERS MAY BE USED INSTEAD OF ORIFICE PLATES TO CONTROL FLOW. REFER TO SERVICING DRAWINGS FOR SIZES AND LOCATIONS.
9. DROP STRUCTURES AS PER TOWN STANDARDS.
10. SUBDRAINS, CONFORMING TO OPSS 405, SHALL BE CONTINUOS BETWEEN CATCHBASINS AND SHALL BE 150mm DIA. PERFORATED WRAPPED IN FILTER FABRIC.

WATERMAIN

1. WATERMAINS 150mm ID. TO 300mm DIA. SHALL BE PVC CL. 150 (DR–18) CONFORMING TO A.W.W.A. C900–89 & C.S.A. CAN3 B137.3–M1986 OR LATEST REVISION THEREOF WITH GASKETED JOINTS AND BE PROVIDED WITH 12 GAUGE SOLID COPPER TRACER WIRE.
2. UNLESS OTHERWISE INDICATED, WATER SERVICE CONNECTIONS (RESIDENTIAL) SHALL BE 20mm TYPE "K" COPPER INSTALLED AS PER O.P.S.D. 1104.01. RUBBER INDUSTRIES LTD. SADDLE NO. 266 OR APPROVED EQUAL SHALL BE USED FOR CONNECTIONS TO WATERMAIN. ALL WATER SERVICES SHALL BE INSTALLED 1.2m FROM STREET LINE WITHIN THE MUNICIPAL ROAD ALLOWANCE. WATERBOXES TO BE OF THE BALL TYPE WATERBOXES NOT TO BE LOCATED IN DRIVEWAYS.
3. A MIN. HORIZONTAL SEPARATION OF 2.5m AND A MIN. VERTICAL SEPARATION OF 0.30m BETWEEN WATERMAINS AND SEWERS MUST BE MAINTAINED. IF WATERMAIN IS ABOVE SEWER OR 0.50m IF SEWER IS ABOVE WATERMAIN, OUTSIDE TO OUTSIDE OF PIPES.
4. WTAERMAIN BEDDING AND EMBEDMENT MATERIAL SHALL BE GRANULAR AS PER O.P.S.D. 1102.02 GRANULAR "A" TO CONFORM TO O.P.S.D. 1010.
5. ALL HYDRANTS SHALL BE AS PER O.P.S.D. 1105.01 AND SHALL HAVE PUMPER CONNECTIONS, ANCHOR TEES AND DRAIN VALVES, PROVIDES FITTING AT PUMPER CONNECTION NOZZLE.
6. ALL PLUGS, CAPS, TEES AND BENDS SHALL HAVE THRUST BLOCKS OR BE MECHANICALLY RESTRAINED, THRUST BLOCKS TO CONFORM TO O.P.S.D. 1103.01 (HORIZONTAL) AND O.P.S.D. 1103.020 (VERTICAL), RESTRAINING JOINTS AS PER STD.W–6A.
7. MINIMUM DEPTH OF COVER OVER WATERMAIN SHALL BE 1.7m MEASURED FROM THE ROAD CENTERLINE.
8. GATE VALVES SHALL BE RESILIENT SEAT VALVES WITH NON–RISING STEM, 50mm METRO TYPE OPERATING NUT OPENING COUNTERCLOCKWISE AND BE PLACED IN VALVE CHAMBERS.
9. VALVE CHAMBERS SHALL CONFORM TO TOWN STANDARDS. FRAMES AND COVERS TO CONFORM TO O.P.S.D. 401.01 TYPE "A" COVERS TO BE STAMPED "WATER". BACKFILL SHALL BE GRANULAR "B" CONFORMING TO O.P.S.S. 101.
10. COMMERCIAL VALVE CHAMBERS SHALL CONFORM TO TOWN STANDARDS COMPLETE WITH CHECK VALVE.
11. 50mm BLOWOFFS SHALL BE AS PER TOWN STANDARDS.
12. DUCTILE IRON FITTINGS SHALL BE CATHODICALLY PROTECTED. EXACT WEIGHT OF THE ANODES TO BE DETERMINED AT THE TIME OF CONSTRUCTION BY SOIL CONSULTANT.
13. RETRAINED JOINTS TO BE INSTALLED WHERE WATERMAIN IS CONSTRUCTED IN FILL AREAS. REFER TO PLAN AND PROFILE DRAWINGS.

SANITARY SEWER

1. SANITARY MANHOLES AS PER O.P.S.D. 1001.010 WITH FRAMES AND COVERS AS PER O.P.S.D. 401.01 TYPE "A" SANITARY MANHOLE TOPS TO BE STAMPED "SANITARY".
2. SANITARY SEWER PIPES SHALL BE PVC OR CONCRETE AND AS SHOWN ON DRAWINGS. PVC PIPE SHALL BE SDR–35 CONFORMING TO C.S.A. SPECIFICATION B182.2–M1990 AND B182.4–M1992 OR LATEST REVISION THEREOF. 300mm DIA. AND SMALLER CONCRETE PIPES TO BE NON–REINFORCED EXTRA STRENGTH CONFORMING TO C.S.A. SPECIFICATION A257.1–M1982 OR LATEST REVISION THEREOF.
3. BEDDING FOR PVC SANITARY SEWERS TO BE AS PER O.P.S.D. 802.010 WITH GRANULAR "A" BEDDING AND O.P.S.D. 802.030 CLASS "B" WITH GRANULAR "A" BEDDING FOR CONCRETE PIPES.
4. BENCHING TO BE AS PER O.P.S.D. 1004.01 WITH MINIMUM WIDTH OF 230mm OR AS SPECIFIED ON DRAWINGS.
5. SAFETY PLATFORMS TO BE AS PER O.P.S.D. 404.020 AND TO BE INSTALLED IN MANHOLES WHERE DEPTH EXCEEDS 5.0m.
6. DROP STRUCTURES SHALL BE AS PER O.P.S.D. 1003.01 OR 1003.02.
7. SANITARY SERVICE CONNECTIONS (RESIDENTIAL) SHALL BE SINGLE 125mm GREEN PVC SDR–28 PIPE AS PER TOWN STD, O.P.S.D. 1006.02 SERVICE CONNECTIONS TO TERMINATE AT STREETLINE, 50mm X 100mm MARKER STAKES TO BE INSTALLED AT THE END OF ALL SERVICE CONNECTIONS, MARKER STAKES ARE TO EXTEND TO MIN. 1.2m ABOVE PRE–GRADE ELEVATIONS AND TO BE SUITABLY MARKED SAN OR BE COLOUR PAINTED AS DIRECTED BY THE ENGINEER.
8. RISERS ARE REQUIRED ON ALL SANITARY CONNECTIONS WHERE COVER ON MAIN SEWER EXCEEDS 4.5M AS PER O.P.S.D. 1006.02 MODIFIED TO PROVIDE HUB GRADED LIMESTONE BEDDING MATERIAL MAXIMUM 3.0m IN DEPTH OR AS APPROVED BY THE TOWN.

REGION OF PEEL – ADDITIONAL NOTES

1. LOCATION OF ALL EXISTING UTILITIES IN THE FIELD TO BE ESTABLISHED BY THE CONTRACTOR.
2. THE CONTRACTOR(S) SHALL BE SOLELY RESPONSIBLE FOR LOCATES, EXPOSING, SUPPORTING AND PROTECTING OF ALL UNDERGROUND AND OVERHEAD UTILITIES AND STRUCTURES EXISTING AT THE TIME OF CONSTRUCTION IN THE AREA OF HIS WORK, WHETHER SHOWN ON THE PLANS OR NOT, AND FOR ALL REPAIRS AND CONSEQUENCES RESULTING FROM DAMAGE TO SAME.
3. THE CONTRACTOR(S) SHALL BE SOLELY RESPONSIBLE TO GIVE 72 HOURS WRITTEN NOTICE TO UTILITIES PRIOR TO CROSSING SUCH UTILITIES, FOR THE PURPOSE OF INSPECTION BY THE CONCERNED UTILITY. THIS INSPECTION WILL BE FOR THE DURATION OF THE CONSTRUCTION, WITH THE CONTRACTOR RESPONSIBLE FOR ALL COSTS ARISING FROM SUCH INSPECTION.

SITE PLAN LEGEND:

202.00	MAINTAIN EXISTING GRADE	TC	TOP OF CURB
202.00	NEW SPOT ELEVATION	BC	BOTTOM OF CURB
200.00	EXISTING SPOT ELEVATION	H.PT	HIGH POINT
(XXX.XX)	EXISTING BOUNDARY ELEVATION		LIGHT STANDARD
1.8%	SURFACE DRAINAGE		STORM WATER STORAGE
	CONC. CURB		
	CONC. TOE WALL		SILTATION CONTROL FENCE
	PROPERTY LINE		
H+V	HYDRANT & VALVE		OVERLAND FLOW ROUTE
CB	CATCH BASIN	MC	METER CHAMBER
MH	STORM MAINTENANCE HOLE	CVC	CHECK VALVE CHAMBER
CBMH	CATCH BASIN/MAINTENANCE HOLE	PVC	PROTECTUS III VALVE CHAMBER
SAN	SANITARY MANHOLE		


BLOCK 296 REGISTERED PLAN 43M–1324
PART 1, PLAN 43R–37169
PART 2, PLAN 43R–37169
PART 3, PLAN 43R–37169
PART 4, PLAN 43R–37169
PART 5, PLAN 43R–37169
PART 6, PLAN 43R–37169
PART 1, PLAN 43R–10166
PART 2, PLAN 43R–10166
PART 1, PLAN 43R–35489
PART 2, PLAN 43R–35489
PART 1, PLAN 43R–38725
PART 2, PLAN 43R–38725
PART 4, PLAN 43R–40166
PART 5, PLAN 43R–40166
PART 6, PLAN 43R–40166
PART 7, PLAN 43R–40166
PART 8, PLAN 43R–40166
PART 9, PLAN 43R–40166
PART 10, PLAN 43R–40166
PART 11, PLAN 43R–40166
PART 12, PLAN 43R–40166
PART 13, PLAN 43R–40166
PART 14, PLAN 43R–40166
PART 15, PLAN 43R–40166
PART 16, PLAN 43R–40166
PART 17, PLAN 43R–40166
PART 18, PLAN 43R–40166
PART 19, PLAN 43R–40166
PART 20, PLAN 43R–40166
PART 21, PLAN 43R–40166
PART 22, PLAN 43R–40166
PART 23, PLAN 43R–40166
PART 24, PLAN 43R–40166
PART 25, PLAN 43R–40166
PART 26, PLAN 43R–40166
PART 27, PLAN 43R–40166
PART 28, PLAN 43R–40166
PART 29, PLAN 43R–40166
PART 30, PLAN 43R–40166
PART 31, PLAN 43R–40166
PART 32, PLAN 43R–40166
PART 33, PLAN 43R–40166
PART 34, PLAN 43R–40166
PART 35, PLAN 43R–40166
PART 36, PLAN 43R–40166
PIN 14326–0690 (LT)
PIN 14326–0616 (LT)
PIN 14326–0617(LT)
PIN 14326–0618(LT)
PIN 14326–0619(LT)
PIN 14326–0620(LT)
PIN 14326–0621(LT)
PIN 14326–0622(LT)
PIN 14326–0623(LT)
PIN 14326–0624(LT)
PIN 14326–0625(LT)
PIN 14326–0626(LT)
PIN 14326–0627(LT)
PIN 14326–0628(LT)
PIN 14326–0629(LT)
PIN 14326–0630(LT)
PIN 14326–0631(LT)
PIN 14326–0632(LT)
PIN 14326–0633(LT)
PIN 14326–0634(LT)
PIN 14326–0635(LT)
PIN 14326–0636(LT)
PIN