

**NITRATE IMPACT ASSESSMENT REPORT
PROPOSED NEW SUB-DIVISION
0 MOUNT PLEASANT ROAD
TOWN OF CALEDON
ONTARIO**

Prepared for:

**Tropical Land Developments Limited
c/o David Goodman
1500-439 University Ave
Toronto, ON M5G 1Y8**

Prepared By:

SIRATI & PARTNERS CONSULTANTS LIMITED

Project: SP17-212-00
September 10, 2019



12700 Keele Street
King City, Ontario L7B 1H5
Tel: 905.833.1582
Fax:905.833.5360

TABLE OF CONTENTS

1.0	INTRODUCTION AND BACKGROUND	1
2.0	LAND USE	1
3.0	SITE DEVELOPMENT PLAN	2
4.0	PHYSICAL SETTING	2
4.1	Topography and Drainage	2
4.2	Physiography	2
4.3	Overburden Geology	3
4.4	Bedrock Geology	3
5.0	HYDROGEOLOGY	3
5.1	Private Water Wells	3
5.2	Palgrave Municipal Water Supply Wells	4
6.0	SOIL AND GROUNDWATER CONDITIONS	4
6.1	Soil Stratigraphy	4
6.2	Groundwater Conditions	5
7.0	GROUNDWATER QUALITY AND BACKGROUND NITRATE CONCENTRATION	5
7.1	General Water Quality	5
7.2	Nitrate Concentrations	6
8.0	WATER BALANCE	7
8.1	Site Level Water Balance	7
8.2	Climate Data	7
8.3	Infiltration and Runoff	9
9.0	ASSESSMENT OF POTENTIAL NITRATE IMPACTS	10
9.1	Background Nitrate Concentration	10
9.2	Nitrate Dilution Calculation – On-Site Impact Assessment	10
9.3	Nitrate Dilution – Application of Reasonable Use Policy	11
10.0	CONCLUSIONS AND RECOMMENDATIONS	12
	SELECTED BIBLIOGRAPHY	14
	LIMITATIONS AND USE OF THE REPORT	15

FIGURES

Figure 1-1 – Site Location Plan

Figure 3-1 – Site Development Plan

Figure 3-2 – Site Grading Plan

Figure 4-1 – Regional Topographic Map

Figure 4-2 – Site Topographic Survey Map

Figure 4-3 – Innisfil Creek Watershed Map

Figure 4-4 – Physiography Map

Figure 4-5 – Surficial Geology Map

Figure 4-6 – Bedrock Geology Map

Figure 5-1 – MECP Well Record Map

Figure 5-2 – Hydrogeologic Cross section a/c MECP Well Records

Figure 6-1 – SIRATI Borehole/Monitoring Well Location Plan

Figure 6-2 – Cross Section a/c SIRATI Boreholes – MW1, MW2, BH3 and MW4 – A-A'

Figure 6-3 – Cross Section a/c SIRATI Boreholes – BH5, MW6, BH7 & MW8 – B-B'

Figure 6-4 – Inferred Shallow Groundwater Flow Direction Map

Figure 8-1 – Mean Annual Temperature at the Site

Figure 8-2 – Mean Annual Precipitation at the Site

Figure 8-3 – Monthly Average Temperature at the Site

Figure 8-4 – Monthly Average Precipitation in Study Area

APPENDICES

Appendix A – Borehole Logs

Appendix B – Laboratory Certificate of Analysis

Appendix C – Water Balance -Thornthwaite

1.0 INTRODUCTION AND BACKGROUND

Sirati & Partners Consultants Ltd (SIRATI) was retained by Tropical Land Developments Limited, c/o David Goodman (collectively referred to as the “Client”) to conduct a Nitrate Impact Assessment study at the property located at 0 Mount Pleasant Road, Town of Caledon, Ontario (the Subject Property or the Site). The approximate site location is presented on Figure 1-1.

The entire Property is an approximately 12.28-hectare (30.34 acres) parcel of land extending approximately 678.5 metres (m) along northeast and southwest and about 181 m along Mount Pleasant Road. The Property is a cultivated land and includes no structures.

This study was performed in conformance with the Town of Caledon Official Plan Secondary Plan Policies Section 7.1.8.3.

Section 7.1.8.3 indicated that an applicant for an estate residential plan of subdivisions will be required to undertake any studies deemed necessary to assess the termination probability of contaminants on wells in nearby properties by septic system leachate or other sources of contaminants likely to be caused by the proposed development. Accordingly, an assessment of nitrate loadings from the on-site septic systems is being carried out.

It should be noted that a geotechnical investigation was carried out previously at the Site, which consisted of drilling eight (8) boreholes and completion of five (5) monitoring wells in selected boreholes. A hydrogeological study was completed using the data obtained from the geotechnical investigation and the data obtained from the existing monitoring wells. A report entitled “Hydrogeological Impact Study, Proposed New Subdivision, 0 Mount Pleasant Road, Town of Caledon, Ontario” dated September 9, 2019 was prepared by SIRATI. The data or information obtained in the previous investigations was used and incorporated into this report.

2.0 LAND USE

The Subject Property is a vacant undeveloped parcel of land, and is bounded by Mount Pleasant Road to the northeast, vegetated woodlot to the southeast and southwest, and a property with a single/detached residential house to the northwest.

The Site is located within Oak Ridges Moraine Conservation Plan area, in an area designated as Palgrave Estate Residential Community land use area (a component of Countryside Area), where residential development is permitted.

3.0 SITE DEVELOPMENT PLAN

The Subject Property, covering an area of about 12.28 hectares (30.34 acres), was proposed to be developed as a residential subdivision, ultimately comprising of eight (8) single detached custom homes with one-level basement or eight (8) development lots. The proposed site development is shown on Figures 3-1 and 3-2.

It is understood that the source of potable water to the proposed development will be supplied through the Palgrave municipal supply wells, and the new development will be serviced by private septic systems.

4.0 PHYSICAL SETTING

4.1 Topography and Drainage

As shown on Figure 4-1 (The regional topographic map of the study area), the topography of the Site generally ranges in elevation between 290 metres above sea level (mASL) and 300 mASL. Based on Site survey map provided by the Client (Figure 4-2), elevated locations are located in the mid-portion of the Site, where a drainage divide is apparently present in areas of Lots 3, 6 and 7. The highest elevation is identified to be approximately 298.1 mASL in Lot 3.

The Site is located in the area under the jurisdiction of Nottawasaga Valley Conservation Authority (NVCA). The Nottawasaga Valley watershed has nine subwatersheds including Innisfil Creek subwatershed. The Innisfil Creek subwatershed consists of four main creek systems, namely Innisfil Creek, Bailey Creek, Beeton creek and Penville Creek that drain the southeast portion of the Nottawasaga River watershed. The Subject Property falls within the Beeton Creek system of Innisfil Creek subwatershed (Figure 4-3).

Beeton Creek arises on the Oak Ridges Moraine south of Tottenham. Flowing north, the creek enters a reservoir at the Tottenham Conservation Area and then continues downstream. An east branch, originating east of Tottenham, flows westward through agricultural lands and enters Beeton Creek north of Tottenham. Beeton Creek continues to flow northward through an agricultural landscape, skirting the west side of Beeton before joining Bailey Creek and then entering Innisfil Creek.

4.2 Physiography

The Subject Property lies within the physiographic region termed as Oak Ridges Moraine (Figure 4-4). The Oak Ridges Moraine is comprised of rolling sandy hills, hummocky topography and closed depressions that form the source of the headwaters to major stream that drain off the moraine. The Oak Ridges Moraine is an extensive interlobate moraine that extends from the Caledon area, eastward across the northern limits of the Greater Toronto area.

4.3 Overburden Geology

As shown on Figure 4-5, the Subject Property is located in an area covered with ice-contact stratified deposits, which generally consist of gravel and sand deposits, with minor till, and also contain esker, kame, end moraine, ice-marginal delta and subaqueous fan deposits.

The Paleozoic bedrock topography appears to strongly influence the overlying Quaternary sediment thickness and distribution. The thicker Quaternary sediments occur in bedrock topographical lows (i.e. within bedrock valleys and beneath the ORM). The overburden thickness within the Oak Ridges Moraine (ORM) ranges from approximately 56 m to 240 m.

4.4 Bedrock Geology

The bedrock consists of shale, interbedded dolomitic siltstone, and minor limestone, which were deposited in shallow seas about 450 million years ago. These beds, named the Georgian Bay Formation are approximately 250 m thick and dip to the southeast at about 5 m/km. Following long periods of additional sedimentation and erosion, the ancient Laurentian River and its tributaries cut several deep, poorly-defined bedrock valleys trending northwest southeast across the area. As depicted in Figure 4-6, the study area is underlain by the Georgian Bay Formation and have an important influence on drift thickness and groundwater distribution in the study area.

5.0 HYDROGEOLOGY

The regional hydrogeological conditions were assessed using the data obtained from the Ministry of the Environment, Conservation and Parks (MECP) water well database for the domestic water wells and the municipal water wells.

5.1 Private Water Wells

As shown in Figure 5-1, seventeen (17) water wells have been found within a 500 m radius around the property. All these wells were completed between 1966 and 2004, and were screened from the bottom depths ranging from 10 metres below ground surface (mbgs) and 80.4 mbgs (31 ft. to 277 ft.) in medium to coarse sand. No well has encountered bedrock up to the drilled depths of 80.4 mbgs, indicating huge thickness of unconsolidated sediments.

The nearest recorded domestic water wells included the wells #4903748 and #4904792, which are located about 300 m northwest of the Site. Based on the details of the MECP water well records, Well #4903748 was screened between 56.4 mbgs and 57.9 mbgs in coarse sand, with a static water level of 21.3 mbgs, while Well #4904792 was screened between 56.4 mbgs and 57.9 mbgs in sand, with a static water level of 22.9 mbgs.

To present the local geologic profile, a cross-section as shown in Figure 5-2 has been plotted using the information acquired from selected well records.

5.2 Palgrave Municipal Water Supply Wells

The Palgrave community is being serviced by Palgrave municipal supply wells #2, #3 and #4. The Subject Property is situated within a wellhead protection zone, which is associated with the municipal supply well Palgrave Well#3.

Palgrave Well#3 is located about 740 m southwest of the Site, on the northeast side of Mount Hope Road, in Caledon, Ontario. Geologically, Palgrave Well#3 is located near the edge of a local bedrock valley and is overlain by about 80 m thick overburden of Oak Ridges Moraine Aquifer Complex (ORMAC) stratified sediments. This sequence consists (from surface downward) of about four (4) m of sand and gravel, about 35 m of silt and clay with minor sand, about 25 m of gravelly sand and silty sand, a silt and clay unit about five (5) m thick, and finally, about 10 m of gravelly sand where the well is screened (Earthfx , May 2007).

Based on MECP water well record, Palgrave Well#3 was found to have a well ID of 4906859, and was drilled to the depth of approximately 82.3 mbgs into (sandy) clay, and screened between 71.3 mbgs and 80.5 mbgs in (gravelly) sand. The static water level was recorded to be 15.1 mbgs.

Based on the above findings, it can be inferred that layers in a significant thickness of unconsolidated overburden are present in the site area, and multiple sandy soil layers can serve as the aquifer for water supply. However, it is more common that the deeper aquifer is selected for the water supply aquifer, probably because of having a thicker and better protection from the potential contamination.

The ORM is widely recognized as a significant aquifer system and is generally unconfined. The ORM primarily consists of coarse-grained outwash gravel deposits and is reflected by high values of hydraulic conductivity (Gerber and Howard, 2000). Consequently, the ORM complex has become a major source of potable water for domestic wells and communities in the area.

6.0 SOIL AND GROUNDWATER CONDITIONS

6.1 Soil Stratigraphy

The soil stratigraphy of the Site as revealed in the boreholes generally consisted of topsoil with or without fill materials, underlain by native soils of sand, and then by silty sand, silt and sand or sandy silt, locally with silt or clayey silt to silty clay. No bedrock was encountered at the maximum explored depth of 11.2 mbgs.

Figure 6-1 shows the approximate locations of the boreholes and monitoring wells completed in the previous investigations. The details of the soil stratigraphy are presented in Borehole Logs in Appendix A. In addition, two (2) cross sections (as shown on Figures 6-2 and 6-3) were constructed to illustrate the horizontal and vertical extents of the soil and groundwater conditions.

The surficial geology is fairly consistent across the Site, as indicated in the borehole logs. Sand and silty sand are predominant across the site with clayey silt to silty clay situated at deeper depths of 9 m and beyond.

6.2 Groundwater Conditions

Groundwater levels measured in five (5) boreholes (BH/MW1, BH/MW2, BH/MW4, BH/MW6 & BH/MW8) in a monthly monitoring program ranged from 4.41 mbgs and 10.30 mbgs, indicating relatively deep-water table conditions.

The groundwater elevations were recorded to range from 282.3 mASL to 288.2 mASL. The highest groundwater level was measured at MW6, where the high ground elevations are located. Based on the most recent water level data dated March 2018, the groundwater elevation contours were established. As shown on Figure 6-4, groundwater flow appeared to be divergent in the mid-portion of the Site, generally following the surficial topography of the Site.

7.0 GROUNDWATER QUALITY AND BACKGROUND NITRATE CONCENTRATION

7.1 General Water Quality

To assess the general water quality, groundwater samples were collected on July 17, 2019 from three (3) monitoring wells MW1, MW2 and MW4 for chemical analysis (note: the monitoring well MW6 was dry and MW8 was damaged). The samples were submitted to AGAT laboratory for analysis of the parameters as per Water Quality Assessment package provided by AGAT. The analytical results are provided in the Laboratory Certificate of Analysis in Appendix B.

The results were compared with Ontario Drinking Water Quality Standards (ODWQS)-Aesthetic Objectives and Operational Guidelines, and indicated that exceedances or elevated concentrations for aluminum, iron, manganese, total hardness and turbidity were found in all the tested groundwater samples. In addition, nitrate was found exceeding the ODWQS limit of 10 mg/L in groundwater taken from MW1. The exceedances or elevated concentrations may have resulted from the sediments and/or particulates contained in the analyzed water samples.

7.2 Nitrate Concentrations

As part of water quality assessment, nitrate was analyzed in three (3) groundwater samples taken from MW1, MW2 and MW4. The results are presented in Table 7-1 below.

7-1: Nitrate Concentration in Groundwater (dated July 17, 2019)

Monitoring Well	Nitrate as N (mg/L)	ODWQS Standard (mg/L)
MW1	33.1	10
MW2	0.49	10
MW4	8.64	10

To verify the results of nitrate in groundwater, a re-sampling and testing of groundwater was completed on August 16, 2019. The groundwater samples were submitted to ALS laboratory for analysis of nitrate. The analytical results are provided in the Laboratory Certificate of Analysis in Appendix B, and are presented in the table below.

7-2: Nitrate Concentration in Groundwater (dated August 16, 2019)

Monitoring Well	Nitrate as N (mg/L)	ODWQS Standard (mg/L)
MW1	34.0	10
MW2	0.64	10
MW4	4.29	10

Based on the above, the analytical results for nitrate concentration analyzed by two (2) different labs appeared to be fairly consistent, and the exceedances of ODWQS Standard for nitrate were found in groundwater samples taken from MW1.

It is known that high nitrate concentrations are usually due to human activities, such as agriculture, industry, domestic effluents and emissions from combustion engines. Historically, the Site and the northwest adjacent property were used as farmlands. Therefore, the elevated nitrate concentration may be related to the past farming activities on Site and/or off-site such as application (likely overuse) of chemical fertilizer for the crops.

Also, it should be noted that MW1 is located in a low-lying area, where an ephemeral creek is located and accumulation of surface drainage is very possible near this location. In addition, given the presence of thick sand layer and deep groundwater table (about 10 mbgs) at MW1, infiltration of the accumulated water, together with oxidation of organic material contained in the water may take place, which would result in elevated nitrate concentration in this area.

It may be anticipated that the nitrate concentration would be low in the mid-portion of the Site, where high elevations are located.

8.0 WATER BALANCE

8.1 Site Level Water Balance

Based on the Thornthwaite and Mather methodology (1957), the water balance is an accounting of water in the hydrologic cycle. Precipitation (P) falls as rain and snow. It can run off towards lakes and streams (R), infiltrate to the groundwater table (I), or evaporate from ground or evapotranspiration by vegetation (ET). When long-term average values of P, R, I, and ET are used, there is minimal or no net change to groundwater storage (ΔS).

The annual water budget can be expressed as:

$$P = ET + R + I + \Delta S$$

Where:

P = Precipitation (mm/year)

ET = Evapotranspiration (mm/year)

R = Run-off (mm/year)

I = Infiltration (mm/year)

ΔS = Change in groundwater storage (taken as zero) (mm/year)

8.2 Climate Data

Monthly average temperature and precipitation data were obtained from Environment Canada, for Orangeville WPCP station (climate identifier: 6155790) as the nearest station located at about 8 km distance from the Property. Data was available between the years 1962 to 2006. Mean temporal variations of temperature and precipitation are shown in Figures 8-1 and 8-2.




Figure 8-1: Mean Annual Temperature at the Site




Figure 8-2: Mean Annual Precipitation at the Site

Average monthly variations of both temperature and precipitation were calculated for the period from 1962 to 2006 and is presented below in Figures 8-3 and 8-4, respectively. The highest temperature was recorded in the month of July, while the highest precipitation was in the month of August.




Figure 8-3: Average Monthly Temperature at the Site




Figure 8-4: Average Monthly Precipitation at the Site

8.3 Infiltration and Runoff

Potential evapotranspiration was estimated to be about 529 mm/annum using the USGS Thornthwaite Monthly Water Balance software (Appendix D) utilizing average monthly temperature and precipitation results of Environment Canada, Orangeville weather station.

As mentioned above, given the potential evapotranspiration at 529 mm/annum and the average annual precipitation of 725 mm/annum, there is a net water surplus of 196 (=725-529) mm/annum occurring at the Site, which can either infiltrate into subsurface or go as run-off.

As a very conservative estimate of precipitation infiltration at the Subject Property, a value of 196 mm/year (say 0.2 m/year) was utilized for nitrate dilution calculations.

9.0 ASSESSMENT OF POTENTIAL NITRATE IMPACTS

In compliance with Town of Caledon Official Plan, potential nitrate impacts which are associated with the proposed development were assessed.

The impacts on local groundwater regime and down gradient property boundary are dependent upon the hydrogeology of the area, the background concentration of nitrate in the groundwater and contaminant concentration contained within the effluent.

9.1 Background Nitrate Concentration

As discussed in Section 7, nitrate was analyzed in groundwater samples taken from three (3) monitoring wells MW1, MW2 and MW4, and elevated nitrate concentrations were found at MW1. The elevated concentrations may have been caused due to the farming activities and/or due to the low-lying location. As a result, it would be anticipated that the nitrate concentration at the Site will be minimized after the residential development, when a channel is constructed as proposed and no farming activities will take place.

It should be noted that MW1 is located near the proposed channel area, which is outside the proposed eight (8) residential development lots. Therefore, the data obtained from MW1 will not be used as a background nitrate concentration.

Accordingly, the nitrate concentrations obtained from MW2 and MW4 during two rounds of sampling would be used for estimating the background nitrate concentration in the groundwater at the Subject Property, which was calculated to be 3.52 mg/L.

9.2 Nitrate Dilution Calculation – On-Site Impact Assessment

It should be noted that where municipal water and wastewater services are not available, all the proposed developments need to be self-sustaining on private individual water wells and private individual sewage disposal systems. As noted previously in the report, the source of the potable drinking water supply for the proposed residential development will be from the Palgrave municipal water supply wells.

The nitrate dilution calculations presented here are as per the methodology and procedures indicated in the Technical Guideline D-5 (Ministry of Environment, 1996) and the Ontario Building Code (Ministry of

Municipal Affairs and Housing, 2011, as amended) for development proposals involving private on-site servicing.

Based on the Site information, the following data was gathered and on-site nitrate impact assessment calculation was completed.

Site Information:

Number of Proposed lots (P)	8
Daily Effluent Flow /Lot (F)	1,000 L/day
Development Area (A)	11.117 ha
Infiltration Rate (Ir) (From water balance)	0.20 m/year
Nitrate Loading /Dwelling (N)	40 g/day
Impervious Surface (S)	assumed 20%

Calculations:

Step 1: Calculation of On-site Recharge (R)

$$\begin{aligned} &= A \times (1-S) \times Ir + P \times F \\ &= 111,170 \text{ m}^2 \times (1-0.2) \times (0.20 \text{ m/year}) + (8 \times 1,000 \text{ L/day}) \\ &= 17,787.2 \text{ m}^3/\text{year} + 8,000 \text{ L/day} \\ &= 48,732 \text{ L/day} + 8,000 \text{ L/day} \\ &= 56,732 \text{ L/day} \end{aligned}$$

Step 2: Calculation of Nitrate Loading (L)

$$\begin{aligned} &= N \times P \\ &= 40 \text{ g/day} \times 8 \\ &= 320,000 \text{ mg/day} \end{aligned}$$

Step 3: Resultant Nitrate Concentration at Site Boundary

$$\begin{aligned} &= L / R \\ &= 320,000 \text{ mg/day} / 56,732 \text{ L/day} \\ &= 5.64 \text{ mg/L} \end{aligned}$$

Based on the above calculations, a total load of 320,000 mg/day of nitrate will be added on the proposed development lots, which will result in an added concentration of 5.64 mg/L for nitrate in groundwater.

9.3 Nitrate Dilution – Application of Reasonable Use Policy

Reasonable Use Policy (RUP) is used to estimate the off-site nitrate impact assessment at the site boundary of the proposed development, based on RUP Guideline B-7 (MOE, 1996). The RUP dilution equation is as shown below. To be conservative on the nitrate dilution calculations, 80% of the total site

area (i.e., 122,800 x 0.8 m²) was used as water contributing area and the remaining as the impervious land.

$$C_{rup} = (Q_1 C_1 + Q_2 C_2) / Q_t$$

Where,

Q_1 = contribution from 80% of property = total area (m²) x infiltration (m/annum) (98,240 m² * 0.20 m/annum infiltration = 19,648 m³/annum)

C_1 = background nitrate concentration, 3.52 mg/L

Q_2 = contribution from leaching beds = 8 lots * 1,000 L/d = 8,000 L/d (2,920 m³/annum)

C_2 = septic effluent nitrate concentration = 40 mg/L (conservative for Class 4 treatment)

Q_t = total offsite discharge = $Q_1 + Q_2$

C_{rup} = nitrate concentration at down gradient property boundary (mg/L)

Using the above assumptions, the concentration of nitrate in the shallow groundwater system at the property boundary was estimated to be 8.24 mg/L, which is below the limit of 10 mg/L for nitrate set by the Ministry of the Environment, Conservation and Parks (MECP) reasonable use policy.

Therefore, the predicted concentration at the adjacent property boundary does not exceed 10 mg/L, indicating that the RUP guideline is met for the Subject Property. Although, RUP calculations are not typically applied to small sewage systems, the results of the RUP assessment are, however, for reference purpose.

Also, the RUP calculation does not take into consideration of biodegradation or denitrification in the subsurface and does not allow for plant uptake. This RUP calculation has considered dilution only, and thus, is very conservative in terms of overall conditions at the Subject Property.

10.0 CONCLUSIONS AND RECOMMENDATIONS

This report was prepared by SIRATI in support of a proposed development at 0 Mount Pleasant Road, Town of Caledon, Ontario.

Based on the information obtained from previous investigations and the results of nitrate impact assessment conducted at the Subject Property, the following findings or conclusions can be presented:

- The Subject Property falls within the Beeton Creek secondary watershed of Innisfil Creek subwatershed of Nottawasaga Valley Watershed, under the jurisdiction of Nottawasaga Valley Conservation Authority (NVCA).
- The topography of the Site presents elevated locations or a drainage divide located in the mid-portion of the Site.

- The soil stratigraphy of the Site generally consisted of topsoil with or without fill materials, underlain by native soils of sand, and then by silty sand, silt and sand or sandy silt, locally with silt or clayey silt to silty clay.
- Groundwater levels monitored in five (5) existing monitoring wells (BH/MW1, BH/MW2, BH/MW4, BH/MW6 & BH/MW8) ranged from 4.41 mbgs and 10.30 mbgs, with the highest groundwater measured in MW6 located in the mid-portion of the Site.
- Groundwater flow was inferred to be divergent in the mid-portion of the Site, generally following the surficial topography of the Site.
- Water balance analysis indicated a water surplus of 196 mm/year (or about 0.2 m/year) in the site area, which can either infiltrate into subsurface or go as run-off.
- Groundwater quality assessment indicated that groundwater samples may not meet the Ontario Drinking Water Quality Standards (ODWQS) due to the elevated concentrations of aluminum, iron, manganese, total hardness and turbidity and/or nitrate.
- Elevated concentrations or exceedances of nitrate were detected in one (1) monitoring well (MW1) located in a low-lying area near an ephemeral creek, which may be due to the past farming activities or as a result of oxidation of accumulated organic material in groundwater. The background concentration of nitrate in the groundwater was calculated to be 3.52 mg/L, which is below the ODWQS of 10 mg/L for nitrate.
- As the proposed development is based on the private septic systems for the proposed eight (8) residential lots, a concentration of 5.64 mg/L of nitrate is anticipated to be added into the groundwater system in the area of the development lots.
- Reasonable Use Policy (RUP) was used to assess the off-site nitrate impact associated with the proposed residential development, and the estimated or predicted nitrate concentration at the property boundary is 8.24 mg/L, which meets Ministry of the Environment, Conservation and Parks (MECP) reasonable use policy (RUP) guideline of 10 mg/L for nitrate.
- The results of nitrate impact assessment support the proposed residential subdivision plan with eight (8) lots, as no impacts due to the development are anticipated at this time.

SELECTED BIBLIOGRAPHY

Johnson, M.D., Armstrong, D.K., Sanford, B.V., Telford, P.G. and Rutka, M.A., 1992. Paleozoic and Mesozoic geology of Ontario; *in* Geology of Ontario, Ontario Geological Survey, Special Volume 4, Part 2, p.907-1008.

Ministry of Natural Resources, Ontario Geologic Survey, 1984, The Physiography of Southern Ontario, Third Edition, L. J. Chapman and D. F. Putnam

MMAH, 1997. Ontario Building Code, Part 8 – Sewage Systems. Ont. Reg. 403/97 made under the Building Code Act, 1992. As amended from time to time.

Ministry of the Environment, 1982. Manual of Policy, Procedures and Guidelines for Onsite Sewage Systems. Queen's Printer for Ontario, ISBN 0-7743-7303.

Ministry of the Environment, 1996. Procedure D-5-4 – Technical Guideline for Individual On-Site Sewage Systems: Water Quality Impact Assessment.

Ministry of the Environment, 1997. Ontario Building Code. Sewage System Design Flows. Table 8.2.1.3.A. Residential Occupancy

Ministry of the Environment, 2008. Design Guideline for Sewage Works. PIBS6879

Ontario Geological Survey 1991. Bedrock geology of Ontario, southern sheet; Ontario Geological Survey, Map 2544, scale 1: 1 000 000.

Thornthwaite, C.W., and Mather, J.R., 1957 Instructions and tables for computing potential evapotranspiration and the water balance. *Climatology*, vol. X, #3.

Freeze, R. A. and Cherry, J. A., 1979, *Groundwater*, Prentice-Hall, Englewood Cliffs, New Jersey

Sirati & Partners Consultants Ltd., Report on Hydrogeological Impact Study, 0 Mt. Pleasant Road, Town of Caledon, Ontario, May 18, 2018.

LIMITATIONS AND USE OF THE REPORT

This report was produced for the sole use of Tropical Land Developments Limited, c/o David Goodman (the Client) for the property located at 0 Mount Pleasant Road, Town of Caledon, Ontario and may not be relied upon by any other person or entity without the written authorization of Sirati & Partners Consultants Limited (SIRATI). The conclusions presented in this report are professional opinions based on the historical and current records search, visual observations and limited information provided by persons knowledgeable about past and current activities on this site. As such, SIRATI cannot be held responsible for environmental conditions at the Property that was not apparent from the available information. No investigation method can completely eliminate the possibility of obtaining partially imprecise or incomplete information; it can only reduce the possibility to an acceptable level.

Professional judgement was exercised in gathering and analyzing data and formulation of recommendations using current industry guidelines and standards. Similar to all professional persons rendering advice, SIRATI cannot act as absolute insurer of the conclusion we have reached. No additional warranty or representation, expressed or implied, is included or intended in this report other than stated herein the report.

The assessment should not be considered a comprehensive audit that eliminates all risks of encountering environmental problems. The information presented herein this report is primarily based on information collected during the hydrogeological study based on the condition of the Property at the time of site inspection/drilling followed by a review of historical data, as appended to this report.

In assessing the environmental setting of the Property, SIRATI has solely relied upon information supplied by others in good faith and has therefore assumed that the information supplied is factual and accurate. We accept no responsibility for any inaccurate information, misrepresentation or for any deficiency of the information supplied by any third party.

The scope of services performed in the execution of this investigation may not be appropriate to satisfy third parties. SIRATI accepts no responsibility for damages if any, suffered by any third party as a result of decisions made or action taken based on this report. Any use, copying or distribution of the report in whole or in part is not permitted without the express written permission of SIRATI and use of findings, conclusions and recommendations represented in this report, is at the sole risk of third parties.


In the event that during future work new information regarding the environmental condition of the Property is encountered, or in the event that the outstanding responses from the regulatory agencies indicate outstanding issues on file with respect to the Property, SIRATI should be notified in order that we may re-evaluate the findings of this assessment and provide amendments, as required.

Should you have any questions regarding the information presented or limitation set in this report, please do not hesitate to contact our office.

Yours truly,

Sirati and Partners Consultants Limited


Sudhakar Kurli, M.Sc., P. Geo.
Hydrogeologist/Project Manager


Bujing Guan, M. A.Sc., P. Geo.
Senior Hydrogeologist/Environmental Specialist

FIGURES



SIRATI & PARTNERS

Geotechnical Hydrogeological & Environmental Solutions
 12700- Keele Street
 King City, ON. L7B 1H5
 Phone# 905 833 1582, Fax# 905 833 5360



Legend:

----- Property Boundary

Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.


Figure Title:
Site Location Plan

Scale:
0m 100m 200m

Project Number:
SP17-212-30

Date:
September 2019

Figure Number:
1-1



SIRATI & PARTNERS

Geotechnical Hydrogeological & Environmental Solutions

12700- Keele Street
King City, ON. L7B 1H5
Phone# 905 833 1582, Fax# 905 833 5360

North:



Legend:

Property Boundary

Project Title	
0 MOUNT PLEASANT ROAD, CALEDON TROPICAL LAND DEVELOPMENT LTD.	
Location	
MOUNT PLEASANT ROAD-CALEDON	
Drawing Title	
SITE PLAN	
Scale	1:1000
Date	October 3, 2017
Drawn By	C.K./S.R
Checked By	F.C
Project No.	201711
Drawing No.	A-101



Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
Site Development Plan

Scale: **Project Number:**
SP17-212-30

Date: September 2019 **Figure Number:** 3-1



LEGEND

- ENVIRONMENTAL PROTECTION
- REFORESTED / PROTECTION AREA
AREA = 4.00ha
- STRUCTURE ENVELOPE
- * DENSITY BONUS LOT PER O.P. POLICY 7.19.12

LOT SIZE SUMMARY CHART

LOT #	LOT AREA (Ha)	STRUCTURE ENVELOPE (Ha)
1	1.358	0.500
2	0.638	0.500
3	0.616	0.499
4	1.138	0.500
5	3.965	0.500
6	0.891	0.499
7	0.890	0.498
8	1.621	0.484

SCHEDULE OF LAND USE

DESCRIPTION	LOT / BLOCK NO.	RESIDENTIAL UNITS	AREA (Ha)
SINGLE DETACHED RESIDENTIAL	1 - 8	8	11.11
TOTAL SINGLE DETACHED		8	
NET DEVELOPABLE TOTAL		8	11.11
0.3 RESERVE	09, 10		0.005
FUTURE ROAD & TRAIL CONNECTION	11		0.154
RIGHT OF WAY	STREET 'A'		0.999
TOTAL SITE AREA		8	12.27

North:

Legend:

Property Boundary

TROPICAL LAND DEVELOPMENT LTD.

REVISIONS

No.	Description	Date	Int.
3			
2			
1	REVISION	6/12/19	JS

PROJECT No.: 17445
 DATE: May 4, 2018
 SCALE: 1:1000
 DRAFTED BY: JS CHECKED BY: MJ

DP-01

Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.



Figure Title:
Site Grading Plan

Scale: 0m 50m

Project Number: SP17-212-30

Date: September 2019

Figure Number: 3-2



SIRATI & PARTNERS
 Geotechnical Hydrogeological & Environmental Solutions
 12700- Keele Street
 King City, ON. L7B 1H5
 Phone# 905 833 1582, Fax# 905 833 5360

North:

Legend:

- Property Boundary

Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
Regional Topographic Map



Scale:
0m 100m 200m

Project Number:
SP17-212-30

Date:
September 2019

Figure Number:
4-1

Source: Data provided by Ontario Ministry of Natural Resources and Forestry © Copyright: 2018 Queen's Printer of Ontario. All Rights Reserved.



LEGEND


- ENVIRONMENTAL PROTECTION
- REFORESTED / PROTECTION AREA
AREA = 4.00ha
- STRUCTURE ENVELOPE
- * DENSITY BONUS LOT PER O.P. POLICY 7.19.12

LOT SIZE SUMMARY CHART

LOT #	LOT AREA (Ha)	STRUCTURE ENVELOPE (Ha)
1	1.358	0.500
2	0.638	0.500
3	0.616	0.499
4	1.138	0.500
5	3.965	0.500
6	0.891	0.499
7	0.890	0.499
8	1.621	0.484

SCHEDULE OF LAND USE

DESCRIPTION	LOT / BLOCK NO.	RESIDENTIAL UNITS	AREA (Ha.)
SINGLE DETACHED RESIDENTIAL	1 - 8	8	11.117
TOTAL SINGLE DETACHED		8	
NET DEVELOPABLE TOTAL		8	11.117
0.3 RESERVE	09, 10		0.005
FUTURE ROAD & TRAIL CONNECTION	11		0.154
RIGHT OF WAY	STREET 'A'		0.999
TOTAL SITE AREA		8	12.275



Legend:
 Property Boundary

TROPICAL LAND DEVELOPMENT LTD.

REVISIONS

No.	Description	Date	Int.
3			
2			
1	REVISION	6/12/19	JS

PROJECT No.: 17445
 DATE: May 4, 2018
 SCALE: 1:1000
 DRAFTED BY: JS CHECKED BY: MJ

DP-01

Project Title:
 Nitrate Impact Assessment

Site Location:
 0 Mt. Pleasant Road, Caledon, ON.


Figure Title:
 Site Topographic Survey Map

Scale:


Project Number:
 SP17-212-30

Date:
 September 2019

Figure Number:
 4-2



SIRATI & PARTNERS
 Geotechnical Hydrogeological & Environmental Solutions
 12700- Keele Street
 King City, ON. L7B 1H5
 Phone# 905 833 1582, Fax# 905 833 5360



Legend:

- Subject Site
- Approximate Site Location

- | | |
|--|--|
| 1, Blue Mountains W. | SWP Watershed Region |
| 2, Boyne R. | SWP Watershed Area |
| 3, Innisfil Cr. | Upper Tier Municipality |
| 4, Lower Nottawasaga R. | Lower Tiers Municipality |
| 5, Mad R. | Subwatershed Boundary |
| 6, Middle Nottawasaga R. | Water Body |
| 7, Pine R. | Main Water Courses |
| 8, Upper Nottawasaga R. | |
| 9, Willow Cr. | |

Project Title:
Nitrate Impact Assessment


Site Location:
0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
Innisfil Creek Watershed Map

Scale: 0m 1km 2km	Project Number: SP17-212-30
-----------------------------	---------------------------------------

Date: September 2019	Figure Number: 4-3
--------------------------------	------------------------------

Source: Map Data © 2014-2018 NVCA



Legend:

- Subject Site
- Approximate Site Location

Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
Physiography Map

Scale:
0m 1km 2km

Project Number:
SP17-212-30



Date:
September 2019

Figure Number:
4-4

- Innisfil Creek Subwatershed
- Physiographic Regions**
- Horseshoe Moraines
 - Peterborough Drumlin Field
 - Schomberg Clay Plains
 - Simcoe Lowlands
 - Simcoe Uplands
 - Niagara Escarpment
 - Oak Ridges Moraine

Source: Map Data © 2014-2018 NVCA

Beeton Creek Quaternary Geology



SIRATI & PARTNERS

Geotechnical Hydrogeological & Environmental Solutions

12700- Keele Street
King City, ON. L7B 1H5
Phone# 905 833 1582, Fax# 905 833 5360

North:



Legend:

- Subject Site
- Approximate Site Location

Project Title:

Nitrate Impact Assessment


Site Location:

0 Mt. Pleasant Road, Caledon, ON.

Figure Title:

Surficial Geology Map

Scale:



Project Number:


SP17-212-30

Date:

September 2019

Figure Number:

4-5



North:



Legend:



Subject Site



Approximate Site Location

SILURIAN

UPPER SILURIAN

- 54 **Limestone, dolostone, shale, sandstone, gypsum, salt**
 - 54a Bass Islands Fm.
 - 54b Bertie Fm.
 - 54c Salina Fm.
 - 54d Kenogami River Fm. (Upper Silurian to Lower Devonian)

MIDDLE AND LOWER SILURIAN

- 53 **Sandstone, shale, dolostone, siltstone**
 - 53a Guelph Fm.
 - 53b Lockport Fm.
 - 53c Amabel Fm.
 - 53d Clinton Gp.; Cataract Gp.
 - 53e Thornloe Fm.; Earleton Fm.
 - 53f Wabi Gp.
 - 53g Attawapiskat Fm.
 - 53h Ekwan River Fm.
 - 53i Severn River Fm.

ORDOVICIAN

UPPER ORDOVICIAN

- 52 **Shale, limestone, dolostone, siltstone**
 - 52a Queenston Fm.
 - 52b Georgian Bay Fm.; Blue Mountain Fm.; Billings Fm.; Collingwood Mb.; Eastview Mb.
 - 52c Liskeard Gp.
 - 52d Red Head Rapids Fm.
 - 52e Churchill River Gp.
 - 52f Bad Cache Rapids Gp.

MIDDLE ORDOVICIAN

- 51 **Limestone, dolostone, shale, arkose, sandstone**
 - 51a Ottawa Gp.; Simcoe Gp.; Shadow Lake Fm.
 - 51b Chazy Gp., Rockcliffe Fm.

LOWER ORDOVICIAN

- 50 **Dolostone, sandstone:** Beekmantown Gp.

CAMBRIAN

- 49 **Conglomerate, sandstone, shale, dolostone:** Potsdam Gp.; Nepean Fm., Covey Hill Fm.

Project Title:

Nitrate Impact Assessment


Site Location:

0 Mt. Pleasant Road, Caledon, ON.

Figure Title:

Bedrock Geology Map

Scale:



Project Number:


SP17-212-30

Date:

September 2019

Figure Number:

4-6



SIRATI & PARTNERS

Geotechnical Hydrogeological & Environmental Solutions
 12700- Keele Street
 King City, ON. L7B 1H5
 Phone# 905 833 1582, Fax# 905 833 5360

North:



Legend:

- - - - - Property Boundary
- - - - - 500 m Study Area

Project Title:

Nitrate Impact Assessment


Site Location:

0 Mt. Pleasant Road, Caledon, ON.

Figure Title:

MECP Well Record Map

Scale:



Project Number:

SP17-212-30


Date:

September 2019






Figure Number:


5-1

North:



Legend:

-  Top Soil
-  Sand
-  Clay
-  Silt
-  Gravel



Project Title:
Nitrate Impact Assessment

Site Location:
0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
Hydrogeologic Cross Section a/c MECP
Well Records

Scale: As Shown **Project Number:** SP17-212 -00



Date: September 2019 **Figure Number:** 5-2



North:



Legend:

- - - - Property Boundary
- Creek
- Creek Buffer
-  Monitoring Well
-  Borehole

Project Title:

Nitrate Impact Assessment


Site Location:

0 Mt. Pleasant Road, Caledon, ON.

Figure Title:

SIRATI Borehole / Monitoring Well Location Map

Scale:



Project Number:

SP17-212-00


Date:

September 2019

Figure Number:

6-1

North:



Legend:

- Top Soil
 - Fill
 - Sand
 - Silty Sand
 - Clayey Silt / Silty Clay
 - Sandy Silt
 - Silt
- MW1 ← Borehole / Well ID
- ← Water Level
- ← Well Screen

Project Title:

Nitrate Impact Assessment

Site Location:

0 Mt. Pleasant Road, Caledon, ON.

Figure Title:

Cross Section a/c SIRATI Boreholes
 MW1, MW2, BH3 and MW4 – A-A'

Scale:

As Shown

Project Number:

SP17-212-00


Date:

September 2019

Figure Number:

6-2

North:



Legend:

- Top Soil
- Fill
- Sand
- Silty Sand
- Clayey Silt / Silty Clay
- Sandy Silt
- Silt

MW1 ← Borehole / Well ID

▼ ← Water Level

▬ ← Well Screen

Project Title:
 Nitrate Impact Assessment

Site Location:
 0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
 Cross Section a/c SIRATI Boreholes
 MW4, BH5, MW6, BH7 and MW8 - B-B'

Scale: As Shown	Project Number: SP17-212-00
---------------------------	---------------------------------------

Date: September 2019	Figure Number: 6-3
--------------------------------	------------------------------



SIRATI & PARTNERS
 Geotechnical Hydrogeological & Environmental Solutions
 12700- Keele Street
 King City, ON. L7B 1H5
 Phone# 905 833 1582, Fax# 905 833 5360

North:

Legend:

- Contour Line
- Inferred Groundwater Flow Direction
- Monitoring Well & Groundwater Elevation

Project Title:
 Nitrate Impact Assessment

Site Location:
 0 Mt. Pleasant Road, Caledon, ON.

Figure Title:
 Inferred Groundwater Table Contour Map
 March 2018

Scale:
 0m 30m 60m

Project Number:
 SP17-212-00

Date:
 September 2019



Figure Number:
 6-4

APPENDICES

APPENDIX A

<p>PROJECT: Geotechnical, Environmental and Hydrogeological Services CLIENT: Tropical Land Developments Limited PROJECT LOCATION: Mt Pleasant Road, Caledon, ON DATUM: Geodetic BH LOCATION: See Figure 6-1</p>	<p>DRILLING DATA Method: Hollow Stem Augers Diameter: 200mm Date: Jun/02/2017</p> <p style="text-align: right;">REF. NO.: SP17-212-10 ENCL NO.: 2</p>
---	--

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT w	LIQUID LIMIT W _L	POCKET PEN. (C _u) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20 40 60 80 100	20 40 60 80 100						
291.9															GR SA SI CL
0.0	TOPSOIL: 350mm		1	SS	7										
291.6	FILL: silty sand, trace clay, trace rootlets, brown, moist, loose														
0.4															
291.1	SAND: trace silt, trace gravel, brown, moist, very loose		2	SS	3		291								
0.8															
1															
1															
2															
2															
3															
3															
4															
4															
5															
5															
6															
6															
7	compact below 6.1 m		7	SS	12										
7															
8															
8															
9															
9															
10	very moist to wet below 9.1m		8	SS	22		284								
10															
10															
11															
11															
11															
11															
11															
11															
11															
11															
11															
11.2	END OF BOREHOLE Notes: 1) Monitoring well installed in the borehole upon completion. 2) Water level in monitoring well at 9.8m on June 16, 2017.		10	SS	17		281								



SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GP, J. SPCL, GDT, 7/5/17

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/01/2017
REF. NO.: SP17-212-10
ENCL NO.: 3

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT w	LIQUID LIMIT W _L	POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40	60	80						
295.8																	
290.0	TOPSOIL: 200mm																
0.2	SAND: trace silt, trace gravel, brown, moist, loose to compact		1	SS	6												
			2	SS	18												
			3	SS	21												
			4	SS	16												
	occasional silt seams at 3m		5	SS	20												
			6	SS	26												
289.7																	
6.1	SILT TO SANDY SILT: trace clay, trace gravel, grey, wet, compact		7	SS	20											0 10 66 24	
288.2																	
7.6	SILTY SAND: trace clay, brown, wet, compact		8	SS	29												
286.7																	
9.1	CLAYEY SILT TO SILTY CLAY: trace sand, occasional sand seams, greyish brown, wet, stiff		9	SS	9												
284.6			10	SS	13												
11.2	END OF BOREHOLE Notes: 1) Monitoring well installed in the borehole upon completion. 2) Water level in monitoring well at 9.6m on June 16, 2017.																

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GP, J, SPCL, GDT, 7/15/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES +3, x3: Numbers refer to Sensitivity ○ = 3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services	DRILLING DATA
CLIENT: Tropical Land Developments Limited	Method: Hollow Stem Augers
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON	Diameter: 200mm
DATUM: Geodetic	Date: Jun/01/2017
BH LOCATION: See Figure 6-1	REF. NO.: SP17-212-10
	ENCL NO.: 4

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)	
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40	60	80				100
297.7	TOPSOIL: 150mm														
297.6 0.2	SAND: weathered/disturbed, trace silt, brown, moist, loose		1	SS	6										
296.9 0.8	SAND: trace silt, brown, moist, compact		2	SS	12										
	occasional silt seams at 1.5m		3	SS	23										
			4	SS	27										
			5	SS	24										
			6	SS	25										
			7	SS	25										
			8	SS	26										
289.5	END OF BOREHOLE Notes: 1) Borehole dry on completion.														

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON.GPJ SPCL.GDT 7/5/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES + 3, x 3: Numbers refer to Sensitivity ○ ●=3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/01/2017
REF. NO.: SP17-212-10
ENCL NO.: 5

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT w	LIQUID LIMIT W _L	POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%) GR SA SI CL	
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40							60
291.6																
290.6	TOPSOIL: 150mm		1	SS	4											
0.2	FILL: silty sand, trace topsoil, dark brown, moist, very loose		2	SS	3											
290.1																
1.5	SAND: some silt, brown, moist, compact		3	SS	17											
			4	SS	26											
			5	SS	21											
287.0	SANDY SILT: trace clay, trace gravel, grey, wet, compact		6	SS	19											
4.6																
			7	SS	16											
284.0	SILT: trace sand, grey, wet, compact		8	SS	19											
7.6																
283.4																
8.2	END OF BOREHOLE Notes: 1) Monitoring well installed in the borehole upon completion. 2) Water level in monitoring well at 4.7m on June 16, 2017.															

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON.GPJ SPCL_GDT_7/5/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES + 3, × 3: Numbers refer to Sensitivity ○ ●=3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/01/2017
REF. NO.: SP17-212-10
ENCL NO.: 6

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)					
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)							PLASTIC LIMIT	NATURAL MOISTURE CONTENT	LIQUID LIMIT		
							20	40	60	80	100	W _p	w	W _L		GR SA SI CL			
294.3	SAND: trace silt, trace gravel, brown, moist, loose to compact		1	SS	7														
294																			
293																			
292																			
291																			
289.7	SANDY SILT TO SILTY SAND: trace clay, greyish brown, moist to wet, compact		6	SS	25														
289																			
288			7	SS	22														
287																			
286.7	INTERBEDED SAND AND SILT: trace clay, brown, moist, dense		8	SS	35														
286.1																			
8.2	END OF BOREHOLE Notes: 1) Borehole open and dry on completion.																		

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GP J, SPCL, GDT, 7/5/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES + 3, x 3: Numbers refer to Sensitivity ○ = 3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/01/2017
REF. NO.: SP17-212-10
ENCL NO.: 7

SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT w	LIQUID LIMIT W _L	POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%) GR SA SI CL
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE			"N" BLOWS 0.3 m	20 40 60 80 100						
295.1														
0.0	TOPSOIL: 500mm		1	SS	5									
294.6	FILL: sandy silt, trace topsoil, brown, moist, loose POSSIBLE FILL: sand, trace silt, brown, moist, very loose	[Cross-hatched pattern]												
294.3			2	SS	2									
293.5	SILTY SAND: trace clay, brown, moist, very loose	[Dotted pattern]	3	SS	4									
292.8	SAND: trace silt, trace gravel, occasional silt layers, brown to greyish brown, moist to very moist, compact to dense	[Dotted pattern]	4	SS	25									
292.3			5	SS	27									
291.6			6	SS	34									
289.6			7	SS	41									
287.5	SILT TO SANDY SILT: trace clay, grey, moist, compact	[Vertical lines pattern]	8	SS	28									
286.9														
8.2	END OF BOREHOLE Notes: 1) Monitoring well installed in the borehole upon completion.													

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GP J. SPCL. GDT. 7/15/17

GROUNDWATER ELEVATIONS

Measurement 1st 2nd 3rd 4th

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity
○ = 3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/02/2017
REF. NO.: SP17-212-10
ENCL NO.: 8

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT					POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)		
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)								W _p	W
296.6																	
296.4	TOPSOIL: 250mm																
0.3	FILL: sand, some silt, brown, moist, loose		1	SS	6												
295.8																	
296.7	FILL: sandy silt to silty sand mixed with topsoil, brown, moist, compact		2	SS	15												
0.9	SAND: trace silt, trace gravel, brown to greyish brown, moist, compact																
			3	SS	18												
			4	SS	22												
			5	SS	33												
			6	SS	21												
			7	SS	22												
289.0																	
7.6	SILTY FINE SAND: trace clay, layer of silt, brown, wet, compact		8	SS	21												
288.4																	
8.2	END OF BOREHOLE Notes: 1) Borehole open and water level at 7.8m during drilling.																

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GPJ, SPCL, GDT, 7/15/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES + 3, x 3: Numbers refer to Sensitivity ○ ●=3% Strain at Failure

PROJECT: Geotechnical, Environmental and Hydrogeological Services
CLIENT: Tropical Land Developments Limited
PROJECT LOCATION: Mt Pleasant Road, Caledon, ON
DATUM: Geodetic
BH LOCATION: See Figure 6-1

DRILLING DATA
Method: Hollow Stem Augers
Diameter: 200mm
Date: Jun/02/2017
REF. NO.: SP17-212-10
ENCL NO.: 9

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)	
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40	60	80				100
290.9	TOPSOIL: 430mm		1	SS	8										
290.5	FILL: silty sand, trace clay, dark brown, moist, loose														
290.0	SAND: trace silt, brown, moist, very loose to compact		2	SS	4										
289.1	CLAYEY SILT TO SILTY CLAY: trace sand, brown, moist, stiff		3	SS	11										
287.9	SANDY SILT TO SILTY SAND: trace clay, trace gravel, brown, moist, compact to dense		4	SS	10										
			5	SS	13										
			6	SS	42										
			7	SS	37										
			8	SS	34										
			9	SS	25										
281.1	END OF BOREHOLE Notes: 1) Monitoring well installed in the borehole upon completion. 2) Water level in monitoring well at 8.8m on June 16, 2017.														

SPCL SOIL LOG SP17-212-10 - MOUNT PLEASANT, CALEDON, GP, J. SPCL, GDT, 7/15/17

GROUNDWATER ELEVATIONS
Measurement 1st 2nd 3rd 4th

GRAPH NOTES + 3, x 3: Numbers refer to Sensitivity ○ = 3% Strain at Failure

CLIENT NAME: MISC AGAT CLIENT ON, ON
ATTENTION TO: Sudhakar Kurli
PROJECT: SP17-212-30
AGAT WORK ORDER: 19T494518
WATER ANALYSIS REVIEWED BY: Nivine Basily, Inorganics Report Writer
DATE REPORTED: Jul 25, 2019
PAGES (INCLUDING COVER): 10
VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

***NOTES**

All samples will be disposed of within 30 days following analysis. Please contact the lab if you require additional sample storage time.

APPENDIX B



Certificate of Analysis

AGAT WORK ORDER: 19T494518

PROJECT: SP17-212-30

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: MISC AGAT CLIENT ON

ATTENTION TO: Sudhakar Kurli

SAMPLING SITE:

SAMPLED BY: Sudhakar Kurl

Water Quality Assessment (mg/L)

DATE RECEIVED: 2019-07-18

DATE REPORTED: 2019-07-25

Parameter	Unit	20190717-001-			20190717-002-			20190717-003-		
		SAMPLE DESCRIPTION: MW4			MW2			MW1		
		SAMPLE TYPE: Water			Water			Water		
		DATE SAMPLED: 2019-07-17			2019-07-17			2019-07-17		
		G / S: A	G / S: B	RDL	362226	RDL	362272	RDL	362273	
Electrical Conductivity	µS/cm			2	423	2	511	2	691	
pH	pH Units		6.5-8.5	NA	7.95	NA	7.91	NA	7.84	
Saturation pH (Calculated)					7.28		7.16		7.01	
Langelier Index (Calculated)					0.67		0.75		0.83	
Total Hardness (as CaCO ₃) (Calculated)	mg/L		80-100	0.5	202	0.5	232	0.5	321	
Total Dissolved Solids	mg/L		500	20	222[<B]	20	314[<B]	20	500[B]	
Alkalinity (as CaCO ₃)	mg/L		30-500	5	176	5	214	5	219	
Bicarbonate (as CaCO ₃)	mg/L			5	176	5	214	5	219	
Carbonate (as CaCO ₃)	mg/L			5	<5	5	<5	5	<5	
Hydroxide (as CaCO ₃)	mg/L			5	<5	5	<5	5	<5	
Fluoride	mg/L	1.5		0.05	<0.05[<A]	0.05	<0.05[<A]	0.10	<0.10[<A]	
Chloride	mg/L		250	0.10	5.95[<B]	0.10	8.84[<B]	0.20	7.18[<B]	
Nitrate as N	mg/L	10.0		0.05	8.64[<A]	0.05	0.49[<A]	0.10	33.1[>A]	
Nitrite as N	mg/L	1.0		0.05	0.27[<A]	0.05	<0.05[<A]	0.10	<0.10[<A]	
Bromide	mg/L			0.05	<0.05	0.05	<0.05	0.10	<0.10	
Sulphate	mg/L		500	0.10	11.5[<B]	0.10	47.0[<B]	0.20	12.5[<B]	
Ortho Phosphate as P	mg/L			0.10	<0.10	0.10	<0.10	0.20	<0.20	
Ammonia as N	mg/L			0.02	<0.02	0.02	<0.02	0.02	<0.02	
Total Phosphorus	mg/L			0.02	1.21	0.02	0.40	0.02	0.93	
Total Organic Carbon	mg/L			0.5	3.1	0.5	1.5	0.5	2.9	
Colour	TCU		5	5	<5[<B]	5	<5[<B]	5	<5[<B]	
Turbidity	NTU		5	3.0	29700[>B]	0.5	4210[>B]	0.5	7480[>B]	
Calcium	mg/L			0.05	73.2	0.05	77.9	0.05	121	
Magnesium	mg/L			0.05	4.56	0.05	9.16	0.05	4.69	
Sodium	mg/L	20	200	0.05	3.12[<A]	0.05	3.28[<A]	0.05	3.32[<A]	
Potassium	mg/L			0.05	1.55	0.05	11.3	0.05	5.86	
Aluminum	mg/L		0.1	0.004	0.802[>B]	0.004	0.719[>B]	0.004	2.30[>B]	
Antimony	mg/L	0.006		0.003	<0.003[<A]	0.003	<0.003[<A]	0.003	<0.003[<A]	

Certified By:

Divine Basily



Certificate of Analysis

AGAT WORK ORDER: 19T494518

PROJECT: SP17-212-30

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: MISC AGAT CLIENT ON

ATTENTION TO: Sudhakar Kurli

SAMPLING SITE:

SAMPLED BY: Sudhakar Kurl

Water Quality Assessment (mg/L)

DATE RECEIVED: 2019-07-18

DATE REPORTED: 2019-07-25

Parameter	Unit	20190717-001-				20190717-002-		20190717-003-	
		SAMPLE DESCRIPTION: MW4				MW2		MW1	
		SAMPLE TYPE: Water				Water		Water	
		DATE SAMPLED: 2019-07-17				2019-07-17		2019-07-17	
		G / S: A	G / S: B	RDL	362226	RDL	362272	RDL	362273
Arsenic	mg/L	0.025		0.003	<0.003[<A]	0.003	<0.003[<A]	0.003	<0.003[<A]
Barium	mg/L	1		0.002	0.139[<A]	0.002	0.069[<A]	0.002	0.109[<A]
Beryllium	mg/L			0.001	<0.001	0.001	<0.001	0.001	<0.001
Boron	mg/L	5		0.010	0.031[<A]	0.010	0.033[<A]	0.010	0.031[<A]
Cadmium	mg/L	0.005		0.001	<0.001[<A]	0.001	<0.001[<A]	0.001	<0.001[<A]
Chromium	mg/L	0.05		0.003	<0.003[<A]	0.003	<0.003[<A]	0.003	0.004[<A]
Cobalt	mg/L			0.001	0.006	0.001	0.002	0.001	0.006
Copper	mg/L		1	0.003	<0.003[<B]	0.003	0.004[<B]	0.003	0.010[<B]
Iron	mg/L		0.3	0.010	0.654[>B]	0.010	1.31[>B]	0.010	2.65[>B]
Lead	mg/L	0.01		0.001	<0.001[<A]	0.001	0.002[<A]	0.001	0.007[<A]
Manganese	mg/L		0.05	0.002	2.40[>B]	0.002	0.230[>B]	0.002	0.834[>B]
Mercury	mg/L	0.001		0.0001	<0.0001[<A]	0.0001	<0.0001[<A]	0.0001	<0.0001[<A]
Molybdenum	mg/L			0.002	<0.002	0.002	<0.002	0.002	<0.002
Nickel	mg/L			0.003	<0.003	0.003	<0.003	0.003	<0.003
Selenium	mg/L	0.05		0.004	<0.004[<A]	0.004	<0.004[<A]	0.004	<0.004[<A]
Silver	mg/L			0.002	<0.002	0.002	<0.002	0.002	<0.002
Strontium	mg/L			0.005	1.71	0.005	0.297	0.005	0.476
Thallium	mg/L			0.006	<0.006	0.006	<0.006	0.006	<0.006
Tin	mg/L			0.002	<0.002	0.002	<0.002	0.002	<0.002
Titanium	mg/L			0.002	0.030	0.002	0.017	0.002	0.039
Tungsten	mg/L			0.010	<0.010	0.010	<0.010	0.010	<0.010
Uranium	mg/L	0.02		0.002	<0.002[<A]	0.002	<0.002[<A]	0.002	<0.002[<A]
Vanadium	mg/L			0.002	<0.002	0.002	0.003	0.002	0.005
Zinc	mg/L		5	0.005	0.008[<B]	0.005	0.008[<B]	0.005	0.020[<B]
Zirconium	mg/L			0.004	<0.004	0.004	<0.004	0.004	<0.004
% Difference/ Ion Balance (Calculated)	%			NA	4.04	NA	4.38	NA	3.43

Certified By:

Divine Basily



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 19T494518

PROJECT: SP17-212-30

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: MISC AGAT CLIENT ON

SAMPLING SITE:

ATTENTION TO: Sudhakar Kurli

SAMPLED BY: Sudhakar Kurl

Water Quality Assessment (mg/L)

DATE RECEIVED: 2019-07-18

DATE REPORTED: 2019-07-25

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: A Refers to Ontario Drinking Water Quality Standards. Na value is derived from O. Reg. 248, B Refers to Ontario Drinking Water Quality Standards - Aesthetic Objectives and Operational Guidelines

Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

362226 Elevated RDL indicates the degree of sample dilution prior to the analysis in order to keep analytes within the calibration range of the instrument and to reduce matrix interference.

362273 Elevated RDL indicates the degree of sample dilution prior to the analysis in order to keep analytes within the calibration range of the instrument and to reduce matrix interference.

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:

Divine Basily



Guideline Violation

AGAT WORK ORDER: 19T494518

PROJECT: SP17-212-30

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
<http://www.agatlabs.com>

CLIENT NAME: MISC AGAT CLIENT ON

ATTENTION TO: Sudhakar Kurli

SAMPLEID	SAMPLE TITLE	GUIDELINE	ANALYSIS PACKAGE	PARAMETER	UNIT	GUIDEVALUE	RESULT
362226	20190717-001-MW4	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Aluminum	mg/L	0.1	0.802
362226	20190717-001-MW4	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Iron	mg/L	0.3	0.654
362226	20190717-001-MW4	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Manganese	mg/L	0.05	2.40
362226	20190717-001-MW4	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Total Hardness (as CaCO3) (Calculate	mg/L	80-100	202
362226	20190717-001-MW4	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Turbidity	NTU	5	29700
362272	20190717-002-MW2	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Aluminum	mg/L	0.1	0.719
362272	20190717-002-MW2	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Iron	mg/L	0.3	1.31
362272	20190717-002-MW2	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Manganese	mg/L	0.05	0.230
362272	20190717-002-MW2	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Total Hardness (as CaCO3) (Calculated)	mg/L	80-100	232
362272	20190717-002-MW2	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Turbidity	NTU	5	4210
362273	20190717-003-MW1	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Aluminum	mg/L	0.1	2.30
362273	20190717-003-MW1	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Iron	mg/L	0.3	2.65
362273	20190717-003-MW1	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Manganese	mg/L	0.05	0.834
362273	20190717-003-MW1	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Total Hardness (as CaCO3) (Calculate	mg/L	80-100	321
362273	20190717-003-MW1	O.Reg. 169(mg/L)AO&OG	Water Quality Assessment (mg/L)	Turbidity	NTU	5	7480
362273	20190717-003-MW1	O.Reg.169/03(mg/L)	Water Quality Assessment (mg/L)	Nitrate as N	mg/L	10.0	33.1

Quality Assurance

CLIENT NAME: MISC AGAT CLIENT ON
AGAT WORK ORDER: 19T494518
PROJECT: SP17-212-30
ATTENTION TO: Sudhakar Kurli
SAMPLING SITE:
SAMPLED BY: Sudhakar Kurl

Water Analysis															
RPT Date: Jul 25, 2019			DUPLICATE				Method Blank	REFERENCE MATERIAL			METHOD BLANK SPIKE		MATRIX SPIKE		
PARAMETER	Batch	Sample Id	Dup #1	Dup #2	RPD	Measured Value		Acceptable Limits		Recovery	Acceptable Limits		Recovery	Acceptable Limits	
								Lower	Upper		Lower	Upper		Lower	Upper

Water Quality Assessment (mg/L)

Electrical Conductivity	360471		940	942	0.2%	< 2	108%	80%	120%						
pH	360471		8.10	8.00	1.2%	NA	100%	90%	110%						
Total Dissolved Solids	362801		164	162	1.2%	< 20	98%	80%	120%						
Alkalinity (as CaCO3)	360471		358	359	0.3%	< 5	98%	80%	120%						
Bicarbonate (as CaCO3)	360471		358	359	0.2%	< 5									
Carbonate (as CaCO3)	360471		<5	<5	NA	< 5									
Hydroxide (as CaCO3)	360471		<5	<5	NA	< 5									
Fluoride	357185		<0.25	<0.25	NA	< 0.05	99%	90%	110%	96%	90%	110%	108%	85%	115%
Chloride	357185		103	103	0.0%	< 0.10	91%	90%	110%	101%	90%	110%	111%	85%	115%
Nitrate as N	357185		0.99	1.00	NA	< 0.05	94%	90%	110%	102%	90%	110%	108%	85%	115%
Nitrite as N	357185		<0.25	<0.25	NA	< 0.05	NA	90%	110%	106%	90%	110%	108%	85%	115%
Bromide	357185		<0.25	<0.25	NA	< 0.05	93%	90%	110%	100%	90%	110%	105%	85%	115%
Sulphate	357185		128	130	1.0%	< 0.10	95%	90%	110%	101%	90%	110%	100%	85%	115%
Ortho Phosphate as P	357185		<0.50	<0.50	NA	< 0.10	97%	90%	110%	102%	90%	110%	111%	80%	120%
Ammonia as N	363013		<0.02	<0.02	NA	< 0.02	93%	90%	110%	101%	90%	110%	102%	70%	130%
Total Phosphorus	362160		0.03	<0.02	NA	< 0.02	100%	80%	120%	99%	90%	110%	101%	70%	130%
Total Organic Carbon	360517		1.3	1.2	NA	< 0.5	91%	90%	110%	92%	90%	110%	81%	80%	120%
Colour	362741		29	30	2.7%	< 5	102%	90%	110%						
Turbidity	362226	362226	29700	29800	0.6%	< 0.5	98%	90%	110%						
Calcium	362226	362226	73.2	74.3	1.5%	< 0.05	97%	90%	110%	98%	90%	110%	123%	70%	130%
Magnesium	362226	362226	4.56	4.54	0.4%	< 0.05	98%	90%	110%	99%	90%	110%	117%	70%	130%
Sodium	362226	362226	3.12	3.14	0.7%	< 0.05	96%	90%	110%	96%	90%	110%	119%	70%	130%
Potassium	362226	362226	1.55	1.57	1.1%	< 0.05	97%	90%	110%	97%	90%	110%	120%	70%	130%
Aluminum	362160		<0.004	<0.004	NA	< 0.004	94%	90%	110%	91%	90%	110%	104%	70%	130%
Antimony	362160		<0.003	<0.003	NA	< 0.003	100%	90%	110%	95%	90%	110%	118%	70%	130%
Arsenic	362160		<0.003	<0.003	NA	< 0.003	100%	90%	110%	99%	90%	110%	119%	70%	130%
Barium	362160		0.012	0.011	8.7%	< 0.002	106%	90%	110%	106%	90%	110%	121%	70%	130%
Beryllium	362160		<0.001	<0.001	NA	< 0.001	101%	90%	110%	99%	90%	110%	125%	70%	130%
Boron	362160		0.310	0.322	3.8%	< 0.010	107%	90%	110%	102%	90%	110%	100%	70%	130%
Cadmium	362160		<0.001	<0.001	NA	< 0.001	99%	90%	110%	101%	90%	110%	104%	70%	130%
Chromium	362160		<0.003	<0.003	NA	< 0.003	100%	90%	110%	103%	90%	110%	104%	70%	130%
Cobalt	362160		<0.001	<0.001	NA	< 0.001	103%	90%	110%	103%	90%	110%	130%	70%	130%
Copper	362160		<0.003	<0.003	NA	< 0.003	100%	90%	110%	105%	90%	110%	128%	70%	130%
Iron	362160		<0.010	<0.010	NA	< 0.010	110%	90%	110%	102%	90%	110%	114%	70%	130%
Lead	362160		<0.001	<0.001	NA	< 0.001	100%	90%	110%	101%	90%	110%	124%	70%	130%
Manganese	362160		0.020	0.020	0.0%	< 0.002	107%	90%	110%	106%	90%	110%	107%	70%	130%
Mercury	360517		<0.0001	<0.0001	NA	< 0.0001	101%	90%	110%	101%	80%	120%	101%	80%	120%
Molybdenum	362160		0.011	0.011	0.0%	< 0.002	104%	90%	110%	101%	90%	110%	117%	70%	130%
Nickel	362160		<0.003	<0.003	NA	< 0.003	108%	90%	110%	109%	90%	110%	106%	70%	130%

Quality Assurance

CLIENT NAME: MISC AGAT CLIENT ON
 PROJECT: SP17-212-30
 SAMPLING SITE:

AGAT WORK ORDER: 19T494518
 ATTENTION TO: Sudhakar Kurli
 SAMPLED BY: Sudhakar Kurl

Water Analysis (Continued)

RPT Date: Jul 25, 2019			DUPLICATE				Method Blank	REFERENCE MATERIAL			METHOD BLANK SPIKE			MATRIX SPIKE		
PARAMETER	Batch	Sample Id	Dup #1	Dup #2	RPD	Measured Value		Acceptable Limits		Recovery	Acceptable Limits		Recovery	Acceptable Limits		
								Lower	Upper		Lower	Upper		Lower	Upper	
Selenium	362160		<0.004	<0.004	NA	< 0.004	103%	90%	110%	103%	90%	110%	128%	70%	130%	
Silver	362160		<0.002	<0.002	NA	< 0.002	102%	90%	110%	108%	90%	110%	105%	70%	130%	
Strontium	362160		16.7	16.7	0.0%	< 0.005	100%	90%	110%	101%	90%	110%	114%	70%	130%	
Thallium	362160		<0.006	<0.006	NA	< 0.006	103%	90%	110%	106%	90%	110%	129%	70%	130%	
Tin	362160		<0.002	<0.002	NA	< 0.002	105%	90%	110%	101%	90%	110%	125%	70%	130%	
Titanium	362160		0.003	0.004	NA	< 0.002	104%	90%	110%	100%	90%	110%	124%	70%	130%	
Tungsten	362160		<0.010	<0.010	NA	< 0.010	96%	90%	110%	100%	90%	110%	123%	70%	130%	
Uranium	362160		<0.002	<0.002	NA	< 0.002	106%	90%	110%	91%	90%	110%	106%	70%	130%	
Vanadium	362160		<0.002	<0.002	NA	< 0.002	103%	90%	110%	104%	90%	110%	103%	70%	130%	
Zinc	362160		<0.005	<0.005	NA	< 0.005	93%	90%	110%	94%	90%	110%	119%	70%	130%	
Zirconium	362160		<0.004	<0.004	NA	< 0.004	100%	90%	110%	99%	90%	110%	118%	70%	130%	

Comments: NA signifies Not Applicable.
 Duplicate Qualifier: As the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Certified By: _____

Divine Basily

Method Summary

CLIENT NAME: MISC AGAT CLIENT ON
AGAT WORK ORDER: 19T494518
PROJECT: SP17-212-30
ATTENTION TO: Sudhakar Kurli
SAMPLING SITE:
SAMPLED BY: Sudhakar Kurl

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Water Analysis			
Electrical Conductivity	INOR-93-6000	SM 2510 B	PC TITRATE
pH	INOR-93-6000	SM 4500-H+ B	PC TITRATE
Saturation pH (Calculated)		SM 2320 B	CALCULATION
Langelier Index (Calculated)		SM 2330B	CALCULATION
Total Hardness (as CaCO ₃) (Calculated)	MET-93-6105	EPA SW-846 6010C & 200.7	CALCULATION
Total Dissolved Solids	INOR-93-6028	SM 2540 C	BALANCE
Alkalinity (as CaCO ₃)	INOR-93-6000	SM 2320 B	PC TITRATE
Bicarbonate (as CaCO ₃)	INOR-93-6000	SM 2320 B	PC TITRATE
Carbonate (as CaCO ₃)	INOR-93-6000	SM 2320 B	PC TITRATE
Hydroxide (as CaCO ₃)	INOR-93-6000	SM 2320 B	PC TITRATE
Fluoride	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Chloride	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Nitrate as N	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Nitrite as N	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Bromide	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Sulphate	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Ortho Phosphate as P	INOR-93-6004	SM 4110 B	ION CHROMATOGRAPH
Ammonia as N	INOR-93-6059	SM 4500-NH ₃ H	LACHAT FIA
Total Phosphorus	INOR-93-6057	QuikChem 10-115-01-3-A & SM 4500-P I	LACHAT FIA
Total Organic Carbon	INOR-93-6049	EPA 415.1 & SM 5310	SHIMADZU CARBON ANALYZER
Colour	INOR-93-6046	SM 2120 B	SPECTROPHOTOMETER
Turbidity	INOR-93-6044	SM 2130 B	NEPHELOMETER
Calcium	MET-93-6105	EPA SW-846 6010C & 200.7	ICP/OES
Magnesium	MET-93-6105	EPA SW-846 6010C & 200.7	ICP/OES
Sodium	MET-93-6105	EPA SW-846 6010C & 200.7	ICP/OES
Potassium	MET-93-6105	EPA SW-846 6010C & 200.7	ICP/OES
Aluminum	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Antimony	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Arsenic	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Barium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Beryllium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Boron	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Cadmium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Chromium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Cobalt	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Copper	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Iron	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Lead	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Manganese	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Mercury	MET-93-6100	EPA SW 846 7470 & 245.1	CVAAS
Molybdenum	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Nickel	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Selenium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Silver	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Strontium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Thallium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Tin	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Titanium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS

Method Summary

CLIENT NAME: MISC AGAT CLIENT ON

AGAT WORK ORDER: 19T494518

PROJECT: SP17-212-30

ATTENTION TO: Sudhakar Kurli

SAMPLING SITE:

SAMPLED BY: Sudhakar Kurl

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Tungsten	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Uranium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Vanadium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Zinc	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
Zirconium	MET-93-6103	EPA SW-846 6020A & 200.8	ICP-MS
% Difference/ Ion Balance (Calculated)		SM 1030 E	CALCULATION



Laboratory Use Only

Work Order #: 19TY94518

Cooler Quantity: 1 cool

Arrival Temperatures: 3.7 3.5 3.5
1.00 2.5 2.7 2.8

Custody Seal Intact: Yes No N/A

Notes:

Chain of Custody Record

If this is a Drinking Water sample, please use Drinking Water Chain of Custody Form (potable water consumed by humans)

Report Information:

Company: SRATI & PARTNERS
Contact: SUDHAKAR KURLI
Address: 12700 Keele St
King City, ON
647-554-9057 Fax:
Phone: 647-554-9057
Reports to be sent to:
1. Email: sudhakar@sirati.ca
2. Email:

Regulatory Requirements: No Regulatory Requirement

(Please check all applicable boxes)

<input type="checkbox"/> Regulation 153/04	<input type="checkbox"/> Sewer Use	<input type="checkbox"/> Regulation 558
Table <small>Indicate One</small>	<input type="checkbox"/> Sanitary	<input type="checkbox"/> CCME
<input type="checkbox"/> Ind/Com	<input type="checkbox"/> Storm	<input type="checkbox"/> Prov. Water Quality Objectives (PWQO)
<input type="checkbox"/> Res/Park	Region <small>Indicate One</small>	<input type="checkbox"/> Other
<input type="checkbox"/> Agriculture		
Soil Texture <small>(Check One)</small>		
<input type="checkbox"/> Coarse		
<input type="checkbox"/> Fine	<input type="checkbox"/> MISA	<small>Indicate One</small>

Turnaround Time (TAT) Required:

Regular TAT 5 to 7 Business Days

Rush TAT (Rush Surcharges Apply)

3 Business Days 2 Business Days Next Business Day

OR Date Required (Rush Surcharges May Apply):

Please provide prior notification for rush TAT
*TAT is exclusive of weekends and statutory holidays

For 'Same Day' analysis, please contact your AGAT CPM

Project Information:

Project: SP17-212-30
Site Location: 0 HE Pleasant Rd, Caledon
Sampled By: SUDHAKAR KURLI
AGAT Quote #: _____ PO: _____

Please note: If quotation number is not provided, client will be billed full price for analysis.

Invoice Information:

Bill To Same: Yes No

Company: _____
Contact: _____
Address: _____
Email: _____

Is this submission for a Record of Site Condition?

Yes No

Report Guideline on Certificate of Analysis

Yes No

Sample Matrix Legend

- B Biota
- GW Ground Water
- O Oil
- P Paint
- S Soil
- SD Sediment
- SW Surface Water

Field Filtered - Metals, Hg, CrVI

Sample Identification	Date Sampled	Time Sampled	# of Containers	Sample Matrix	Comments/ Special Instructions	Y / N	Metals and Inorganics	0. Reg 153	Full Metals Scan	Regulation/Custom Metals	Nutrients:	Volatiles:	PHCs F1 - F4	ABNs	PAHs	PCBs:	Organochlorine Pesticides	TOLP:	Sewer Use	Potentially Hazardous or High Concentration (Y/N)	
20190717-001-MW4	7/17	11.00	5	GW		22	<input type="checkbox"/> All Metals <input type="checkbox"/> 153 Metals (excl. Hydrides) <input type="checkbox"/> Hydride Metals <input type="checkbox"/> 153 Metals (incl. Hydrides)				ORPs: <input type="checkbox"/> B-HWS <input type="checkbox"/> Cl <input type="checkbox"/> CN <input type="checkbox"/> Cr ⁶⁺ <input type="checkbox"/> EC <input type="checkbox"/> FOC <input type="checkbox"/> Hg <input type="checkbox"/> pH <input type="checkbox"/> SAR	<input type="checkbox"/> TP <input type="checkbox"/> NH ₃ <input type="checkbox"/> TKN <input type="checkbox"/> NO ₃ <input type="checkbox"/> NO ₂ <input type="checkbox"/> NO ₃ +NO ₂	<input type="checkbox"/> VOC <input type="checkbox"/> BTEX <input type="checkbox"/> THM			<input type="checkbox"/> Total <input type="checkbox"/> Aroclors	<input type="checkbox"/> M&I <input type="checkbox"/> VOCs <input type="checkbox"/> ABNs <input type="checkbox"/> B(a)P <input type="checkbox"/> PCBs	<input type="checkbox"/> Sewer Use			
20190717-002-MW2	7/17	11.45	5	GW		22															
20190717-003-MW1	7/17	12.30	5	GW		22															

Samples Relinquished By (Print Name and Sign): <u>SUDHAKAR KURLI</u>	Date: <u>07/18</u>	Time:	Samples Received By (Print Name and Sign): <u>[Signature]</u>	Date: <u>July 18/19</u>	Time: <u>9:10</u>
Samples Relinquished By (Print Name and Sign): <u>[Signature]</u>	Date: <u>July 18/19</u>	Time: <u>5:29</u>	Samples Received By (Print Name and Sign):	Date:	Time:
Samples Relinquished By (Print Name and Sign):	Date:	Time:	Samples Received By (Print Name and Sign):	Date:	Time:



Sirati & Partners Consultants Ltd.
ATTN: SUDHAKAR KURLI
12700 Keele St
King City ON L7B 1H5

Date Received: 19-AUG-19
Report Date: 22-AUG-19 13:14 (MT)
Version: FINAL

Client Phone: 905-833-1582

Certificate of Analysis

Lab Work Order #: L2331489
Project P.O. #: SP17-212-30
Job Reference: SP17-212-30
C of C Numbers: 17-826240
Legal Site Desc:

Rick Hawthorne
Account Manager

[This report shall not be reproduced except in full without the written authority of the Laboratory.]

ADDRESS: 60 Northland Road, Unit 1, Waterloo, ON N2V 2B8 Canada | Phone: +1 519 886 6910 | Fax: +1 519 886 9047
ALS CANADA LTD Part of the ALS Group An ALS Limited Company

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters	Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2331489-1 20190816-MW4-001 Sampled By: SK on 16-AUG-19 @ 09:00 Matrix: WATER Anions and Nutrients Nitrate (as N)	4.29		0.020	mg/L		21-AUG-19	R4764382
L2331489-2 20190816-MW1-002 Sampled By: SK on 16-AUG-19 @ 09:30 Matrix: WATER Anions and Nutrients Nitrate (as N)	34.0		0.020	mg/L		21-AUG-19	R4764382
L2331489-3 20190816-MW2-003 Sampled By: SK on 16-AUG-19 @ 10:15 Matrix: WATER Anions and Nutrients Nitrate (as N)	0.642		0.020	mg/L		21-AUG-19	R4764382

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

Reference Information

Test Method References:

ALS Test Code	Matrix	Test Description	Method Reference**
EC-SCREEN-WT	Water	Conductivity Screen (Internal Use Only)	APHA 2510
Qualitative analysis of conductivity where required during preparation of other tests - e.g. TDS, metals, etc.			
NO3-IC-WT	Water	Nitrate in Water by IC	EPA 300.1 (mod)
Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.			

** ALS test methods may incorporate modifications from specified reference methods to improve performance.

The last two letters of the above test code(s) indicate the laboratory that performed analytical analysis for that test. Refer to the list below:

Laboratory Definition Code	Laboratory Location
WT	ALS ENVIRONMENTAL - WATERLOO, ONTARIO, CANADA

Chain of Custody Numbers:

17-826240

GLOSSARY OF REPORT TERMS

Surrogates are compounds that are similar in behaviour to target analyte(s), but that do not normally occur in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery. In reports that display the D.L. column, laboratory objectives for surrogates are listed there.

mg/kg - milligrams per kilogram based on dry weight of sample

mg/kg wwt - milligrams per kilogram based on wet weight of sample

mg/kg lwt - milligrams per kilogram based on lipid weight of sample

mg/L - unit of concentration based on volume, parts per million.

< - Less than.

D.L. - The reporting limit.

N/A - Result not available. Refer to qualifier code and definition for explanation.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

Analytical results in unsigned test reports with the DRAFT watermark are subject to change, pending final QC review.



Quality Control Report

Workorder: L2331489

Report Date: 22-AUG-19

Page 1 of 2

Client: Sirati & Partners Consultants Ltd.
12700 Keele St
King City ON L7B 1H5

Contact: SUDHAKAR KURLI

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
NO3-IC-WT	Water							
Batch	R4764382							
WG3138919-4	DUP	WG3138919-3						
Nitrate (as N)		2.24	2.24		mg/L	0.0	20	21-AUG-19
WG3138919-2	LCS							
Nitrate (as N)			102.0		%		90-110	21-AUG-19
WG3138919-1	MB							
Nitrate (as N)			<0.020		mg/L		0.02	21-AUG-19
WG3138919-5	MS	WG3138919-3						
Nitrate (as N)			102.1		%		75-125	21-AUG-19

Quality Control Report

Workorder: L2331489

Report Date: 22-AUG-19

Client: Sirati & Partners Consultants Ltd.
12700 Keele St
King City ON L7B 1H5

Page 2 of 2

Contact: SUDHAKAR KURLI

Legend:

Limit	ALS Control Limit (Data Quality Objectives)
DUP	Duplicate
RPD	Relative Percent Difference
N/A	Not Available
LCS	Laboratory Control Sample
SRM	Standard Reference Material
MS	Matrix Spike
MSD	Matrix Spike Duplicate
ADE	Average Desorption Efficiency
MB	Method Blank
IRM	Internal Reference Material
CRM	Certified Reference Material
CCV	Continuing Calibration Verification
CVS	Calibration Verification Standard
LCSD	Laboratory Control Sample Duplicate

Sample Parameter Qualifier Definitions:

Qualifier	Description
RPD-NA	Relative Percent Difference Not Available due to result(s) being less than detection limit.

Hold Time Exceedances:

All test results reported with this submission were conducted within ALS recommended hold times.

ALS recommended hold times may vary by province. They are assigned to meet known provincial and/or federal government requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by the US EPA, APHA Standard Methods, or Environment Canada (where available). For more information, please contact ALS.

The ALS Quality Control Report is provided to ALS clients upon request. ALS includes comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against pre-determined data quality objectives to provide confidence in the accuracy of associated test results.

Please note that this report may contain QC results from anonymous Sample Duplicates and Matrix Spikes that do not originate from this Work Order.



Chain of Custody (COC) / Analytical Request Form



L2331489-COFC

COC Number: 17 - 826240

Handwritten initials

www.alsglobal.com

Canada Toll Free: 1 800 668 9878

Page of

Report To Contact and company name below will appear on the final report		Report Format / Distribution			Select Service Level Below - Contact your AM to confirm all E&P TATs (surcharges may apply)																								
Company: SIRATI & PARTNERS		Select Report Format: <input checked="" type="checkbox"/> PDF <input checked="" type="checkbox"/> EXCEL <input type="checkbox"/> EDD (DIGITAL)			Regular [R] <input checked="" type="checkbox"/> Standard TAT if received by 3 pm - business days - no surcharges apply																								
Contact: SUDHAKAR KURLI		Quality Control (QC) Report with Report <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO			Priority (Business Days) 4 day [P4-20%] <input type="checkbox"/> 3 day [P3-25%] <input type="checkbox"/> 2 day [P2-50%] <input type="checkbox"/>																								
Phone: 647.554.9057		<input type="checkbox"/> Compare Results to Criteria on Report - provide details below if box checked			EMERGENCY 1 Business day [E - 100%] <input type="checkbox"/>																								
Street: 12700 Keele St		Select Distribution: <input type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX			Same Day, Weekend or Statutory holiday [E2 -200% (Laboratory opening fees may apply)] <input type="checkbox"/>																								
City/Province: KING CITY, ON		Email 1 or Fax: Sudhakara@sirati.ca			Date and Time Required for all E&P TATs: dd-mmm-yy hh:mm																								
Postal Code:		Email 2: bjing@sirati.ca			For tests that can not be performed according to the service level selected, you will be contacted.																								
Invoice To: Same as Report To <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		Email 3: Sudhakara@sirati.ca			Analysis Request																								
Copy of Invoice with Report <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		Select Invoice Distribution: <input type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX			Indicate Filtered (F), Preserved (P) or Filtered and Preserved (F/P) below																								
Company: SIRATI & PARTNERS		Oil and Gas Required Fields (client use)			<table border="1"> <tr><td colspan="5">NUMBER OF CONTAINERS</td></tr> <tr><td colspan="5">NITRATE AS NO3</td></tr> <tr><td colspan="5">SAMPLES ON HOLD</td></tr> <tr><td colspan="5">SUSPECTED HAZARD (see Special Instructions)</td></tr> </table>					NUMBER OF CONTAINERS					NITRATE AS NO3					SAMPLES ON HOLD					SUSPECTED HAZARD (see Special Instructions)				
NUMBER OF CONTAINERS																													
NITRATE AS NO3																													
SAMPLES ON HOLD																													
SUSPECTED HAZARD (see Special Instructions)																													
Project Information		AFE/Cost Center: PO#																											
ALS Account # / Quote #: 25609		Major/Minor Code: Routing Code:																											
Job #: SP17-212-30		Requisitioner:																											
PO / AFE:		Location:																											
LSD:		ALS Lab Work Order # (lab use only): L2331489 RD			ALS Contact: RICK Sampler: SUDHAKAR																								
ALS Sample # (lab use only)	Sample Identification and/or Coordinates (This description will appear on the report)	Date (dd-mmm-yy)	Time (hh:mm)	Sample Type																									
	20190816-MW4-001	16-Aug-19	9AM	GW	1																								
	20190816-MW1-002	"	9:30AM	GW	1																								
	20190816-MW2-003	"	10:15AM	GW	1																								
Drinking Water (DW) Samples¹ (client use)		Special Instructions / Specify Criteria to add on report by clicking on the drop-down list below (electronic COC only)			SAMPLE CONDITION AS RECEIVED (lab use only)																								
Are samples taken from a Regulated DW System? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO					Frozen <input type="checkbox"/> SIF Observations Yes <input type="checkbox"/> No <input type="checkbox"/>																								
Are samples for human consumption/ use? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO					Ice Packs <input type="checkbox"/> Ice Cubes <input type="checkbox"/> Custody seal intact Yes <input type="checkbox"/> No <input type="checkbox"/>																								
					Cooling Initiated <input type="checkbox"/>																								
					INITIAL COOLER TEMPERATURES °C																								
					FINAL COOLER TEMPERATURES °C																								
					7.6																								
SHIPMENT RELEASE (client use)		INITIAL SHIPMENT RECEPTION (lab use only)			FINAL SHIPMENT RECEPTION (lab use only)																								
Released by: SUDHAKAR KURLI	Date:	Time:	Received by:	Date:	Time:	Received by:	Date:	Time:	Received by:	Date:	Time:																		
							19 Aug 19/19	19:30																					

REFER TO BACK PAGE FOR ALS LOCATIONS AND SAMPLING INFORMATION

WHITE - LABORATORY COPY YELLOW - CLIENT COPY

1. If any water samples are taken from a Regulated Drinking Water (DW) System, please submit using an Authorized DW COC form.




Sirati & Partners Consultants Ltd.
ATTN: SUDHAKAR KURLI
12700 Keele St
King City ON L7B 1H5

Date Received: 19-AUG-19
Report Date: 22-AUG-19 13:14 (MT)
Version: FINAL

Client Phone: 905-833-1582

Certificate of Analysis

Lab Work Order #: L2331489
Project P.O. #: SP17-212-30
Job Reference: SP17-212-30
C of C Numbers: 17-826240
Legal Site Desc:



Rick Hawthorne
Account Manager

[This report shall not be reproduced except in full without the written authority of the Laboratory.]

ADDRESS: 60 Northland Road, Unit 1, Waterloo, ON N2V 2B8 Canada | Phone: +1 519 886 6910 | Fax: +1 519 886 9047
ALS CANADA LTD Part of the ALS Group An ALS Limited Company

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters	Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2331489-1 20190816-MW4-001 Sampled By: SK on 16-AUG-19 @ 09:00 Matrix: WATER Anions and Nutrients Nitrate (as N)	4.29		0.020	mg/L		21-AUG-19	R4764382
L2331489-2 20190816-MW1-002 Sampled By: SK on 16-AUG-19 @ 09:30 Matrix: WATER Anions and Nutrients Nitrate (as N)	34.0		0.020	mg/L		21-AUG-19	R4764382
L2331489-3 20190816-MW2-003 Sampled By: SK on 16-AUG-19 @ 10:15 Matrix: WATER Anions and Nutrients Nitrate (as N)	0.642		0.020	mg/L		21-AUG-19	R4764382

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

Reference Information

Test Method References:

ALS Test Code	Matrix	Test Description	Method Reference**
EC-SCREEN-WT	Water	Conductivity Screen (Internal Use Only)	APHA 2510
Qualitative analysis of conductivity where required during preparation of other tests - e.g. TDS, metals, etc.			
NO3-IC-WT	Water	Nitrate in Water by IC	EPA 300.1 (mod)
Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.			

** ALS test methods may incorporate modifications from specified reference methods to improve performance.

The last two letters of the above test code(s) indicate the laboratory that performed analytical analysis for that test. Refer to the list below:

Laboratory Definition Code	Laboratory Location
WT	ALS ENVIRONMENTAL - WATERLOO, ONTARIO, CANADA

Chain of Custody Numbers:

17-826240

GLOSSARY OF REPORT TERMS

Surrogates are compounds that are similar in behaviour to target analyte(s), but that do not normally occur in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery. In reports that display the D.L. column, laboratory objectives for surrogates are listed there.

mg/kg - milligrams per kilogram based on dry weight of sample

mg/kg ww - milligrams per kilogram based on wet weight of sample

mg/kg lwt - milligrams per kilogram based on lipid weight of sample

mg/L - unit of concentration based on volume, parts per million.

< - Less than.

D.L. - The reporting limit.

N/A - Result not available. Refer to qualifier code and definition for explanation.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

Analytical results in unsigned test reports with the DRAFT watermark are subject to change, pending final QC review.



Quality Control Report

Workorder: L2331489

Report Date: 22-AUG-19

Page 1 of 2

Client: Sirati & Partners Consultants Ltd.
12700 Keele St
King City ON L7B 1H5

Contact: SUDHAKAR KURLI

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
NO3-IC-WT	Water							
Batch	R4764382							
WG3138919-4	DUP	WG3138919-3						
Nitrate (as N)		2.24	2.24		mg/L	0.0	20	21-AUG-19
WG3138919-2	LCS							
Nitrate (as N)			102.0		%		90-110	21-AUG-19
WG3138919-1	MB							
Nitrate (as N)			<0.020		mg/L		0.02	21-AUG-19
WG3138919-5	MS	WG3138919-3						
Nitrate (as N)			102.1		%		75-125	21-AUG-19

Quality Control Report

Workorder: L2331489

Report Date: 22-AUG-19

Client: Sirati & Partners Consultants Ltd.
12700 Keele St
King City ON L7B 1H5

Page 2 of 2

Contact: SUDHAKAR KURLI

Legend:

Limit	ALS Control Limit (Data Quality Objectives)
DUP	Duplicate
RPD	Relative Percent Difference
N/A	Not Available
LCS	Laboratory Control Sample
SRM	Standard Reference Material
MS	Matrix Spike
MSD	Matrix Spike Duplicate
ADE	Average Desorption Efficiency
MB	Method Blank
IRM	Internal Reference Material
CRM	Certified Reference Material
CCV	Continuing Calibration Verification
CVS	Calibration Verification Standard
LCSD	Laboratory Control Sample Duplicate

Sample Parameter Qualifier Definitions:

Qualifier	Description
RPD-NA	Relative Percent Difference Not Available due to result(s) being less than detection limit.

Hold Time Exceedances:

All test results reported with this submission were conducted within ALS recommended hold times.

ALS recommended hold times may vary by province. They are assigned to meet known provincial and/or federal government requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by the US EPA, APHA Standard Methods, or Environment Canada (where available). For more information, please contact ALS.

The ALS Quality Control Report is provided to ALS clients upon request. ALS includes comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against pre-determined data quality objectives to provide confidence in the accuracy of associated test results.


Please note that this report may contain QC results from anonymous Sample Duplicates and Matrix Spikes that do not originate from this Work Order.

APPENDIX C

SIRATI & PARTNERS

Geotechnical Hydrogeological & Environmental Solutions

Run Time: 2017-07-25 11:46:17



Date	PET	P	p-PET	soil Moisture	AET	PET-AET	Snow Storage	surplus	Rototal
Jan-62	6.7	17.5	-6.5	145.1	5.1	1.6	17.3	0	12.7
Feb-62	7.7	4.6	-7.5	139.6	5.6	2.1	21.8	0	6.4
Mar-62	16.2	3.8	-8.8	133.5	13.5	2.7	18.2	0	3.3
Apr-62	35.9	31.5	3.1	136.6	35.9	0	9.1	0	3.2
May-62	74.8	58.4	-10.2	129.6	71.5	3.2	0	0	3.7
Jun-62	90.4	50	-42.9	101.8	75.3	15.1	0	0	2.9
Jul-62	93.4	90.9	-7.1	98.2	90	3.5	0	0	4.7
Aug-62	84	37.3	-48.5	74.4	59.3	24.7	0	0	2
Sep-62	45.6	86.4	36.4	110.8	45.6	0	0	0	4.4
Oct-62	29.5	125.7	89.9	200	29.5	0	0	0.8	6.7
Nov-62	13.2	105.9	75.6	200	13.2	0	12.9	75.6	42.2
Dec-62	7.7	38.9	8.3	200	7.7	0	35.3	8.3	23.7
Jan-63	6.3	1	-6.3	193.7	6.3	0	36.3	0	11.6
Feb-63	6.9	1.5	-6.9	187	6.6	0.2	37.8	0	5.8
Mar-63	17.9	38.1	19.5	200	17.9	0	37.5	6.5	7.3
Apr-63	35	46.2	27.6	200	35	0	18.7	27.6	19.2
May-63	57.3	94.2	41.6	200	57.3	0	9.4	41.6	33.9
Jun-63	92.6	14.5	-69.5	130.5	92.6	0	0	0	15.3
Jul-63	105.1	70.9	-37.7	105.9	92	13.1	0	0	10.9
Aug-63	75.6	80	0.4	106.3	75.6	0	0	0	7.7
Sep-63	44.2	65.8	18.3	124.6	44.2	0	0	0	5.1
Oct-63	35.1	18.3	-17.7	113.6	28.4	6.7	0	0	1.8
Nov-63	16.8	64.3	44.3	157.9	16.8	0	0	0	3.7
Dec-63	6.6	2.8	-3.8	154.9	5.8	0.8	0	0	0.2
Jan-64	8.5	45.7	9.3	164.3	8.5	0	27.2	0	0.8
Feb-64	8.7	0	-6.5	158.9	7.5	1.2	25	0	0.1
Mar-64	17.3	37.1	13.8	172.7	17.3	0	29.9	0	1.1
Apr-64	33.1	69.3	47.7	200	33.1	0	15	20.4	13.7
May-64	69.9	59.7	-5.7	194.3	69.9	0	7.5	0	8.1
Jun-64	89.3	33.8	-49.7	146.1	87.9	1.4	0	0	4.2
Jul-64	111.1	152.7	33.9	180	111.1	0	0	0	8.9
Aug-64	72.4	136.1	56.9	200	72.4	0	0	36.9	25.9
Sep-64	48.9	21.6	-28.3	171.7	48.9	0	0	0	10.6
Oct-64	25.9	23.1	-3.9	168.3	25.3	0.6	0	0	5.9
Nov-64	15.4	17	0.8	169.1	15.4	0	0	0	3.2
Dec-64	8.6	42.4	13.2	182.3	8.6	0	19.7	0	2.1
Jan-65	7.1	27.9	-3.1	179.5	6.9	0.3	43.4	0	0.7
Feb-65	8.9	42.2	5.9	185.4	8.9	0	70.4	0	0.7
Mar-65	14.6	3.3	-0.9	184.6	14.5	0.1	60	0	0.2
Apr-65	27.8	37.8	31.4	200	27.8	0	37	16	9.7
May-65	69	75.2	20.9	200	69	0	18.5	20.9	18.3
Jun-65	84.4	35.3	-41.6	158.4	84.4	0	9.2	0	9
Jul-65	87.3	58.7	-22.3	140.7	82.6	4.6	0	0	6.6
Aug-65	78.9	96.5	12.8	153.5	78.9	0	0	0	6.6
Sep-65	52.3	80.8	24.5	178	52.3	0	0	0	4.9
Oct-65	25.9	119.9	88	200	25.9	0	0	66	39.4
Nov-65	13.8	69.1	52.3	200	13.8	0	0	52.3	45.8
Dec-65	10	51.1	25	200	10	0	14.6	25	35.5

Jan-66	7	2.8	-6.3	193.7	7	0	16.7	0	17
Feb-66	9.5	20.6	0.1	193.8	9.5	0	27.4	0	8.8
Mar-66	19.2	36.1	17.5	200	19.2	0	25.5	11.3	11.1
Apr-66	30.5	29	9.2	200	30.5	0	13.4	9.2	11
May-66	52.5	48.8	0.5	200	52.5	0	6.7	0.5	7.5
Jun-66	93.2	101.3	9.7	200	93.2	0	0	9.7	12.4
Jul-66	109.1	40.4	-70.7	129.3	109.1	0	0	0	5.7
Aug-66	85	74.7	-14.1	120.2	80	5	0	0	5.6
Sep-66	45.6	87.9	37.9	158.1	45.6	0	0	0	5.3
Oct-66	26.9	52.3	22.8	180.9	26.9	0	0	0	3.1
Nov-66	15	103.4	83.5	200	15	0	0	64.4	37.4
Dec-66	8.2	41.4	10.7	200	8.2	0	21.7	10.7	22.3
Jan-67	9.2	9.9	0	200	9.2	0	22.1	0	11
Feb-67	7.3	16	-7.3	192.7	7.3	0	38.1	0	5.4
Mar-67	16.2	2.5	-5.7	187.2	16	0.2	30.1	0	2.8
Apr-67	33.9	69.9	47.5	200	33.9	0	15.1	34.7	22.2
May-67	49.1	42.7	-1	199	49.1	0	7.5	0	11.5
Jun-67	102.3	191.8	87.4	200	102.3	0	0	86.5	57.5
Jul-67	97.6	78.7	-22.8	177.2	97.6	0	0	0	27.9
Aug-67	76.5	111.8	29.7	200	76.5	0	0	6.9	21
Sep-67	45.9	75.9	26.2	200	45.9	0	0	26.2	24.6
Oct-67	27.5	99.8	67.3	200	27.5	0	0	67.3	49
Nov-67	12.3	34.3	20.8	200	12.3	0	0	20.8	33.6
Dec-67	9.1	72.1	32.9	200	9.1	0	28.4	32.9	34.4
Jan-68	6.5	16.5	-6.5	193.5	6.5	0	44.9	0	16.3
Feb-68	7.6	17	-7.6	186.1	7.4	0.2	61.9	0	8.2
Mar-68	19.6	27.2	23.4	200	19.6	0	45.2	9.5	9.8
Apr-68	38.6	38.9	20.9	200	38.6	0	22.6	20.9	16.8
May-68	55.2	92.7	44.2	200	55.2	0	11.3	44.2	34.1
Jun-68	89.8	62	-25.3	174.7	89.8	0	5.6	0	17.9
Jul-68	103.8	68.6	-33	145.9	99.6	4.2	0	0	10.8
Aug-68	84.5	150.4	58.4	200	84.5	0	0	4.3	13.4
Sep-68	56.7	125.5	62.5	200	56.7	0	0	62.5	40.5
Oct-68	31.6	64.8	30	200	31.6	0	0	30	35.3
Nov-68	13.7	76.7	53.1	200	13.7	0	6.6	53.1	45.8
Dec-68	7.6	8.6	-3.8	196.2	7.6	0	11.3	0	21.4
Jan-69	7.9	26.4	0.5	196.8	7.9	0	29	0	10.9
Feb-69	9.2	0	-5.9	191	9.1	0.1	25.8	0	5.3
Mar-69	15.7	40.4	11.6	200	15.7	0	38	2.6	4.8
Apr-69	36.3	117.3	94.1	200	36.3	0	19	94.1	54.9
May-69	61	84.1	28.4	200	61	0	9.5	28.4	42.9
Jun-69	83.4	85.6	7.4	200	83.4	0	0	7.4	27.4
Jul-69	100.6	56.1	-47.3	152.7	100.6	0	0	0	14.3
Aug-69	93.3	56.4	-39.7	122.3	83.9	9.4	0	0	8.6
Sep-69	52	15.7	-37.1	99.7	37.6	14.4	0	0	3.7
Oct-69	27.2	65.3	34.8	134.5	27.2	0	0	0	4.7
Nov-69	14.6	85.9	67.3	200	14.6	0	0	1.8	5.6
Dec-69	7.3	10.9	3.5	200	7.3	0	0	3.5	2.7
Jan-70	5.9	8.1	-5.9	194.1	5.9	0	8.1	0	1.3

Feb-70	8.3	1	0.8	194.9	8.3	0	0	0	0.6
Mar-70	14.9	26.4	-2.4	192.6	14.9	0.1	13.4	0	0.8
Apr-70	34.8	60.5	29.4	200	34.8	0	6.7	21.9	14.2
May-70	66.5	70.9	7.6	200	66.5	0	0	7.6	12.9
Jun-70	90.9	53.6	-40	160	90.9	0	0	0	7.4
Jul-70	108.4	90.7	-22.2	142.2	104	4.4	0	0	6.9
Aug-70	86.6	86.4	-4.5	139	85.3	1.3	0	0	5.5
Sep-70	53	110.7	52.2	191.2	53	0	0	0	6.1
Oct-70	30.2	101.1	65.8	200	30.2	0	0	57	33.9
Nov-70	15.1	47	29.7	200	15.1	0	0	29.7	31.5
Dec-70	7.5	20.8	-0.7	199.3	7.5	0	13.7	0	14.9
Jan-71	6.4	5.1	-6.4	193	6.3	0	18.8	0	7.3
Feb-71	9.4	20.6	0	192.9	9.4	0	29.8	0	3.9
Mar-71	14.7	4.8	-7.2	186	14.4	0.3	27.1	0	1.9
Apr-71	30.3	20.3	1.8	187.8	30.3	0	14.3	0	1.9
May-71	61	31	-24.4	164.9	59.5	1.5	7.1	0	2
Jun-71	98.6	81.5	-14	153.3	96.1	2.5	0	0	4.3
Jul-71	98.2	87.1	-15.4	141.5	94.6	3.6	0	0	4.5
Aug-71	81.9	97.5	10.7	152.2	81.9	0	0	0	4.9
Sep-71	58.5	21.8	-37.8	123.5	49.5	9	0	0	1.1
Oct-71	36.4	37.8	-0.5	123.2	36.2	0.2	0	0	1.9
Nov-71	14	18.5	3.7	126.9	14	0	0	0	0.8
Dec-71	9.6	70.9	36.1	163	9.6	0	23.2	0	1.9
Jan-72	7.7	15	-1.9	161.4	7.4	0.4	32.3	0	0.1
Feb-72	8	0	-7.1	155.7	6.6	1.4	31.4	0	0
Mar-72	13.9	53.6	10.7	166.3	13.9	0	59.8	0	0.8
Apr-72	27.5	39.6	32.4	198.7	27.5	0	37.8	0	1.7
May-72	68.6	56.1	3.6	200	68.6	0	18.9	2.4	4
Jun-72	81.8	109.5	31.6	200	81.8	0	9.5	31.6	21.9
Jul-72	105.1	36.8	-60.7	139.3	105.1	0	0	0	10
Aug-72	82.9	42.7	-42.4	109.8	70.1	12.9	0	0	6.2
Sep-72	53.6	50.5	-5.6	106.7	51.1	2.5	0	0	4.6
Oct-72	24	112.5	82.9	189.6	24	0	0	0	6.7
Nov-72	12.6	41.4	20.6	200	12.6	0	6.6	10.2	7.1
Dec-72	8.7	76.5	33.2	200	8.7	0	39.6	33.2	21
Jan-73	8.6	19.8	5.4	200	8.6	0	45.1	5.4	12.7
Feb-73	7.9	14.7	-6.2	193.8	7.9	0	58.1	0	6.2
Mar-73	23.3	82.8	78.6	200	23.3	0	35.2	72.4	43.1
Apr-73	36.1	70.4	48.4	200	36.1	0	17.6	48.4	47.4
May-73	58	98	43.9	200	58	0	8.8	43.9	48.8
Jun-73	100.4	78	-17.5	182.5	100.4	0	0	0	25.8
Jul-73	110.4	46	-66.7	121.6	104.6	5.9	0	0	13.3
Aug-73	99.9	115.8	10.1	131.7	99.9	0	0	0	11.3
Sep-73	52.3	50	-4.8	128.5	50.7	1.6	0	0	5.2
Oct-73	31.7	95.3	58.8	187.3	31.7	0	0	0	6.1
Nov-73	14.5	77.7	59.6	200	14.5	0	0	46.9	27.7
Dec-73	8.3	23.1	2.5	200	8.3	0	11.9	2.5	13.7
Jan-74	8.2	69.6	16.2	200	8.2	0	56.3	16.2	15.6
Feb-74	7.7	21.1	-7.2	192.8	7.7	0	76.9	0	7.4

Mar-74	17.1	36.3	26.9	200	17.1	0	68.2	19.7	14.5
Apr-74	37.2	104.1	95.8	200	37.2	0	34.1	95.8	59.9
May-74	55.5	106.2	62.4	200	55.5	0	17.1	62.4	63.8
Jun-74	90.9	64.8	-20.8	179.2	90.9	0	8.5	0	32.5
Jul-74	109.1	33.5	-68.7	117.6	101.9	7.2	0	0	16.3
Aug-74	91	96.5	0.7	118.3	91	0	0	0	12.1
Sep-74	48.3	51.1	0.3	118.5	48.3	0	0	0	6.2
Oct-74	26.4	31.8	3.9	122.4	26.4	0	0	0	3.4
Nov-74	14.7	85.1	66.4	188.8	14.7	0	0	0	4.9
Dec-74	9.8	3.3	-6.6	182.6	9.4	0.4	0	0	0.6
Jan-75	9.1	19.1	0.1	182.7	9.1	0	9.5	0	0.6
Feb-75	9.8	47.5	10.6	193.3	9.8	0	35.8	0	0.8
Mar-75	15.3	41.9	13.2	200	15.3	0	48.4	6.5	4.2
Apr-75	26.8	35.1	23	200	26.8	0	32.3	23	14.6
May-75	80.1	59.4	-7.5	192.5	80.1	0	16.2	0	9.5
Jun-75	99.8	66.5	-28.5	165	98.7	1.1	8.1	0	6.6
Jul-75	112.5	85.1	-23.6	145.6	108.4	4.1	0	0	5.9
Aug-75	88.2	117.9	23.8	169.3	88.2	0	0	0	6.7
Sep-75	45.6	65	16.1	185.4	45.6	0	0	0	3.7
Oct-75	30.2	28.4	-3.2	182.5	30	0.2	0	0	1.6
Nov-75	18	44.7	24.4	200	18	0	0	6.9	5.8
Dec-75	7.6	18.5	-1.2	198.8	7.6	0	11.8	0	2
Jan-76	6.3	3.6	-6.3	192.5	6.3	0	15.4	0	0.9
Feb-76	10.8	44.5	16	200	10.8	0	32.1	8.6	5.7
Mar-76	19	68.1	42.6	200	19	0	36.4	42.6	25.9
Apr-76	37.9	51.8	29.5	200	37.9	0	18.2	29.5	29.1
May-76	58.4	77.7	24.5	200	58.4	0	9.1	24.5	29.4
Jun-76	102.3	76.5	-20.5	179.5	102.3	0	0	0	16.6
Jul-76	101.9	112.8	5.3	184.7	101.9	0	0	0	12
Sep-76	49.5	116.8	61.5	200	49.5	0	0	46.2	32.1
Oct-76	23.3	42.7	17.3	200	23.3	0	0	17.3	23.9
Nov-76	11.5	17.8	5.8	200	11.5	0	0	5.8	14.3
Dec-76	6.6	1.3	-5.3	194.7	6.6	0	0	0	6.9
Jan-77	5.5	0	-5.5	189.4	5.4	0.1	0	0	3.4
Feb-77	8.8	16.8	-4.8	184.8	8.5	0.3	12.7	0	1.9
Mar-77	21	59.3	33.4	200	21	0	15.2	18.2	12.3
Apr-77	38.4	37.9	5.2	200	38.4	0	7.6	5.2	9.5
May-77	73.4	23.1	-43.8	156.2	73.4	0	0	0	5
Jun-77	85.5	73	-16.1	143.6	81.9	3.5	0	0	5.5
Jul-77	113.2	90.3	-27.4	123.9	105.5	7.7	0	0	5.5
Aug-77	82.4	164	73.4	197.3	82.4	0	0	0	8.7
Sep-77	51.7	142.9	84.1	200	51.7	0	0	81.3	48.1
Oct-77	26.5	86.8	55.9	200	26.5	0	0	55.9	52.8
Nov-77	14.9	70.3	52.1	200	14.9	0	0	52.1	53.6
Dec-77	7.8	26.6	2.4	200	7.8	0	16	2.4	26.7
Jan-78	6.6	25.9	-6.6	193.4	6.6	0	41.9	0	13.2
Feb-78	6.8	0	-6.8	186.8	6.5	0.2	41.9	0	6.6
Mar-78	14.5	43.2	11.3	198.2	14.5	0	58.6	0	4
Apr-78	29.6	48.8	42.9	200	29.6	0	32.6	41.1	24.5

May-78	67.3	100.2	44.2	200	67.3	0	16.3	44.2	38.2
Jun-78	91.5	64.8	-21.8	178.2	91.5	0	8.2	0	19.8
Jul-78	107.1	23.8	-76.3	110.2	98.8	8.3	0	0	9.5
Aug-78	89.3	153.8	56.8	167	89.3	0	0	0	11.8
Sep-78	49.8	152.2	94.8	200	49.8	0	0	61.8	40.6
Oct-78	27	45.2	15.9	200	27	0	0	15.9	26.7
Nov-78	14	46.6	30.6	200	14	0	0	30.6	29.5
Dec-78	8.6	20.4	1.9	200	8.6	0	9.5	1.9	15.1
Jan-79	6.9	4	-6.4	193.6	6.9	0	13	0	7.4
Feb-79	6.3	12.2	-6.3	187.4	6.1	0.2	25.2	0	3.7
Mar-79	20.2	71.4	46.4	200	20.2	0	27.3	33.9	21.4
Apr-79	31.5	64.6	43.5	200	31.5	0	13.6	43.5	34.4
May-79	61.7	84.2	25.1	200	61.7	0	6.8	25.1	32.3
Jun-79	92.6	78.4	-11.3	188.7	92.6	0	0	0	18
Jul-79	106.4	25	-82.7	110.7	101.7	4.7	0	0	8.3
Aug-79	80.9	89.2	3.8	114.5	80.9	0	0	0	8
Sep-79	51.3	37.4	-15.8	105.5	44.6	6.8	0	0	3.6
Oct-79	26.9	111.2	78.8	184.3	26.9	0	0	0	6.4
Nov-79	14.6	99.6	80.4	200	14.6	0	0	64.6	37.4
Dec-79	9.5	60.2	28.2	200	9.5	0	21	28.2	32
Jan-80	8	37.8	5.8	200	8	0	44.6	5.8	18.5
Feb-80	7.8	1	-7.2	192.8	7.8	0	45.1	0	9.1
Mar-80	16.1	43.4	19	200	16.1	0	52.3	11.8	11.5
Apr-80	34.3	109.3	95.7	200	34.3	0	26.2	95.7	58.5
May-80	69.9	34.2	-24.3	175.7	69.9	0	13.1	0	28.2
Jun-80	79.3	102	24.1	199.8	79.3	0	6.5	0	18.4
Jul-80	107.7	156.2	47.2	200	107.7	0	0	47	37.9
Aug-80	94.5	46	-50.8	149.2	94.5	0	0	0	17.4
Sep-80	49.5	86	32.2	181.5	49.5	0	0	0	11.8
Oct-80	23.6	66	39.1	200	23.6	0	0	20.6	17.4
Nov-80	12.9	33.8	19.6	200	12.9	0	0	19.6	18.1
Dec-80	6.8	29.2	-1.9	198.1	6.8	0	24.1	0	8.6
Jan-81	6	0	-6	192.2	5.9	0.1	24.1	0	4.2
Feb-81	11.4	35.7	15.5	200	11.4	0	32	7.7	6.8
Mar-81	18.2	16	2.9	200	18.2	0	26.4	2.9	4.9
Apr-81	36.8	43.6	17.8	200	36.8	0	13.2	17.8	13.3
May-81	59.8	60	3.8	200	59.8	0	6.6	3.8	10.5
Jun-81	94.4	101.8	8.9	200	94.4	0	0	8.9	13.3
Jul-81	108.4	115.4	1.2	200	108.4	0	0	1.2	10.5
Aug-81	84.5	136	44.7	200	84.5	0	0	44.7	31.5
Sep-81	49.5	88.8	34.9	200	49.5	0	0	34.9	34.2
Oct-81	24.2	70.6	42.9	200	24.2	0	0	42.9	39.9
Nov-81	14.3	53.8	37	200	14.3	0	0	37	39.1
Dec-81	8.7	4.6	-4.2	195.8	8.7	0	0	0	18.4
Jan-82	5.9	12.2	-5.9	190	5.8	0.1	12.2	0	9.2
Feb-82	8.2	0	-7.7	182.8	7.8	0.4	11.6	0	4.6
Mar-82	16.2	43	11.3	194.1	16.2	0	26.2	0	3.3
Apr-82	30.9	39	19	200	30.9	0	13.3	13.1	9.6
May-82	77.1	60.6	-12.9	187.1	77.1	0	6.7	0	6.9

Jun-82	80.8	132.6	51.8	200	80.8	0	0	38.9	28
Jul-82	109.1	83.8	-29.5	170.5	109.1	0	0	0	14.9
Aug-82	75.6	132.6	50.4	200	75.6	0	0	20.9	22.4
Sep-82	50.1	110.8	55.2	200	50.1	0	0	55.2	41
Oct-82	29.1	41.2	10	200	29.1	0	0	10	24.8
Nov-82	15	123.4	102.5	200	15	0	0	102.5	68.5
Dec-82	10.7	90	57	200	10.7	0	19.3	57	62.9
Jan-83	8.5	24.6	3.8	200	8.5	0	31.3	3.8	32.1
Feb-83	10.7	24.2	8.2	200	10.7	0	36.1	8.2	20.5
Mar-83	19.1	50	30.7	200	19.1	0	34.6	30.7	27
Apr-83	32.3	96.2	76.4	200	32.3	0	17.3	76.4	55.7
May-83	54.5	126.4	74.2	200	54.5	0	8.6	74.2	68.9
Jun-83	94.4	35	-52.5	147.5	94.4	0	0	0	33
Jul-83	118.2	75.4	-46.6	113.1	106	12.2	0	0	19.4
Aug-83	95.6	81.2	-18.5	102.7	87.6	8	0	0	11.9
Sep-83	57	43.4	-15.8	94.5	49.4	7.7	0	0	6.1
Oct-83	28.2	82	49.7	144.2	28.2	0	0	0	6.1
Nov-83	14.3	50.4	33.8	178	14.3	0	0	0	3.3
Dec-83	7.2	24.6	-0.9	177.2	7.1	0.1	18.1	0	0.7
Jan-84	6.5	0	-6.5	171.4	5.8	0.7	18.1	0	0.2
Feb-84	12	40.5	19.4	190.8	12	0	26	0	1.2
Mar-84	13.8	34.4	2.4	193.2	13.8	0	43.8	0	0.5
Apr-84	36.8	44.2	27.1	200	36.8	0	21.9	20.3	12.4
Jun-84	96.8	54.6	-33.9	166.1	96.8	0	10.9	0	7.8
Jul-84	104.4	49.4	-52	122.9	95.6	8.8	5.5	0	5
Aug-84	96.2	73.8	-20.7	110.2	88.3	8	0	0	5
Sep-84	46.8	86.7	35.6	145.7	46.8	0	0	0	5
Oct-84	30.6	49.6	16.5	162.3	30.6	0	0	0	2.8
Nov-84	14	76.2	58.9	200	14	0	0	21.2	14.1
Dec-84	10.2	63.2	34.3	200	10.2	0	16.8	34.3	24.5
Jan-85	6.8	0.8	-6.6	193.4	6.8	0	17.3	0	11.3
Feb-85	8.9	32.4	1.3	194.8	8.9	0	39.2	0	5.9
Mar-85	18.1	63.1	37.9	200	18.1	0	44.4	32.6	21
Apr-85	39.6	25	6.3	200	39.6	0	22.2	6.3	14
May-85	67.7	91.6	30.4	200	67.7	0	11.1	30.4	26.1
Jun-85	82.9	26.6	-52	148	82.9	0	5.6	0	12.1
Jul-85	105.1	59.6	-42.9	116.2	93.9	11.2	0	0	8.4
Aug-85	85	148.7	56.2	172.5	85	0	0	0	10.1
Sep-85	57.4	118.9	55.6	200	57.4	0	0	28	21.3
Oct-85	28.6	62.4	30.7	200	28.6	0	0	30.7	26.1
Nov-85	13.9	100.6	74.6	200	13.9	0	7.7	74.6	53.2
Dec-85	7.6	12.4	-2.4	197.6	7.6	0	14.8	0	24.6
Jan-86	7.9	10.2	-3.6	194.1	7.8	0	20.6	0	12.3
Feb-86	8.5	10.1	-5.4	188.9	8.3	0.2	27.5	0	6.2
Mar-86	19.5	40.4	21.2	200	19.5	0	25.8	10.1	9.5
Apr-86	39.4	57.5	28.2	200	39.4	0	12.9	28.2	21
May-86	74.3	72.1	0.6	200	74.3	0	6.5	0.6	13
Jun-86	86	106.9	22	200	86	0	0	22	21
Jul-86	114.6	122	1.3	200	114.6	0	0	1.3	14.6

Aug-86	81.4	145.6	56.9	200	81.4	0	0	56.9	40
Sep-86	51.3	218.9	156.6	200	51.3	0	0	156.6	105.6
Oct-86	27.7	65.6	34.6	200	27.7	0	0	34.6	67.9
Nov-86	12.8	18.4	4.9	200	12.8	0	0	4.9	35.5
Dec-86	9.3	9.2	-0.4	199.6	9.3	0	0	0	17.6
Jan-87	8.2	2.4	-5.8	193.8	8.2	0	0	0	8.7
Feb-87	9.1	8	-1.1	192.7	9	0	0	0	4.4
Mar-87	20.2	41.7	13.2	200	20.2	0	6.7	5.9	6.7
Apr-87	41.4	80	41.3	200	41.4	0	0	41.3	27.2
May-87	73.9	33.6	-41.9	158.1	73.9	0	0	0	13.3
Jun-87	101	62	-42.1	124.7	92.2	8.8	0	0	8.9
Jul-87	124.2	95.1	-33.9	103.6	111.5	12.8	0	0	7.7
Aug-87	88.2	91.6	-1.2	103	87.7	0.6	0	0	6
Sep-87	54	68.5	11.1	114.1	54	0	0	0	4.2
Oct-87	24.8	79	50.3	164.4	24.8	0	0	0	4.3
Nov-87	14.3	70.2	52.8	200	14.3	0	0	17.2	11.9
Dec-87	9.8	23.3	12.8	200	9.8	0	0	12.8	11.5
Jan-88	7.9	39.2	3.2	200	7.9	0	27.7	3.2	7.4
Feb-88	8.4	21	-3.5	196.5	8.4	0	43.7	0	3.6
Mar-88	17.4	25.4	11.6	200	17.4	0	39.3	8.1	6.5
Apr-88	34.3	58.9	41.3	200	34.3	0	19.7	41.3	26.5
May-88	72.5	52.4	-12.9	187.1	72.5	0	9.8	0	14.4
Jun-88	92.6	48.2	-37	152.5	90.3	2.4	0	0	8.3
Jul-88	123.5	61.2	-65.3	102.7	108	15.5	0	0	6
Aug-88	97.4	73	-28.1	88.2	83.8	13.7	0	0	5.1
Sep-88	51.3	106.1	49.5	137.7	51.3	0	0	0	6
Oct-88	23.9	91.3	62.9	200	23.9	0	0	0.6	5.2
Nov-88	15.5	98.5	78.2	200	15.5	0	0	78.2	44.3
Dec-88	8.4	23.2	2.8	200	8.4	0	11.6	2.8	21.5
Jan-89	9.6	33	11	200	9.6	0	23.3	11	16.8
Feb-89	8.2	2	-6.9	193.1	8.2	0	24	0	8
Mar-89	15.6	39	10.2	200	15.6	0	36.3	3.3	6.5
Apr-89	31.5	44.7	29.1	200	31.5	0	18.2	29.1	19.6
May-89	64.5	106.2	45.5	200	64.5	0	9.1	45.5	36.8
Jun-89	97.4	132	37.1	200	97.4	0	0	37.1	40.9
Jul-89	112.5	26.2	-87.6	112.4	112.5	0	0	0	18.5
Aug-89	86.6	100.6	9	121.3	86.6	0	0	0	13.6
Sep-89	51.7	39.7	-13.9	112.9	46.2	5.5	0	0	6.3
Oct-89	28.6	71.6	39.4	152.3	28.6	0	0	0	5.7
Nov-89	12.8	140.6	101.5	200	12.8	0	21	53.8	33.3
Dec-89	5.5	2	-5.5	194.5	5.5	0	23	0	14
Jan-90	10.3	37	18.9	200	10.3	0	29.8	13.4	14.7
Feb-90	10	26.2	6.1	200	10	0	39.5	6.1	10.3
Mar-90	19.7	52.4	35.3	200	19.7	0	35	35.3	24.5
Apr-90	39.9	46.6	21.9	200	39.9	0	17.5	21.9	24.6
May-90	60.2	123.4	65.8	200	60.2	0	8.8	65.8	50.2
Jun-90	96.8	109.8	16.3	200	96.8	0	0	16.3	35.7
Jul-90	107.1	80.4	-30.7	169.3	107.1	0	0	0	19.1
Aug-90	88.8	88.1	-5.1	165	88	0.8	0	0	11.9

Sep-90	51.3	90.9	35	200	51.3	0	0	0	8.3
Oct-90	27.5	134.4	100.2	200	27.5	0	0	100.2	58.7
Nov-90	15.7	73.5	54.1	200	15.7	0	0	54.1	56.7
Dec-90	9.6	70	35.5	200	9.6	0	22.9	35.5	46.2
Jan-91	7.6	3.8	-4.9	195.1	7.6	0	24.1	0	22.2
Feb-91	10.8	29.8	10.1	200	10.8	0	32.3	5.1	14.3
Mar-91	19.9	97.6	68.5	200	19.9	0	38	68.5	44.6
Apr-91	39.9	133.6	106.1	200	39.9	0	19	106.1	80.2
May-91	81.6	65.6	-9.8	190.2	81.6	0	9.5	0	40.1
Jun-91	104.9	44.1	-53.5	139.4	102.3	2.6	0	0	20.6
Jul-91	111.8	93	-23.5	123	104.7	7.1	0	0	13.8
Aug-91	95.1	76.6	-22.3	109.3	86.5	8.6	0	0	8.4
Sep-91	48.9	51.1	-0.3	109.1	48.7	0.1	0	0	4.9
Oct-91	30.6	100.2	64.6	173.7	30.6	0	0	0	6.2
Nov-91	13.2	48.6	33.4	200	13.2	0	0	7.1	6.1
Dec-91	8.8	17.5	8.3	200	8.8	0	0	8.3	6.6
Jan-92	8.6	9	0.3	200	8.6	0	0	0.3	3.4
Feb-92	10	33.2	4.1	200	10	0	18.5	4.1	4.2
Mar-92	16.5	45.6	15.3	200	16.5	0	31.2	15.3	10.6
Apr-92	32.5	107.2	85	200	32.5	0	15.6	85	52.6
May-92	63.3	85.6	25.9	200	63.3	0	7.8	25.9	40.8
Jun-92	81.8	55.4	-21.4	178.6	81.8	0	0	0	21
Jul-92	90.6	126.6	29.7	200	90.6	0	0	8.3	19.6
Aug-92	76.5	173.8	88.6	200	76.5	0	0	88.6	59.6
Sep-92	50.4	91.4	36.4	200	50.4	0	0	36.4	48.3
Oct-92	24.6	46.6	19.6	200	24.6	0	0	19.6	34
Nov-92	13.5	152.2	117	200	13.5	0	15.4	117	80.6
Dec-92	9.3	23.6	9	200	9.3	0	20.1	9	42.3
Jan-93	8.5	39.4	9.9	200	8.5	0	40.5	9.9	26.4
Feb-93	7.2	0	-7.2	192.8	7.2	0	40.5	0	12.9
Mar-93	15.5	0.2	-6.9	186.2	15.2	0.2	32	0	6.5
Apr-93	35	72.1	49.5	200	35	0	16	35.7	24.7
May-93	61.7	61.6	4.8	200	61.7	0	8	4.8	16
Jun-93	87.6	111.4	26.2	200	87.6	0	0	26.2	25.2
Jul-93	111.8	80.4	-35.4	164.6	111.8	0	0	0	13.8
Aug-93	93.3	54.4	-41.6	130.3	85.9	7.4	0	0	7.6
Sep-93	44.5	68.8	20.8	151.2	44.5	0	0	0	5.9
Oct-93	25.9	70.3	40.9	192.1	25.9	0	0	0	4.7
Nov-93	13.5	58.4	36.6	200	13.5	0	5.9	28.6	17.3
Dec-93	8.7	12	-1.2	198.8	8.7	0	10.2	0	7.7
Jan-94	5.2	28.5	-5.2	193.7	5.1	0	38.7	0	3.7
Feb-94	7.3	0	-7.3	186.6	7.1	0.2	38.7	0	1.9
Mar-94	16.9	12.4	1	187.6	16.9	0	32.8	0	1.3
Apr-94	36.5	80.4	56.2	200	36.5	0	16.4	43.9	26.4
May-94	58.7	107.6	51.7	200	58.7	0	8.2	51.7	42.4
Jun-94	98	49.4	-42.8	157.2	98	0	0	0	21
Jul-94	111.1	54.7	-59.2	110.7	98.5	12.7	0	0	12
Aug-94	80.4	50	-32.9	92.5	65.7	14.7	0	0	7.1
Sep-94	51	63	8.8	101.3	51	0	0	0	5.5

Oct-94	28.7	59.5	27.8	129.1	28.7	0	0	0	4.1
Nov-94	16	59.2	40.2	169.3	16	0	0	0	3.5
Dec-94	10	18.4	7.9	177.1	10	0	0	0	0.8
Jan-95	9.3	69.9	26.1	200	9.3	0	33.1	3.2	3.2
Feb-95	7.9	6	-6.9	193.1	7.9	0	38.1	0	0.9
Mar-95	20.1	1.4	-4.9	188.3	19.9	0.2	24.3	0	0.5
Apr-95	29.1	90	63.9	200	29.1	0	17.2	52.3	30.5
May-95	63.7	76.2	17.3	200	63.7	0	8.6	17.3	25.7
Jun-95	103.6	79.8	-19.2	180.8	103.6	0	0	0	14.9
Jul-95	114.6	65.9	-52	133.8	109.6	5	0	0	8.8
Aug-95	98.7	62.2	-39.6	107.3	85.6	13.1	0	0	5.8
Sep-95	47.1	45.4	-3.9	105.2	45.2	1.8	0	0	3.6
Oct-95	31	146.3	108	200	31	0	0	13.2	14.6
Nov-95	11.7	105.2	65.6	200	11.7	0	24.5	65.6	39.9
Dec-95	7.3	0	-4.7	195.3	7.3	0	21.8	0	18.2
Jan-96	7.2	50.8	0.3	195.6	7.2	0	65	0	9.3
Feb-96	8.8	33.4	5.2	200	8.8	0	84	0.8	5.3
Mar-96	15.3	4.8	4.2	200	15.3	0	69.2	4.2	4.7
Apr-96	29.8	80.8	77.7	200	29.8	0	38.7	77.7	45
May-96	59.5	93	48.2	200	59.5	0	19.3	48.2	49.3
Jun-96	98.6	149.2	52.8	200	98.6	0	9.7	52.8	56.2
Jul-96	100.6	112.4	15.8	200	100.6	0	0	15.8	37.9
Aug-96	90.5	52	-41.1	158.9	90.5	0	0	0	18.7
Sep-96	52.3	155.1	95	200	52.3	0	0	54	42.8
Oct-96	27.9	65.2	34.1	200	27.9	0	0	34.1	37.8
Nov-96	12.1	33.6	13.6	200	12.1	0	6.8	13.6	25.2
Dec-96	10.1	63.2	35.7	200	10.1	0	22.3	35.7	31.8
Jan-97	7.3	25.5	-1.7	198.3	7.3	0	42.1	0	15.1
Feb-97	10.4	55.6	23.9	200	10.4	0	62.4	22.2	19.6
Mar-97	16.5	39	22.2	200	16.5	0	61.7	22.2	21.4
Apr-97	32.7	26.6	23.4	200	32.7	0	30.8	23.4	23.2
May-97	50.9	90.8	50.8	200	50.9	0	15.4	50.8	40.9
Jun-97	105.5	79.7	-22.1	177.9	105.5	0	7.7	0	22.1
Jul-97	105.1	58.3	-42	140.5	100.5	4.6	0	0	12
Aug-97	79.4	72.5	-10.5	133.1	76.3	3.1	0	0	8.2
Sep-97	52.3	63.7	8.2	141.3	52.3	0	0	0	5.5
Oct-97	27.5	31.6	2.5	143.8	27.5	0	0	0	2.7
Nov-97	13.1	32.6	18.2	162.1	13.1	0	0	0	1.9
Dec-97	9.6	13	3.1	165.1	9.6	0	0	0	0.6
Jan-98	9.4	71.2	27.3	192.4	9.4	0	33.1	0	1.6
Feb-98	12.3	30.8	18	200	12.3	0	32.7	10.4	6.2
Mar-98	19.7	71.8	48	200	19.7	0	34.2	48	29.2
Apr-98	38.2	39.2	16.2	200	38.2	0	17.1	16.2	23.4
May-98	83.6	56.7	-21.2	178.8	83.6	0	8.6	0	13.5
Jun-98	96.2	57	-33.4	148.9	92.6	3.5	0	0	8.2
Jul-98	107.7	47.8	-62.3	102.5	91.8	15.9	0	0	5.1
Aug-98	92.2	96.4	-0.6	102.2	91.9	0.3	0	0	6.2
Sep-98	55.7	44	-13.9	95.1	48.9	6.8	0	0	2.9
Oct-98	28.9	13.6	-16	87.5	20.5	8.4	0	0	1

Nov-98	14.9	40.6	23.8	111.3	14.9	0	0	0	2.1
Jan-99	7.2	37	-2.5	109.9	6.1	1.1	32.1	0	0.3
Jul-99	128.2	63.4	-51.9	81.4	104.8	23.4	16.1	0	3.2
Aug-99	83.4	70.7	-8.2	78.1	78.6	4.9	8	0	3.6
Sep-99	56	71.6	20.1	98.1	56	0	0	0	3.6
Oct-99	27.9	63.1	32.1	130.2	27.9	0	0	0	3.2
Nov-99	16.2	75.4	55.4	185.6	16.2	0	0	0	3.8
Dec-99	9.6	42	17.2	200	9.6	0	14	2.8	2.6
Jan-00	8	30.6	2.5	200	8	0	33.8	2.5	2.3
Feb-00	11	25	10.1	200	11	0	37.2	10.1	6.6
Mar-00	23.3	35.1	25.6	200	23.3	0	21.7	25.6	17.5
Apr-00	33.9	56	30.1	200	33.9	0	10.8	30.1	25.8
May-00	69.9	164.9	92.2	200	69.9	0	5.4	92.2	65.8
Jun-00	96.2	219	117.3	200	96.2	0	0	117.3	98.4
Jul-00	98.8	91.2	-12.1	187.9	98.8	0	0	0	48.3
Aug-00	85	68.4	-20	169	83.8	1.2	0	0	25.3
Sep-00	52.3	110.6	52.8	200	52.3	0	0	21.8	27.4
Oct-00	31.4	29.6	-3.2	196.8	31.4	0	0	0	12.4
Nov-00	13.9	51.4	35.3	200	13.9	0	0	32	23.7
Dec-00	6.6	0	-6.6	193.4	6.6	0	0	0	10.7
Jan-01	8.6	0	-8.6	185.1	8.3	0.3	0	0	5.4
Feb-01	9.9	34	4	189.1	9.9	0	19.6	0	3.2
Mar-01	17.1	6	-8	181.6	16.7	0.4	16.3	0	1.5
Apr-01	37.7	40	8.5	190	37.7	0	8.1	0	2.7
May-01	70.7	79.2	12.7	200	70.7	0	0	2.7	5.6
Jun-01	96.8	94.4	-7.1	192.9	96.8	0	0	0	5.6
Jul-01	101.9	73.6	-32	162.1	100.8	1.1	0	0	4.1
Aug-01	99.3	48.6	-53.1	119.1	89.2	10.1	0	0	2.6
Sep-01	52.3	84.4	27.9	146.9	52.3	0	0	0	4.3
Oct-01	28.9	147.9	111.6	200	28.9	0	0	58.5	36.7
Nov-01	17.9	85.6	63.4	200	17.9	0	0	63.4	50.6
Dec-01	11	20	8.2	200	11	0	0	8.2	28
Jan-02	10.4	1	-9.4	190.6	10.4	0	0	0	13.7
Feb-02	11.3	29.8	5.9	196.5	11.3	0	12	0	7.5
Mar-02	18.5	38.1	12.8	200	18.5	0	17.5	9.3	9.3
Apr-02	36.8	102.5	69.4	200	36.8	0	8.8	69.4	43.8
May-02	55.5	111.4	59	200	55.5	0	0	59	54.4
Jun-02	98	74.8	-26.9	173.1	98	0	0	0	28.2
Jul-02	125	66.6	-61.8	119.7	116.7	8.3	0	0	15.5
Aug-02	94.5	35	-61.2	83	69.9	24.6	0	0	7.9
Sep-02	63.4	52.5	-13.5	77.4	55.5	7.9	0	0	5.7
Oct-02	25.9	78	48.2	125.6	25.9	0	0	0	5.4
Nov-02	13.3	30	15.5	141.1	13.3	0	0	0	2
Dec-02	8.9	11	1.8	142.9	8.9	0	0	0	0.6
Jan-03	6.6	0	-6.6	138.2	4.7	1.9	0	0	0.2
Feb-03	7.7	13	-7.4	133.1	5.4	2.3	12.7	0	0.1
Mar-03	17.6	25.8	3.4	136.4	17.6	0	16.7	0	0.8
Apr-03	32.3	24.6	-0.5	136.1	32.1	0.2	8.4	0	1.3
May-03	61.3	95.6	37.9	173.9	61.3	0	0	0	4.8

Jun-03	95	77.3	-21.5	155.2	92.2	2.8	0	0	3.9
Jul-03	109.1	38.8	-72.2	99.2	92.9	16.2	0	0	1.9
Aug-03	95.1	99.9	-0.1	99.1	95	0.1	0	0	5
Sep-03	53.3	107.8	49.1	148.2	53.3	0	0	0	5.4
Oct-03	26.4	94.6	63.5	200	26.4	0	0	11.7	10.6
Nov-03	15.5	94.4	74.3	200	15.5	0	0	74.3	44.7
Dec-03	9.7	45.6	20.3	200	9.7	0	14.3	20.3	31.5
Jan-04	6.2	9.2	-6.2	193.8	6.2	0	23.5	0	15.1
Feb-04	9.8	1	-5.8	188.2	9.6	0.2	20.5	0	7.6
Mar-04	20	98	65.1	200	20	0	29.9	53.3	34
Apr-04	34.8	66.3	43.2	200	34.8	0	15	43.2	40.1
May-04	64.5	117	54.2	200	64.5	0	7.5	54.2	51.3
Jun-04	89.3	57.5	-27.2	172.8	89.3	0	0	0	25.6
Jul-04	104.4	116.7	6.4	179.3	104.4	0	0	0	17.2
Aug-04	78.9	60.8	-21.2	160.3	76.7	2.2	0	0	8.7
Sep-04	57.8	39.7	-20	144.2	53.8	4	0	0	4.8
Oct-04	28.7	58.4	26.7	171	28.7	0	0	0	4.3
Nov-04	15.2	63.9	45.6	200	15.2	0	0	16.6	12.1
Dec-04	8	33.5	6	200	8	0	19	6	8
Jan-05	7.1	29	-3.3	196.7	7.1	0	44.1	0	3.8
Feb-05	9.6	31.2	8.3	200	9.6	0	56.9	5	4.8
Mar-05	16.1	14	5.1	200	16.1	0	49.4	5.1	5.1
Apr-05	35.4	57.1	43.5	200	35.4	0	24.7	43.5	27
May-05	56.2	47.2	1	200	56.2	0	12.3	1	14.9
Jun-05	118.7	32.3	-81.9	118.1	118.7	0	6.2	0	7.9
Jul-05	121.2	141.7	19.6	137.7	121.2	0	0	0	10.2
Aug-05	95.6	148.3	45.2	183	95.6	0	0	0	9
Sep-05	59.2	76.6	13.6	196.5	59.2	0	0	0	4.6
Oct-05	30.4	51	18.1	200	30.4	0	0	14.6	10.2
Nov-05	15.5	95.9	75.7	200	15.5	0	0	75.7	46.4
Dec-05	8.1	23.3	2.1	200	8.1	0	12.6	2.1	22.3
Jan-06	10.8	79.3	46.7	200	10.8	0	32.1	46.7	36.6
Feb-06	9.5	36	7.3	200	9.5	0	50.9	7.3	21.3
Mar-06	18.8	59.9	41.9	200	18.8	0	48.2	41.9	33.3
Apr-06	37.5	93.6	75.6	200	37.5	0	24.1	75.6	58.1
May-06	68.6	106.1	44.3	200	68.6	0	12	44.3	54.2
Jun-06	99.2	53.9	-42	158	99.2	0	6	0	27.1
Jul-06	122.7	100.4	-21.3	141.2	118.2	4.5	0	0	17.2
Aug-06	90.5	52.6	-40.5	112.6	78.6	11.9	0	0	8.7
Sep-06	49.8	163.3	105.4	200	49.8	0	0	18	20.2
Oct-06	26.9	120.2	87.3	200	26.9	0	0	87.3	55.7
Nov-06	16.3	50.8	31.9	200	16.3	0	0	31.9	43.3
Dec-06	11.6	36.6	23.6	200	11.6	0	0	23.6	33.6
	529	725	163	2141	516	13	142	175	207