

S:\p\2020\20717121\Drawings\EPF1_EPF1_17121.dwg, ESC-2, 2026-04-17 13:18:08 AM



KEY PLAN
N.T.S.

LEGEND:

- +301.08
— 188.5 —
- EXISTING ELEVATION
○ EXISTING CONTOUR
□ STORM MANHOLE
□ CATCHBASIN
BH7 BOREHOLE LOCATION
TP-4 TEST PIT LOCATION
— STRUCTURAL ENVELOPE
— ENVIRONMENTAL PROTECTION
— REFORESTED / PROTECTION AREA
--- SILT FENCE
--- CONSTRUCTION FENCE
◇ ROCK CHECK DAM

TOWN OF CALEDON
PLANNING
RECEIVED
May 27, 2026

NOTE:
THIS PLAN HAS BEEN PREPARED IN CONJUNCTION WITH THE FUNCTIONAL SERVICING REPORT TO DEMONSTRATE FEASIBILITY OF THE PROPOSED DEVELOPMENT IN CONJUNCTION WITH THE DRAFT PLAN OF SUBDIVISION APPLICATION. DETAILED DESIGNS WILL BE PREPARED AT THE DETAILED SUBDIVISION ENGINEERING DESIGN STAGE.

BENCHMARK NOTE:
ELEVATIONS ARE BASED ON GPS OBSERVATIONS TO PERMANENT REFERENCE STATIONS IN THE NAD83 (CSRS-2010) COORDINATE SYSTEM WITH HEIGHTS CONVERTED TO ORTHOMETRIC ELEVATIONS ON THE CGVD28 DATUM (1979 ADJUSTMENT) WITH GEOID MODEL HTV2.0, AS SUPPLIED BY NATURAL RESOURCES CANADA.

SURVEYOR: VAN HARTEN LAND SURVEYORS DATE: MARCH 13, 2026

METRIC:
DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METERS AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

NO.	DATE	REVISIONS	BY
2	APR.17, 2026	AS PER TOWN AND REGION COMMENTS	D.G.
1	FEB.14, 2024	UPDATED BOUNDARY SURVEY	D.G.

PRELIMINARY

VALDOR ENGINEERING INC.
Consulting Engineers - Project Managers
571 Chesko Road, Unit 4, 2nd Floor, Woodbridge, Ontario, L4L 6A2
TEL: (905) 844-4704 FAX: (905) 844-4704
E-MAIL: info@valdor-engineering.com
www.valdor-engineering.com


AMELIA STREET SUBDIVISION
COMMUNITY OF ALTON
TOWN OF CALEDON
REGION OF PEEL
FILE NUMBER: 21T-24001C

EROSION AND SEDIMENT
CONTROL NOTES &
DETAILS

SCALE: 1:500	DATE OF DWG. APR. 11, 2022	PROJECT NO. 17121
DRAWN BY: D.N.Z.	DRAWING NO. ESC-2	
CHKD BY: D.A.G.		

EROSION & SEDIMENT CONTROL NOTES

1. THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO PREVENT SEDIMENT RELEASES TO THE NATURAL ENVIRONMENT.
2. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED AND IN PROPER WORKING ORDER PRIOR TO THE COMMENCEMENT OF EARTHWORKS, THE EXACT LOCATION TO BE DETERMINED IN THE FIELD.
3. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE ROUTINELY INSPECTED AND MAINTAINED IN PROPER WORKING ORDER AND CLEANED PERIODICALLY.
4. ALL CONSTRUCTION VEHICLES SHALL EXIT THE SITE VIA THE TEMPORARY CONSTRUCTION ACCESS.
5. HYDROSEEDING TO BE APPLIED BY AN APPROVED CONTRACTOR. SEED MIX TO BE OBTAINED FROM LOCAL SEED SOURCE.
6. MONITORING OF THE GERMINATION OF THE HYDROSEED IS REQUIRED TO IDENTIFY ANY BARE AREAS THAT MAY RESULT. CONTRACTOR TO RE-SOW ALL BARE AREAS TO ENSURE SURFACES ARE ADEQUATELY STABILIZED.
7. ALL AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RESTORED TO THEIR ORIGINAL CONDITION OR BETTER TO THE SATISFACTION OF THE MUNICIPALITY AND NVCA. DISTURBED AREAS TO BE STABILIZED AS DIRECTED BY THE CONSULTANT ENGINEER AND TO THE SATISFACTION OF THE MUNICIPALITY IF LEFT UN-WORKED WITHIN 30 DAYS.
8. CONTRACTOR TO CLEAN AND MAINTAIN THE EXISTING ROADS ON A REGULAR BASIS FREE FROM DIRT AND MUD.



NOTE:

1. MUD MAT TO BE INSTALLED AT THE TEMPORARY CONSTRUCTION ACCESS LOCATION.
2. GRANULAR MATERIAL TO BE PERIODICALLY REPLACED AS IT BECOMES CONTAMINATED

MUD MAT DETAIL

N.T.S.

