

SPECIFICATIONS continued from previous panel

C. BED PREPARATION

i) The Contractor shall scarify the sides and bottom of excavated tree pits and shrub beds prior to backfilling. Due to the heavy clay soil in the Bolton area, tree and planting beds shall be backfilled to the specified depths with:

2 Parts "triple mix," delivered to the site, to be well-mixed with . . .

1 Part local topsoil (viz., subdivision topsoil that has been removed and stockpiled.) If topsoil is unavailable, topsoil with clay content shall be imported and mixed with triple mix.

ii) Tree pits shall be constructed with saucers and mulch as detailed.

D. TOPSOIL AND FINE GRADING

i) The Contractor shall place 100mm of rich topsoil on approved subgrades. Topsoil shall be imported when insufficient amounts are available on site.

ii) Minor grade deficiencies and irregularities shall be eliminated prior to seeding.

E. HYDROSEEDING

i) The Contractor shall apply 2280 kg/ha fibre mulch over the newly seeded area to form a uniform, blotter-like ground cover that allows the absorption and percolation of water.

ii) The area seeded in a single day shall not exceed the area that can be mulched that same day.

iii) The Contractor shall apply the specified seed mixture using accepted industry methods for hydroseeding and at rates recommended by the seed supplier. The type and rate of fertilizer application shall be as recommended in the topsoil test report for the particular area being seeded.

F. PRELIMINARY ACCEPTANCE

i) When landscaping is completed, the Consulting Landscape Architect shall submit a Certificate of Completion for Preliminary Acceptance to the Town of Caledon certifying that all landscape works have been completed in accordance with the approved plans.

ii) Upon receipt of the Certificate of Completion, the Town Staff will conduct a preliminary inspection of the site and, provided that the works are in satisfactory condition, will grant preliminary acceptance of the landscaping.

specifications continued on next panel . . .

TOWN OF CALEDON					APR'D: C.C.	DATE: JUNE 08
NATURALIZATION SPECIFICATIONS STANDARD NOTES PART 2		2	STANDARD No. 716 NOW 705	APR 19	DRAWN: abal	SCALE: NTS
		1	STANDARD No. 1175.02 NOW 716	JUNE 08	STANDARD No. 705	
NO.	REVISION	APR'D	DATE			